



Document Control No.: 4200-22-AEDP

**FINAL
SITE INSPECTION PRIORITIZATION REPORT
COMMERCIAL ENVELOPE MFG. CO., INC.
DEER PARK, NEW YORK**

CERCLIS ID No.: NYD981184138

Volume 1 of 2

16 September 1994

Work Order No.: 04200-022-081-0006

Prepared for:

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

Prepared by:

ROY F. WESTON, INC.
Raritan Plaza I
4th Floor
Raritan Center
Edison, New Jersey 08837

203018





Document Control No.: 4200-22-AEDP


FINAL
SITE INSPECTION PRIORITIZATION REPORT
COMMERCIAL ENVELOPE MFG. CO., INC.
DEER PARK, NEW YORK

CERCLIS ID No.: NYD981184138
Work Assignment No.: 022-2JZZ
Work Order No.: 04200-022-081-0006


Submitted by:

ROY F. WESTON, INC.
Raritan Plaza I - 4th Floor
Raritan Center
Edison, New Jersey 08837


WESTON/ARCS - Reviewed and Approved


Diane Donovan Minsavage
Task Manager


9/16/94
Date


Thomas A. Varner
Site Assessment Manager

9/19/94
Date


Dennis J. Foerter, CHMM
Quality Assurance Representative

9/16/94
Date


Martin J. O'Neill, CIH
Project Manager

9/19/94
Date

GENERAL DESCRIPTION AND SITE HISTORY

The Commercial Envelope Mfg. Co., Inc. (hereafter referred to as CEM) site (CERCLIS ID No. NYD981184138) is located at 900 Grand Boulevard in the Village of Deer Park, Babylon, Suffolk County, New York (Ref. Nos. 1; 2; 10). CEM also operates under the name Business Envelope Manufacturers Inc. (Ref. Nos. 2; 20, p. 26). CEM is an active envelope printing and manufacturing facility which has been located at the 7-acre site since 1977. ELM Freight Handling/ELM Public Warehouse and Distributing operates a warehouse out of a separate building on site. Alwin Seal, Incorporated, a producer of door frames and steel fencing, operated at the site from 1973 until 1977 (Ref. Nos. 19, p. 78; 20, 202). The property is currently owned by MAS Boulevard Associates (Ref. No. 9). Numerous parties have held title to the site since 1977 (Ref. No. 20, pp. 201-203). The site is located in an area primarily occupied by light industrial and commercial businesses. CEM is located on the southern side of Grand Boulevard and is bordered to the south, west, and east by Burt Drive, Innovation, Inc., and Art Marlin, respectively (Ref. No. 2).

The Suffolk County Department of Health Services (SCDHS) has conducted numerous inspections at CEM since January 1981. The SCDHS investigated a spill of between 1,937 and 5,835 gallons of dark purple liquid which occurred on 15 January 1981 (Ref. No. 20, pp. 92-94). The affected area was reported to have been excavated to a depth of 3 feet below the ground surface by Art Weiner-Earth Moving on 27 February 1981 (Ref. No. 20, p. 97). Subsequent inspections at CEM revealed various spills and reports of colored liquids bubbling up through the ground surface (Ref. Nos. 3, p. 8; 5, p. 4; 19, pp. 101, 104; 20, p. 110).

CEM produces approximately 750 gallons of wastewater per day that contains inks, glues and solvents. CEM operates an on-site wastewater incinerator. Prior to incineration, wastewater is stored on site in a 2,000-gallon steel aboveground storage tank located within the main building until a sufficient quantity has been collected. This storage tank was installed in 1983 (Ref. Nos. 6; 19, pp. 14, 80; 21). Prior to the installation of the aboveground tank, wastewater had been collected in three underground storage tanks located east of the building on site. SCDHS and CEM signed an Order on Consent in October 1982 requiring CEM to cease their (unspecified) unpermitted discharge of toxic and hazardous substances and to test the three subsurface holding tanks for leaks (Ref. Nos. 19, p. 109; 20, pp. 211-215).

Subsequently, the SCDHS discovered that CEM was also discharging industrial wastewater into two subsurface leaching pools. On 9 July 1985, the Suffolk County District Attorney's Office of Special Investigation served a search warrant to CEM. The search, which was conducted with the SCDHS, uncovered a third leaching pool at the site (Ref. No. 20, pp. 100-102). An Order on Consent requiring CEM to properly dispose of liquid and sludge contained in the leaching pools was prepared by SCDHS on 12 November 1985; however, this order was not

signed (Ref. No. 20, pp. 217-221). On 30 January 1986, CEM pleaded guilty to one felony count of Unlawful Discharge of Hazardous Waste in the Second Degree and 100 violations of the Suffolk County Sanitary Code. As a condition of the plea offer, CEM agreed to sign an Order on Consent requiring them to conduct a field investigation and clean up the site (Ref. No. 20, p. 205). The three leaching pools were pumped out and filled with clean sand. The sludge removed from the leaching pools was reportedly disposed of at a licensed facility; the wastewater was incinerated. The wastes were removed from the underground storage tanks. The wastewater from the tanks was collected and stored on site in 180 55-gallon drums. The sludge from the underground storage tanks was reportedly disposed of at a treatment, storage and disposal facility. The underground storage tanks were then filled with concrete and abandoned in place (Ref. Nos. 6, pp. 30, 31; 19, pp. 4, 60, 61, 70; 20, pp. 103, 117). Additionally, there are two 10,000-gallon underground storage tanks containing fuel oil and gasoline at the site. Approximately 9,300 gallons of fuel oil were discharged into an on-site observation well in January 1986 (Ref. Nos. 19, pp. 18, 78, 109). Petroleum products are excluded under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA); therefore, these two tanks and the fuel oil discharge will not be included in this evaluation.

Waste sources at CEM include the underground storage tanks, the subsurface leaching pools and an area of contaminated soil. The underground storage tanks were used to contain CEM's wastewater prior to incineration from 1977 until 1983. The three tanks have a combined capacity of 7,000 gallons (Ref. Nos. 19, p. 109; 20, p. 117). A representative of SCDHS reported the presence of blue and black deposits along a sidewall of the excavation during the tank abandonment (Ref. No. 20, p. 103). The blue and black deposits indicate a release from the source area. The leaching pools received wastewater from 1977 until 1985 (Ref. Nos. 19, p. 109; 20, pp. 100-102). The leaching pools were not lined or otherwise contained. The total volume deposited in the leaching pools is unknown; however, over 6,000 gallons of liquid and 2,255 gallons of sludge were reported to have been removed from the pools (Ref. Nos. 3, pp. 8, 9; 19, p. 69). Several volatile organic compounds and metals have been detected in CEM's wastewater (Ref. Nos. 3; 5, pp. 4, 5; 6, p. 7; 19, pp. 90, 93; 20, pp. 121, 122). Various areas of documented contaminated soil were paved over prior to July 1987 (Ref. No. 20, p. 83). A surficial soil sample collected in the vicinity of a solvent storage shed revealed the presence of contaminants (Ref. No. 20, pp. 74, 78, 79, 124-130). The area associated with the contaminated soil was not delineated; however, for the purposes of this assessment, the area is considered to be 1 square foot. Solvents, glue, and alcohols are stored in a storage shed on site. A stained area located south of the storage shed and liquid present in the bottom of the storage shed were noted on 15 July 1987. The capacity of the storage shed is not known; therefore, for the purposes of this assessment, at least one 55-gallon drum is considered to be present in the shed (Ref. No. 20, p. 74).

Numerous sampling events have been conducted at the CEM site between January 1981 and October 1988. Table 1 presents a summary of the sampling events and Tables 2 and 3 present a summary of the analytical data collected during the sampling events. Eder Associates, H2M and Geraghty & Miller have been hired independently as environmental consultants by CEM. EM Science and Technology prepared a Phase I Investigation Report on CEM for the NYSDEC/Division of Solid and Hazardous Waste (DSHW) in June 1987 (Ref. No. 19). NUS Corporation completed a Site Inspection Report for the U.S. Environmental Protection Agency (EPA) in September 1990 (Ref. No. 20).

An off-site reconnaissance was conducted by Roy F. Weston, Inc. (WESTON®) on 19 April 1994. Currently, CEM is active, employing approximately 61 people. The areas overlying the underground storage tanks and leaching pools have been paved over. The site is not completely fenced and access to exterior areas is not limited (Ref. Nos. 2; 20, p. 90). No plans for additional cleanup actions are present in available background files.

EVALUATION OF EXISTING INFORMATION AND SITE INSPECTION REPORT

Existing information, primarily from the NYSDEC/DSHW Phase I Report, the NUS Corporation Site Inspection Report and supporting documentation were used to conduct an evaluation of the CEM site. Updated and additional data were collected to further evaluate the site to determine the need for remedial action under the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA). The information used to evaluate the current site status includes groundwater user populations within a 4-mile radius of the site, wellhead protection area information, fishery and sensitive environment data within 15 miles downstream of the site, and 1990 census population data and sensitive environments within 4 miles of the site.

HAZARD ASSESSMENT

Groundwater Migration Pathway - An observed release of hazardous substances from the CEM site to groundwater has been documented. Three shallow monitoring wells, screened at depths ranging from 30 to 34.2 feet below ground surface, have been installed to monitor groundwater conditions at the site. Groundwater samples have been collected during four sampling events conducted between February 1986 and June 1988. Dichloroethylene, trichloroethylene and tetrachloroethylene were detected in groundwater samples collected by Geraghty & Miller on 29 June 1988 from downgradient monitoring well DP-2 at concentrations greater than three times their respective upgradient concentrations (Ref. No. 4). Tetrachloroethylene was detected in groundwater collected by Geraghty & Miller on 27 February 1987 at a concentration five times the upgradient concentration (Ref. No. 20, pp. 65, 66). Groundwater samples collected from the downgradient monitoring wells in February 1986 and July 1987 indicate the presence of

TABLE 1

**SUMMARY OF SAMPLING EVENTS CONDUCTED AT THE
COMMERCIAL ENVELOPE MFG. CO., INC. SITE**

| Sampling Date | No. of Samples Collected | Matrix | Source | Analyses | Sampler | Laboratory | Quality Assurance/ Quality Control | Reference Numbers |
|---------------|--------------------------|---------|--------------------------|---------------------------------------------------|---------|------------|---------------------------------------|-------------------|
| 1/15/81 | 1 | Aqueous | Spill | Cd, Cu, Cr, Cr ⁺⁶ , Pb, Ag, Zn | SCDHS | SCHSL | Unknown | 20, p. 122 |
| 4/29/83 | 1 | Aqueous | UST Puddle | Volatile halogenated organics | SCDHS | H2M Corp. | Unknown | 3 |
| 8/29/84 | 1 | Aqueous | Loading Dock Storm Drain | VOCs | SCDHS | SCDHS/PHL | COC | 20, p. 121 |
| 9/19/84 | 2 | Aqueous | Bubbling Pool | VOCs | SCDHS | SCDHS/PHL | COC | 19, pp. 90-93 |
| | 1 | Aqueous | Bubbling Pool | Cd, Cu, Cr, Cr ⁺⁶ , Fe, Pb, Ag, Zn, Ni | SCDHS | SCHSL | COC | 19, pp. 90-93 |
| | 1 | Aqueous | Loading Dock Spill | Cd, Cu, Cr, Cr ⁺⁶ , Fe, Pb, Ag, Zn, Ni | SCDHS | SCHSL | COC | 19, pp. 90-93 |
| 10/24/84 | 1 | Aqueous | Ground Discharge | VOCs | SCDHS | SCDHS/PHL | COC | 5, pp. 4, 5 |
| 12/4/84 | 5 | Aqueous | Wastewater | Cd, Cu, Cr, Fe, Pb, Ni, Ag | H2M | H2M | Unknown | 6, pp. 7, 8 |
| 2/8/85 | 1 | Aqueous | Wastewater | Cd, Cu, Cr, Fe, Pb, Ag, Zn, Phenols | H2M | H2M | Unknown | 6, p. 9 |
| 2/11/85 | 1 | Aqueous | Wastewater | Cd, Cu, Cr, Fe, Pb, Ag, Zn | H2M | H2M | Unknown | 6, p. 10 |
| 2/15/85 | 1 | Aqueous | Wastewater | Cd, Cu, Cr, Fe, Pb, Ag, Zn | H2M | H2M | Unknown | 6, p. 11 |

TABLE 1 (CONTINUED)

 SUMMARY OF SAMPLING EVENTS CONDUCTED AT THE
 COMMERCIAL ENVELOPE MFG. CO., INC. SITE

| Sampling Date | No. of Samples Collected | Matrix | Source | Analyses | Sampler | Laboratory | Quality Assurance/ Quality Control | Reference Numbers |
|---------------|--------------------------|-------------------|------------------------------|---------------------------------------------------|-------------------|--------------------|---------------------------------------|-------------------|
| 7/9/85 | 1 | Aqueous | Leaching Pool | VOCs | SCDHS | SCDHS/PHL | COC | 19, pp. 97-100 |
| | 1 | Sludge | Loading Dock | VOCs | SCDHS | SCDHS/PHL | COC | 19, pp. 97-100 |
| | 1 | Aqueous | Leaching Pool | Cd, Cu, Cr, Cr ⁺⁶ , Fe, Pb, Ni, Ag, Zn | SCDHS | SCDHS | COC | 19, pp. 97-100 |
| | 1 1 | Sludge Aqueous | Loading Dock | Cd, Cu, Cr, Cr ⁺⁶ , Fe, Pb, Ni, Ag, Zn | SCDHS | SCDHS | COC | 19, pp. 97-100 |
| 2/6/86 | 2 | Groundwater | NA | VOCs, Metals | Geraghty & Miller | Ecotest Labs, Inc. | Unknown | 20, pp. 63, 64 |
| 2/27/86 | 3 | Solid | UST, Clinkers, Bubbling Pool | Cd, Cu, Cr, Pb, Ni, Ag, Zn | SCDHS | SCHSL | COC | 19, pp. 71-76 |
| | 2 | Aqueous | UST | Cd, Cu, Cr, Pb, Ni, Ag, Zn | SCDHS | SCHSL | COC | 19, pp. 71-76 |
| | 1 | Aqueous | UST | VOCs | SCDHS | SCHSL/PHL | COC | 19, pp. 71-76 |
| 3/20/86 | 3 | Solid/Soil | UST | RCRA Characteristics, Organics | Eder Associates | Nytest | COC | 6, pp. 16-28 |
| | 3 | Aqueous | Wastewater | RCRA Characteristics, Organics | Eder Associates | Nytest | COC | 6, pp. 16-28 |
| 2/27/87 | 2 | Groundwater | NA | VOCs, Metals | Geraghty & Miller | Ecotest Labs, Inc. | Unknown | 20, pp. 65, 66 |

TABLE 1 (CONTINUED)

 SUMMARY OF SAMPLING EVENTS CONDUCTED AT THE
 COMMERCIAL ENVELOPE MFG. CO., INC. SITE

| Sampling Date | No. of Samples Collected | Matrix | Source | Analyses | Sampler | Laboratory | Quality Assurance/ Quality Control | Reference Numbers |
|---------------|--------------------------|-------------|----------------|------------------------------|-------------------|--------------------|---------------------------------------|--------------------|
| 7/13/87 | 2 | Soil | Solvent Shed | TCL Parameters (Organics) | NUS Corporation | Nanco | CLP Protocols | 20, pp. 3, 131-196 |
| | 3 | Groundwater | NA | TCL Parameters (Organics) | NUS Corporation | Nanco | CLP Protocols | 20, pp. 3, 131-196 |
| | 2 | Soil | Solvent Shed | TCL Parameters (Inorganics) | NUS Corporation | Chemtech | CLP Protocols | 20, pp. 3, 131-196 |
| | 3 | Groundwater | NA | TCL Parameters (Inorganics) | NUS Corporation | Chemtech | CLP Protocols | 20, pp. 3, 131-196 |
| 9/11/87 | 1 | Aqueous | Waste | Metals, RCRA Characteristics | Chem. Mgt. Inc. | Ecotest Labs, Inc. | Unknown | 5, pp. 6, 7 |
| 6/29/88 | 3 | Groundwater | NA | VOCs, Metals | Geraghty & Miller | Ecotest Labs, Inc. | Unknown | 4, pp. 7-9 |
| 8/31/88 | 5 | Aqueous | Ink Waste | EP Toxicity Metals | CEM | Ecotest Labs, Inc. | Unknown | 5, pp. 9-13 |
| 9/13/88 | 4 | Aqueous | Drum Composite | EP Toxicity Metals | CEM | Ecotest Labs, Inc. | Unknown | 5, pp. 14-17 |
| 10/4/88 | 1 | Aqueous | Drum Composite | EP Toxicity Metals | CEM | Ecotest Labs, Inc. | Unknown | 5, p. 18 |

Notes: Analytes are represented by their respective symbols (Cd = cadmium, Cu = copper, Cr = chromium, Cr⁺⁶ = hexavalent chromium, Fe = iron, Pb = lead, Ni = nickel, Ag = silver, and Zn = zinc).

- NA - Not applicable.
- SCDHS - Suffolk County Department of Health Services.
- SCHSL - Suffolk County Health Services Laboratory.
- SCDHS/PHL - Suffolk County Department of Health Services/Public Health Laboratory.
- VOCs - Volatile Organic Compounds
- COC - Chain of custody
- UST - Underground storage tank
- TCL - Target Compound List
- CLP - Contract Lab Program
- RCRA - Resource, Conservation and Recovery Act
- EP - Extraction Procedure



TABLE 2

**SUMMARY OF THE HIGHEST CONCENTRATIONS OF SELECTED
HAZARDOUS SUBSTANCES DETECTED IN WASTE SAMPLES COLLECTED
AT COMMERCIAL ENVELOPE MFG. CO., INC. SITE**

| Hazardous Substance | Aqueous | Reference No. | Sludge/Solid | Reference No. |
|-------------------------------|---------|---------------|--------------|---------------|
| Organic Compounds | | | | |
| | (ug/L) | | (ug/kg) | |
| Methylene Chloride | 2,500 | 3 | | |
| cis-Dichloroethylene | 2,300 | 20, p. 121 | | |
| 1,1,1-Trichloroethylene | 150 | 19, p. 90 | | |
| 1,1,2-Trichloroethane | 520 | 20, p. 121 | | |
| Tetrachloroethylene | 970 | 20, p. 121 | | |
| Benzene | 11 | 20, p. 121 | | |
| m-Xylene/Chlorobenzene | 640 | 3 | | |
| p-Xylene | 73 | 3 | | |
| o-Xylene | 330 | 3 | | |
| Ethylbenzene | 260 | 3 | | |
| Styrene | 49 | 20, p. 121 | 33 | 19, p. 100 |
| 1,2,4-Trimethylbenzene | 190 | 19, p. 93 | | |
| Methyl isobutyl ketone | 270 | 5, pp. 4, 5 | | |
| Toluene | 690 | 19, p. 93 | | |
| Inorganic Contaminants | | | | |
| | (mg/L) | | (mg/kg) | |
| Cadmium | | | 12 | 19, p. 73 |
| Copper | 32.9 | 6, p. 7 | 1,017 | 19, p. 73 |
| Chromium | 43 | 20, p. 122 | 74 | 19, p. 73 |
| Iron | 193 | 6, p. 8 | 7,700 | 19, p. 98 |
| Lead | 210 | 20, p. 122 | 166 | 19, p. 71 |
| Nickel | 0.6 | 19, p. 76 | 46 | 19, p. 73 |
| Silver | 4.0 | 6, p. 7 | 2.9 | 19, p. 98 |
| Zinc | 11 | 20, p. 122 | 170 | 19, p. 98 |

Notes:

Blank space - Contaminant was not analyzed for or not detected.

ug/L: - Micrograms per liter.

ug/kg: - Micrograms per kilogram.

mg/L: - Milligrams per liter.

mg/kg: - Milligrams per kilogram.

TABLE 3**SUMMARY OF THE SELECTED GROUNDWATER SAMPLING RESULTS
FROM SAMPLING EVENTS CONDUCTED AT THE
COMMERCIAL ENVELOPE MFG. CO., INC. SITE**

(All results in ug/L)

| Hazardous Substance | Downgradient | Upgradient | Detection Limit | Reference No. |
|----------------------|--------------|------------|-----------------|---------------|
| 1,2-Dichloroethylene | 17 | ND | 2 | 4 |
| Trichloroethylene | 4 | ND | 1 | 4 |
| Tetrachloroethylene | 32 | ND | 1 | 4 |
| Tetrachloroethylene | 5 | ND | 1 | 19, pp. 71-76 |

Note:

ug/L - Micrograms per liter.
ND - Not Detected

various chlorinated hydrocarbons; however, no upgradient sample was collected in 1986 and the 1987 results do not meet observed release criteria (Ref. No. 20, pp. 63, 64, 124, 164-174).

The aquifer of concern is the Cretaceous age Magothy Formation. In the vicinity of the site, the Magothy is overlain by Quaternary age upper Pleistocene deposits which form the Upper Glacial Aquifer. The Upper Glacial Aquifer is composed of outwash deposits consisting of fine to very coarse quartzose sand and pebble- to boulder-sized gravel. The Upper Glacial Aquifer extends from land surface to a depth ranging from 104 to 138 feet below ground surface within 1 mile of the site. In July 1987, the depth to groundwater at the site ranged from 16 to 22.2 feet below ground surface. The hydraulic conductivity of the upper glacial aquifer ranges from 10^{-2} to 10^{-4} centimeters per second (cm/sec). The Magothy Formation is composed of grey, white, red, brown and yellow quartzose sand and gravel. Medium to fine sand is interbedded in this formation along with layers of coarse sand, sandy and solid clay. The Magothy Formation is up to 1,100 feet thick on Long Island. The log for a well located approximately 0.2 mile from the site indicates that the Magothy is 710 feet thick at that location. The hydraulic conductivity of the Magothy Formation ranges from 10^{-4} to 10^{-6} cm/sec. There is no confining unit separating the Upper Glacial and the Magothy aquifers in the vicinity of the site; therefore, these unconsolidated deposits are considered to act as a single hydrogeologic unit. Groundwater flow in the aquifers is generally toward the southeast (Ref. Nos. 12; 14).

Groundwater is the sole source of potable water on Long Island. Three public or municipal water systems supply water to businesses and residences located within 4 miles of the site. These water systems obtain water from the Magothy or the Magothy and Upper Glacial Aquifers. The nearest public/municipal supply well is located approximately 3,500 feet northeast of the site. Public/municipal wells located within a 4-mile radius of the site supply water to approximately 157,770 people (0-¼ mile: 0; ¼-½ mile: 0; ½-1 mile: 13,920; 1-2 miles: 27,840; 2-3 miles: 49,350; 3-4 miles: 66,660) (Ref. Nos. 10-12). NYSDEC has designated deep flow recharge areas for the Magothy and Lloyd aquifers and a fixed variable-shape zone around any public water supply well drawing from the Upper Glacial Aquifer as wellhead protection areas on Long Island. CEM does not overlie a deep flow recharge area. There are public/municipal supply wells drawing from the glacial aquifer within 4 miles of the site; therefore, designated wellhead protection areas are present within the target distance limit (Ref. No. 13).

Surface Water Migration Pathway - A release of contaminants to surface water is not observed or suspected. No surface water or sediment samples were collected in association with the CEM site. The nearest downslope surface water is Sampawams Creek, located approximately 1,800 feet southeast of the site. There are several storm drains situated along the overland migration route between the site and the creek; therefore, there is a low likelihood for a release of hazardous substances from the site to surface water, as these storm drains are reported to

discharge to the leaching pools. Sampawams Creek [average flow rate: 9.63 cubic feet per second (cfs)] flows approximately 5 miles toward the south-southwest, through several small lakes before discharging into Great South Bay at Babylon Cove. The 15-mile surface water migration pathway extends east to Nicoll Bay in Brookhaven, west to South Oyster Bay in Massapequa and south through Fire Island Inlet to the Atlantic Ocean. The southward migration pathway is limited by the presence of several coastal barrier islands including Fire Island. Drinking water on Long Island is obtained from groundwater wells; therefore, there are no drinking water intakes located within 15 miles downstream of the site.

Sampawams Creek contains fresh water from its headwaters to Route 27 (Sunrise Highway), a distance of approximately 2.8 miles. South of Route 27, Sampawams Creek is brackish to Montauk Highway, approximately 1.6 miles downstream. Sampawams Creek is saline south of Montauk Highway. Great South Bay, Nicoll Bay, South Oyster Bay, Fire Island Inlet and the Atlantic Ocean are saline coastal tidal waters. The fresh water portion of Sampawams Creek is a recreational fishery. The Atlantic Ocean and Great South Bay are commercial shellfisheries. Fire Island Inlet and South Oyster Bay are recreational fisheries. Approximately 2 miles of seasonally-flooded palustrine wetlands are located along Sampawams Creek. Approximately 85 miles of estuarine wetlands front the coastal tidal waters included in the 15-mile surface water migration pathway. Sampawams Creek, Great South Bay, and portions of the Atlantic Ocean have been designated by the NYSDEC for the maintenance of aquatic life and are therefore considered sensitive environments. Habitats for three State-listed endangered species and two State-listed threatened species have been identified along the coastal tidal waters associated with the site. Fire Island is a partially developed coastal barrier and a National Seashore Recreation Area, both of which are considered sensitive environments (Ref. Nos. 11; 15-17; 20, p. 223). The site is located outside the boundary of the 500-year floodplain (Ref. No. 20, pp. 226-228).

Soil Exposure Pathway - Soil contamination has been documented at the CEM site. Samples collected from spills and seeps on the ground by the SCDHS at the site document a release of contaminants to soil; however, the affected areas have since been paved over and are not accessible for direct contact. Tetrachloroethylene was detected in one surficial soil sample collected by NUS Corporation on 13 July 1987. The soil sample was collected at a depth of 0 to 6 inches below ground level proximal to the solvent shed and several empty drums. The area associated with the contaminated soil was not documented or described; therefore, for the purposes of this report, the area is estimated to be 1 square foot. NUS Corporation did not collect a background soil sample (Ref. Nos. 2; 20, pp. 3, 73, 79, 86, 90, 148). CEM is located amidst several light industrial and commercial enterprises. Based on the WESTON off-site reconnaissance conducted on 19 April 1994, there are at least 61 people currently employed at CEM (Ref. No. 2, pp. 4, 5). There are no residences, schools or day care centers within 200 feet of the site. The site is not fenced. There are no known terrestrial sensitive environments located within 200 feet of the site (Ref. No. 18).

Air Migration Pathway - A release of contaminants to air is not observed or suspected. CEM operates an on-site waste incinerator. Several complaints were lodged against CEM for odors; however, follow-up investigations by SCDHS and NYSDEC/Division of Air Resources did not substantiate the complaints (Ref. No. 8). No readings above background were detected in the ambient air during the NUS Corporation sampling event using an organic vapor analyzer (OVA) flame ionization detector or an HNu photoionization detector. NUS Corporation reported that readings above background were detected on the air monitoring instruments in the solvent storage shed (Ref. No. 22, pp. 73-84). CEM is not required to monitor the incinerator emissions and no report of any emissions testing was located in available background information. The site is active. An off-site reconnaissance conducted by WESTON on 19 April 1994 revealed the presence of 61 vehicles at the site; therefore, at least 61 people currently work at CEM (Ref. No. 2, p. 4). Approximately 197,870 people live within 4 miles of the site (0-¼ mile: 240; ¼-½ mile: 970; ½-1 mile: 7,570; 1-2 miles: 41,250; 2-3 miles: 61,850; 3-4 miles: 85,990) (Ref. No. 17). The habitats of two federal-listed endangered species, four State-listed endangered species, four State-listed threatened species and one species under review as to its federal status have been identified within 4 miles of the site (Ref. No. 18). There are approximately 381 acres of wetlands within 4 miles of the site. (0-¼ mile: 0; ¼-½ mile: 0; ½-1 mile: 0; 1-2 miles: 6; 2-3 miles: 156; 3-4 miles: 219) (Ref. No. 15).

SUMMARY

The existing information, data and additional information gathered were sufficient to evaluate the site. This assessment indicates that the site poses a threat to human health and the environment. A release of contaminants attributable to the site to the Upper Glacial Aquifer has been documented. The Upper Glacial Aquifer is hydraulically connected to the Magothy Formation. All potable water on Long Island is obtained from groundwater. Public and municipal water systems supply over 150,000 people with drinking water obtained from groundwater wells located within 4 miles of the site. The nearest potable water well is located approximately 3,500 feet northeast of the site. Surficial soil contamination has been documented; however, the unpaved area is relatively small. The site is active, and at least 61 people currently work at CEM. There are no residences, day care centers, or schools located within 200 feet of the site. There is no evidence which indicates that hazardous substances attributable to the site have migrated to the nearest downslope surface water body which is located approximately 1,800 feet from CEM. There are no known sensitive environments in the vicinity of the site and the underground storage tanks and leaching pools have been paved over, limiting the exposure via contact with the soil and air migration.

REFERENCES

1. U.S. Environmental Protection Agency (EPA) Superfund Program, Comprehensive Environmental Response, Compensation and Liability Information System (CERCLIS), List-4: Site Alias Location Listing, p. 330, 3 June 1994; and List-8: Site/Event Listing, p. 337, 6 June 1994.
2. Field Logbook for the Commercial Envelope Mfg. Co., Inc. site, Document Control No.: 4200-22-ADVT, Off-site Reconnaissance conducted by Roy F. Weston, Inc. (WESTON®) on 19 April 1994.
3. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Various Suffolk County Department of Health Services inspection reports, observations and analytical results, 27 June 1994; plus attachments.
4. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Assorted groundwater monitoring information, 27 June 1994; plus attachments.
5. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Assorted sampling results, 28 June 1994; plus attachments.
6. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: CEM's incinerator, 28 June 1994; plus attachments.
7. Letter from Robert Seyfarth, Senior Public Health Sanitarian, County of Suffolk/Department of Health Services, to Mr. Joseph Guarino, Town of Babylon, 17 January 1991; plus attachment.
8. County of Suffolk Department of Health Services memorandum from Robert Seyfarth to Robert Capp, P.E., New York State Department of Environmental Conservation (NYSDEC)-Stony Brook, Subject: Commercial Envelope-Deer Park. 28 January 1993; plus attachments.
9. Phone Conversation Record: Conversation between Cindy, Tax Assessors Office, and Diane Donovan Minsavage, WESTON, 15 April 1994.

REFERENCES**Document Control No.: 4200-22-AEDP**

10. Four-Mile Vicinity Map for Commercial Envelope Mfg. Co., Inc. compiled from U.S. Department of the Interior, Geological Survey Topographic Maps, 7.5 minute series, Quadrangles of "Amityville, NY," 1969; "Bay Shore East, NY," 1967; "Bay Shore West, NY," 1969; "Central Islip, NY," 1967; "Greenlawn, NY," 1967; and "Huntington, NY," 1967, all photorevised 1979.
11. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Potable water sources within 4 miles of the site, 20 June 1994; plus attachments.
12. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Geology in the vicinity of the site, 23 June 1994; plus attachments.
13. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Wellhead protection areas located within 4 miles of the site, 24 June 1994; plus attachments.
14. Hazard Ranking System; Final Rule, 40 Code of Federal Regulations, Part 300, Federal Register, Volume 55, No. 241, p. 51601, 14 December 1990.
15. Fifteen-Mile Surface Water Migration Pathway Map for Commercial Envelope Mfg. Co., Inc. compiled from the U.S. Department of the Interior, Fish and Wildlife Services, National Wetland Inventory Maps, 7.5 minutes series, Quadrangles of: "Bay Shore East, NY"; "Bay Shore West, NY"; "Central Islip, NY"; "Greenlawn, NY"; and "Sayville, NY", all based on aerial photography April 1980; and "Amityville, NY"; "Huntington, NY"; and "West Gilgo Beach, NY", all based on aerial photography April 1981.
16. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Surface water pathway information, 24 June 1994; plus attachments.
17. Letter from Bob Frost, Frost Associates, to Jan Holderness, WESTON, Subject: Commercial Envelope Mfg. Co., 22 April 1994.
18. Project Note from D. D. Minsavage, WESTON, to Commercial Envelope Mfg. Co., Inc. file, Subject: Listed species habitats located within a 4-mile radius or 15 miles downstream of the site, 27 June 1994; plus attachment.

REFERENCES

Document Control No.: 4200-22-AEDP

THE "ORIGINAL" COPY OF THIS REPORT IS IN THE SITE FILE

WHY DUPLICATE (?)

- * 19. NYSDEC/Division of Solid and Hazardous Waste, Engineering Investigations at Inactive Hazardous Waste Sites in the State of New York, Phase I Investigation Report, Commercial Envelope Mfg. Co., Inc. (New York ID No. 152103), prepared by EA Science and Technology, June 1987. *136 PAGES*

THE "ORIGINAL" COPY OF THIS REPORT IS IN THE SITE FILE

- * 20. U.S. EPA, Final Draft Site Investigation Report, Commercial Envelope Mfg. Co., Inc., prepared by NUS Corporation, 21 September 1990. *233 PAGES*

WHY DUPLICATE (?)

21. Letter from Gary A. Rozmus, Vice President, Eder Associates Consulting Engineers, P.C., to Mr. Vincent J. Frisina, P. E., Public Health Engineer, SCDHS/Hazardous Materials Management, 14 April 1986; plus attachments.

REFERENCE NO. 1

CERCLIS DATA BASE DATE: 06/03/94

** PROD VERSION **

PAGE NO: 330

CERCLIS DATA BASE TIME: 16:31:10

U.S. EPA SUPERFUND PROGRAM

VERSION 2.01

LEVEL: REGION 02

** CERCLIS **

RUN DATE: 06/06/94

SELECTION: INTEGRATED

LIST-4: SITE ALIAS LOCATION LISTING

RUN TIME: 12:17:39

SEQUENCE: REG, ST, SITE NAME

REGION: 02

| EPA IDENTIFICATION NUMBER | SITE NAME/ALIAS NAME STREET/ALIAS STREET CITY/ALIAS CITY COUNTY NAME | STATE/ALIAS STATE COUNTY CODE | ZIP CODE | ALIAS SEQ. # | NAME SOURCE | FEDERAL FACILITY FLAG | CONGRESSIONAL DISTRICT (S) |
|---------------------------------|-----------------------------------------------------------------------------------|----------------------------------|-------------|--------------------|----------------|-----------------------------|-------------------------------|
| NYD000285478 | COLUMBIA MILLS OFF RTE 48 MINETTO OSWEGO | NY 075 | 13115 | | STS | N | |
| | COLUMBIA MILLS | | | 01 | | | |
| | OSWEGO | NY | | | | | |
| NYD002105534 | COLUMBUS MCKINNON CORP FILLMORE & FREMONT ST TONAWANDA ERIE | NY 029 | 14150 | | HWDM | N | |
| NYD981184138 | COMMERCIAL ENVELOPE MFG. CO., INC. 900 GRAND BOULEVARD DEER PARK SUFFOLK | NY 103 | 11729 | | EPA | N | |
| NYD125499673 | COMPUTER CIRCUITS 145 MARCUS BLVD. HAUPPAUGE SUFFOLK | NY 103 | 11746 | | | N | |
| NYD981486947 | CONKLIN DUMPS ROUTE 7 CONKLIN BROOME | NY 007 | 13748 | | EPA | N | |
| | CONKLIN DUMPS | | | 01 | | | |
| | BROOME | NY | | | | | |
| NYD980528434 | CONRAIL-(HORNELLSVILLE) LODER ST HORNELLSVILLE STEUBEN | NY 101 | 14807 | | STS | N | |
| | CONRAIL HORNELLSVILLE LODER STREET TOWN OF HORNELLSVILLE | NY | 14807 | 01 | | | |

RUN DATE: 06/07/94 13:51:39
CERCLIS DATA BASE DATE: 06/06/94
CERCLIS DATA BASE TIME: 17:28:58
VERSION 3.00

** PROD VERSION **
U.S. EPA SUPERFUND PROGRAM
** CERCLIS **
LIST-8: SITE/EVENT LISTING

PAGE: 337
CERHELP DATA BASE DATE: N/A
CERHELP DATA BASE TIME: N/A

SELECTION:
SEQUENCE: REGION, STATE, SITE NAME

EVENTS: ALL

| EPA ID NO. | SITE NAME STREET CITY COUNTY CODE AND NAME | STATE ZIP CONG DIST. | OPRBLE UNIT | EVENT TYPE | EVENT QUAL | ACTUAL START DATE | ACTUAL COMPL DATE | CURRENT EVENT LEAD |
|--------------|---------------------------------------------------------------------------------------|----------------------------|----------------|--------------------------|---------------|-------------------------|----------------------------------------------|--------------------------------------------------------|
| NYD002063154 | COLUMBIA CORP NY RTE 67 WALLOOMSAC 083 RENSSELAER | NY 12133 | 00 | DS1 PA1 | NFA | | 02/01/78 06/08/87 | EPA (FUND) STATE(FUND) |
| NYD002063147 | COLUMBIA CORP LF NY RTE 295 CHATHAM 021 COLUMBIA | NY 12037 | 00 | DS1 PA1 SI1 | NFA NFA | 07/01/83 | 02/01/78 08/01/83 08/01/83 | EPA (FUND) EPA (FUND) STATE(FUND) |
| NYD000285478 | COLUMBIA MILLS OFF RTE 48 MINETTO 075 OSWEGO | NY 13115 | 00 | DS1 PA1 SI1 | | | 03/01/80 03/01/80 03/01/89 | EPA (FUND) EPA (FUND) STATE(FUND) |
| NYD002105534 | COLUMBUS MCKINNON CORP FILLMORE & FREMONT ST TONAWANDA 029 ERIE | NY 14150 | 00 | DS1 PA1 SI1 | | 12/04/87 | 11/16/81 12/30/87 10/01/89 | EPA (FUND) EPA (FUND) STATE(FUND) |
| NYD981184138 | COMMERCIAL ENVELOPE MFG. CO., INC. 900 GRAND BOULEVARD DEER PARK 103 SUFFOLK | NY 11729 | 00 | DS1 PA1 SI1 | | 09/21/87 | 03/25/86 03/27/86 09/22/87 | STATE(FUND) STATE(FUND) EPA (FUND) |
| NYD125499673 | COMPUTER CIRCUITS 145 MARCUS BLVD. HAUPPAUGE 103 SUFFOLK | NY 11746 | 00 | DS1 PA1 SI1 | | 06/29/87 | 06/29/87 07/01/87 07/01/87 | STATE(FUND) STATE(FUND) STATE(FUND) |
| NYD981486947 | CONKLIN DUMPS ROUTE 7 CONKLIN 007 BROOME | NY 13748 | 00 | RS1 RS2 DS1 PA1 | | 04/11/90 07/08/91 | 09/14/90 08/12/91 09/06/85 04/11/86 | EPA (FUND) EPA (FUND) STATE(FUND) STATE(FUND) |

REFERENCE NO. 2

W.O.# 04200-022-081-0006

DCN#4200-22-ADVT

Commercial Envelope

BUSINESS REPLY MAIL

FIRST CLASS MAIL PERMIT NO. 386 WEST CHESTER, PA

POSTAGE WILL BE PAID BY ADDRESSEE

ROY F. WESTON, INC.
1 WESTON WAY
WEST CHESTER, PA 19380-9846

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

COMMERCIAL ENVELOPE MFG. CO., INC.
DEER PARK, SUFFOLK COUNTY, NEW YORK
CERCLIS ID No.: NYD981184138

DCN:4200-22-ADVT

Commercial Envelope Mfg. Co., Inc.
Deer Park, Suffolk County, New York
WO# 04200-022-081-0006-

20

Table of Contents

Page(s)


Off-site Reconnaissance

3-5

Photograph Log

7

21



April

Wec

1500 Loc

ope

Gra

Cor

Env

Rec

502 Pa

Co

Do

Wal

Com

Env

Ar

Ple

Not

bal

Sgt

ELN

Conn

east

Drec

plon

4/19/98

COMMERCIAL ENVELOPE MFG. CO., INC.
DEER PARK, SUFFOLK COUNTY, NEW YORK

April 19, 1994

Off-site reconnaissance

Weather: Cloudy/overcast, warm (~75°), humid

1500 Located site. Adjacent to other commercial operations/warehouses on south side of Grand Boulevard.
Commercial Envelope Mfg. Co./Business Envelope Mfg Co is active.

Recon team:

Diane D. Minsavage — WESTON

502 Parked in "Fleet Bank" parking lot; located on corner of Grand Blvd and Jeffry Blvd.

Observed storm drains in bank parking lot.

Walked west along Grand Blvd, toward Commercial Envelope Mfg. Co., Inc./Business Envelope Mfg. Co site.

"Art Martin" building located between Fleet Bank and site.

Northeast of site, across Grand Blvd a ball field; ~200 ft from site. Three Softball players present.

ELM Freight Handling operating out of "warehouse". Counted 27 vehicles present in parking lot on eastern side of CEM/BEM bldg.

Directly across Grand Blvd — fenced + gated property — no sign identifying company

4/19/94

COMMERCIAL ENVELOPE MFG. Co., INC.

DEER PARK, SUFFOLK COUNTY, NEW YORK

19 APRIL 1994

19 APRIL 19

34 Vehicles counted in parking lot on western side of CEM/BEM bldg.

1522

— Total of 61 vehicles counted on site (windshield survey)

Innovision Inc. operating in bldg. adjacent to/ just west of CEM/BEM site.

1511 Panoramic photo of front of CEM/BEM looking south to southeast from across Grand Blvd; photos 1P12-1P16 (roll continues) from 3-Dimensional Circuits recon)

Looking for upgradient well (TW1), supposed to be across Grand Blvd from CEM/BEM site. Monitoring well not located — may have been removed, or may be behind north of fence in wooded area.

1517 Panoramic photo (1P16-1P19) of eastern portion of CEM/BEM site from across street (Grand Blvd).

No visible drums present at site; incinerator not obvious.

1520 Photo (1P30) of eastern portion of site and ballfield across street looking west (down Grand Blvd) from front of "Art Mulin"

COMMERCIAL ENVELOPE MFG. CO., INC.

DEER PARK, SUFFOLK COUNTY, NEW YORK

19 APRIL 1994

1522 Return to vehicle; drive about area —

ELM Freight Handling also posted as
"ELM Public Warehouse and Distributing"

Drove southeast down Jeffryn — more
commercial/industrial facilities
ELM accessible from Burt Drive — Storm
drains on Jeffryn and Burt. No storm
drains on Grand Blvd / in vicinity of
CEM/BEM Site.

No residences/day care center present
within 200 feet of the site; only
industrial/commercial operations —

DDM
4/19/94

TIME
1511

1517

1520

DDM

Commercial Envelope Mfg. Co., Inc.
Deer Park, Suffolk County, New York

All photos taken by D.D. Minsavage

PHOTOGRAPH LOG

| <u>TIME</u> | <u>No.</u> | <u>DESCRIPTION</u> |
|-------------|------------|-------------------------------------------------------------------------------------------------------------------------|
| 1511 | 1P12-16 | Photo Panoramic view of 4/19/94 front of CEM/BEM looking south to southeast from across Grand Blvd. |
| 1517 | 1P17-19 | Panoramic view of eastern portion of CEM/BEM site, looking west from across Grand Blvd. |
| 1520 | 1P20 | Photo of front of CEM/BEM and ballpark located across street, looking west from front of "Art Marlin" |

DEM

4/19/94

REFERENCE NO. 3

WESTON.

PROJECT NOTE

TO: Commercial Envelope Mfg. Co., Inc., file DATE: 27 June 1994
FROM: D.D. Minsavage W.O. NO.: 04200-022-081-00016-02
SUBJECT: Various Suffolk County Department of Health Services Inspection Reports, Observations, and Analytical Results

The attached information includes various inspection reports, etc. not previously included in either the PA or ST.

DDM

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
15 HORSEBLOCK PLACE, FARMINGVILLE, N.Y. 11738
(516) 451-4633

COUNTY EX 2 in
HWB 3-8-83

| | | | | | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|-----------------------------------------------------|-------|----------------------------------------------------------|-----|
| NAME OF FACILITY | | OWNER/OFFICER <u>Mr. Alan Kristel</u> | | PAGE 1 OF | |
| COMPANY NAME <u>Commercial Envelope Mfg. Co.</u> | | CONTACT <u>Mr. Paul Creditor</u> | | TEL. | |
| PLANT ADDRESS <u>Grand Bluch.</u> | | VILLAGE | | TOWN | |
| MAILING ADDRESS | | | | ZIP | |
| DATE <u>29 April 83</u> | TIME <u>1 PM</u> | ORIG. PERIODIC <input checked="" type="radio"/> RE. | WASTE | NO WASTE | H&H |
| INDUSTRY <u>Mfg. Envelopes</u> | | SEWAGE SYSTEM | | PUBLIC PRIVATE | |
| SPDES OR NPDES PERMIT? YES NO PERMIT NO. | | 360 PERMIT? YES NO PERMIT NO. | | | |
| SCAVENGER | | TEL. | | | |
| SCAVENGER APPROVED YES NO | | PICK UP RECORDS AVAILABLE YES NO | | RECORDS CONSISTENT WITH EXPECTED WASTE GENERATION YES NO | |
| HEATING SYSTEM-MFG. NAME | | FUEL TYPE | | FIRING RATE | |
| INCIN. NAME | | WASTE BURNED | | RATE | |
| DRUM STORAGE <input checked="" type="radio"/> YES NO | NUMBER STORED | TYPE OF MATERIAL STORED | | | |
| | INDOORS <u>30+</u> OUTDOORS <u>0+</u> | WASTE RAW | | | |
| STORAGE TANKS <input checked="" type="radio"/> YES NO | NUMBER OF TANKS | TYPE OF MATERIAL STORED | | | |
| | ABOVEGROUND <u>1</u> UNDERGROUND <u>3</u> | WASTE RAW | | | |
| OPEN PROCESS TANKS <input checked="" type="radio"/> YES NO | NUMBER OF OPEN PROCESS TANKS <u>1</u> | ANY ART. XII VIOLATIONS | | <input checked="" type="radio"/> YES NO | |
| Results of walk thru inspection conducted at Commercial Envelope Mfg. Co. Inspection made with Mr. Paul Creditor, representing Commercial Envelope. Also removed samples from select locations & drums or containers. | | | | | |
| Of special concern was a sample removed from black liquid which was discovered discharging from the South west wall of the excavation around an inground holding tank. The excavation is over the nearest tank to the building on the East side of the lot. The black liquid continued to discharge during the inspection and sampling on the | | | | | |
| PERMISSION IS GRANTED BY THIS FACILITY TO THE SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES TO CONDUCT ROUTINE SAMPLING OF CESSPOOLS, STORMDRAINS, AND OTHER DISCHARGE POINTS AT THE FACILITY. | | | | | |
| REINSPECTION SCHEDULED ON OR AFTER _____ FAILURE TO CORRECT UNSATISFACTORY CONDITIONS BY REINSPECTION DATE MAY RESULT IN A HEARING AND/OR FINE. | | | | | |
| SIGN. OF PERSON REC. REPORT | | TITLE | | INSPECTOR <u>David Obry</u> | |

| INDUSTRIAL WASTE PROCESS | | | | |
|--------------------------|--------------------------------------------------------------------------------|-----------------------------------------|-----------|--------------|
| NO. | PROCESS | CHEMICALS USED AND APPROXIMATE QUANTITY | DISCHARGE | DISCHARGE TO |
| | East side of Commercial Envelope (Approx 60-70 minutes) | | This new | |
| | discharge is of particular concern because all industrial waste | | | |
| | discharges from Commercial Envelope are by their claim ceased. The | | | |
| | liquid may be from one of three possible sources, i.e. unpermitted | | | |
| | industrial waste discharge, fourth industrial waste tank, or sewerage | | | |
| | The latter of the three seems unlikely because the waste is | | | |
| | observed while removing a sample of the liquid. | | | |
| | Also of concern was the two samples removed from the drum, | | | |
| | storage area in the South East portion of the side yard. Samples | | | |
| | from the waste "Cyl Press wash" smelled strongly of perchloroethylene, and | | | |
| | the liquid sampled separated into two phases in the sample bottle. The | | | |
| | sample removed from the plastic waste containers was highly caustic, | | | |
| | pH ≈ 10 , addition of acid for preservation caused a foaming reaction, | | | |

[illegible]

29 April 1983

1:00 PM.

Commercial Envelope Mfg. Co.
Grant Blvd. Deer Park.

Inspection Results

Specific Areas Noted Not in Compliance with Suffolk County
Sanitary Code Article 12, or NYS. Environmental Conservation Law.

As per numbers on Map. #1

- ① Cooling water discharge from pipe on wall to ground.
- ② In ground storage tank of gasoline, ~~no permit~~, no permit, not registered with Suffolk County.
- ③ Flammable material storage building, no permit, does not comply with SCSC Art. 12.
- ④ Ink pot wash tank, inside building, process tank, may not comply with SCSC Article 12.
- ⑤ Ink storage, 55 gal. drums, may not comply with SCSC Article 12, must provide chemical analysis.
- ⑥ Raw chemical storage area "Cyrl-Press Wash," must comply with SCSC Article 12.
- ⑦ 2000 gal. steel tank, industrial waste, no permit, must comply with SCSC Article 12.
- ⑧ Outside, inground, industrial waste holding tanks, no permit, not tested.
- ⑨ Outside, ink, oil waste drum storage, no permit, must comply with SCSC Article 12.
- ⑩ Outside, photo chem. press wash, drum-container storage area, no permit, must comply with Article 12.

Also observed at site #8, was a discharge thru soil of black liquid from unknown source.



SUFFOLK COUNTY
DEPT OF

HEALTH SERVICES


JOB Common 11 Envelope Mtg. Co.

SHEET NO. Grand Blvd. Deer Park

CALCULATED BY _____ DATE _____

CHECKED BY Daniel Obry DATE 29 April 1988

SCALE _____





HOLZMACHER, McLENDON and MURRELL, P.C.
H2M CORP.

575 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11747

Tel. (516) 694-3040

LABORATORY REPORT

LAB ID 03

CLIENT NAME AND ADDRESS

S. C. Dept. of Health Services
15 Horseblock Place
Farmingville, NY 11738

puddle inside excavation ground in rd.
tank, created by flow from tank

LAB. NO. 352672
TYPE WATER Miscellaneous
SAMPLING PT. I.D. #R4-D0-4-29
DATE SAMPLED 4/29/83
TIME SAMPLED _____
RUN TIME (WELL) _____
COLLECTED BY CL 99

VOLATILE HALOGENATED

ug/l

methylen chloride 2500
1,1-dichloroethylene <5
1,1-dichloroethane <5
* {trans-1,2-dichloroethylene <5
cis-1,2-dichloroethylene <5
chloroform <5
1,1,2-trichlorotrifluoroethane <5
1,2-dichloroethane <5
1,1,1-trichloroethane <5
carbon tetrachloride <5
bromodichloromethane <5
* {1,2-dichloropropane <5
2,3-dichloropropane <5
trans-1,3-dichloropropene <5
trichloroethylene <5
1,1,2-trichloroethane <5
* {chlorodibromomethane <5
cis-1,3-dichloropropene <5
bromoform <5
* {1,1,1,2-tetrachloroethane <5
tetrachloroethylene 430
1,1,2,2-tetrachloroethane <5
vinylchloride <5
* {dichlorodifluoro methane <5
chlorobenzene <5

VOLATILE NON-HALOGENATED

benzene
toluene
* {m-xylene
p-xylene
o-xylene

PESTICIDES

ug/l

lindane
heptachlor
aldrin
heptachlor epoxide
dieldrin
endrin
o,p' DDT
p,p' DDT
methoxychlor
toxaphene
chlordane

HERBICIDES

2,4-D
2,4,5-TP (silvex)

OTHERS

*Reported value represents total

RECEIVED

JUN 21 1983

SUFFOLK COUNTY DEPT.
HEALTH SERVICES

5/16/83

DATE REPORTED

Y.C. McLENDON, P.E., LAB DIRECTOR



HOLZMACHER, McLENDON and MURRELL, P.C.

H2M CORP.

575 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11747

Tel. (516) 694-3040

LABORATORY
REPORT

LAB ID 03

CLIENT NAME AND ADDRESS

S.C. Dept. of Health Services
15 Horseblock Place
Farmingville, NY 11738

LAB. NO. 352678

TYPE WATER Miscellaneous

SAMPLING PT. I.D. #R4-D0-4-29

DATE SAMPLED 4/29/83

TIME SAMPLED

RUN TIME (WELL)

COLLECTED BY D0 99

VOLATILE HALOGENATED

ug/l

methylene chloride
1,1-dichloroethylene
1,1-dichloroethane
* {trans-1,2-dichloroethylene
cis-1,2-dichloroethylene
chloroform
1,1,2-trichlorotrifluoroethane
1,2-dichloroethane
1,1,1-trichloroethane
carbon tetrachloride
bromodichloromethane
* {1,2-dichloropropane
2,3-dichloropropane
trans-1,3-dichloropropane
trichloroethylene
* {1,1,2-trichloroethane
chlorodibromomethane
cis-1,3-dichloropropane
* {bromoform
1,1,1,2-tetrachloroethane
* {tetrachloroethylene
1,1,2,2-tetrachloroethane
* {vinylchloride
dichlorodifluoro methane
chlorobenzene

VOLATILE NON-HALOGENATED

benzene
toluene
* {m-xylene . & chlorobenzene
p-xylene
o-xylene
ethylbenzene

PESTICIDES

ug/l

lindane
heptachlor
aldrin
heptachlor epoxide
dieldrin
endrin
o,p' DDT
p,p' DDT
methoxychlor
toxaphene
chlordane

HERBICIDES

2,4-D
2,4,5-TP (silvex)

OTHERS

RECEIVED

RUN NO. (S)

*Reported value represents total

JUN 21 1983

5/22/83

DATE REPORTED

SUFFOLK COUNTY DEPT.
HEALTH SERVICES

S.C. McLENDON, PE, LAB DIRECTOR

LETTER 116

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
15 HORSEBLOCK PLACE, FARMINGVILLE, N.Y. 11738
(516) 451-4633


| | | | |
|--------------------------------------------------|--------------------------|----------------------------------------------------------------|--------------------|
| NAME OF FACILITY | | OWNER/OFFICER <u>Mr. Ken Mitdaka</u> PAGE <u>1</u> OF <u>1</u> | |
| COMPANY NAME <u>Commercial Envelope Mfg. Co.</u> | | CONTACT <u>Mr. Ramon Tre-H2W</u> TEL. <u></u> | |
| PLANT ADDRESS <u>Grand Blvd.</u> | VILLAGE <u>Deer Park</u> | TOWN <u>Bab. N.Y.</u> | ZIP <u></u> |
| MAILING ADDRESS <u></u> | | | |
| DATE <u>Jan 3, 85</u> | TIME <u>9:30 AM</u> | ORIG. PERIODIC <u>RE</u> | WASTE <u>WASTE</u> |
| | | NO WASTE | H&H |
| | | SEWAGE SYSTEM | PUBLIC PRIVATE |

① CPC pump tanker → EPA# NYDO 82785429 NYS Lic 8030-PT.

②


#① Site of bubbling pool, (puddle).
filled to grade with liquid.

#② Solid covered pool, filled with
gray liquid approx 4-5 ft. below grade.
Pipe in NE corner approx. 6-8" iron
probable over flow to #③



#② observed 2nd 3-4" pipe
entering pool, approx. 5-6 ft below
grade, from NW direction.

#③ Removed cover, pool very deep
leaching pool, depth to liquid approx.
20 ft.



#② observed 3-4" pipe entering
pool, 5-6 ft (3rd)
below grade, from a SW direction,
approx. 20-40 gal of dark liquid entered the
pool from the pipe, but stopped after the
initial spurt.

③ Approx 10:30 CPC removed approx 3000 gal. from pool #②

④ CPC has removed the debris + sludge from around the "real off" dumpster
area + placed them in drums.

Jan. 3, 85

(5) Storm drain inside loading dock, liquid approx. 23 ft. below grade there appears to be 3x 3-4" pipes at liquid level. These pipes probable are overflow pipes to additional pools.

(6) Resample of storm drain in loading dock revealed a lead of $9 \pm 9 \text{ mg/l}$.

(7) CPC has removed $\approx 3000 \text{ gal.}$ from the leaching pool # (2),

Jan. 4, 85

(1) CPC has removed an additional 1500 gal. from pool # (2), and started to bucket sludge from the bottom, + 550 gal. of liquid sludge.

(2) CPC has removed + drained approx. 31 x 55 gal. drums of sludge + debris from around the compactor area. Over note additional liquid spilled from the compactor as Commercial Envelope workers to place ink + other liquids into the compactor. Immediately inside the compactor's door I observed several trash barrels, at least 2 has ink cans within the trash, the cans contained residue from ink.

(3) I delivered a notice to Mr. Alan Krystal a principal of Commercial Envelope. I read the notice to Mr. Krystal + explained to him particular parts of that notice. I had Mr. Krystal sign the notice + give him the original.

(4) Upon returning to the scene at approx 12:45 we observed that the industrial waste incinerator was in operation. I advised Mr. Joe G. Hall that Commercial had not Permit to operate the source.

CONTINUED: INSPECTORS OBSERVATIONS OR INTERVIEWS

Commercial
Enclosure



*① Leaching pool, contains (2) two 3-4" pipes entering the pool from a SW + NW direction, these two 3-4" pipes are approx 5-8 ft. below grade. There is a third pipe going in an East direction, the pipe is 3-4 ft below grade across 6-8" in radius.


INCUBATOR

← heading pools vent

← leaching pools vent

*③

Commercial Enclosure



*② Leaching pool #2: has liquid in it and is approx 20 ft. deep. There are pipes entering it from a Westerly direction, the pipe is 3-4 ft below grade + is 6-8" in radius.

*③ Storm drain in kitchen dock, unknown depth, pipe was placed in drain down approx 8 ft. - 3-4 ft of liquid the rest dark blue sludge. There are (3) three - 3-4 inch pipes in the East side of the drain, approx. 3-4 ft. below grade. These pipes are probably ventilation pipes. The liquid in the storm drain has dropped approx. 12-16" since first observed on the 3rd of Jan 85. in the AM.

CONTINUED: INSPECTORS OBSERVATIONS OR INTERVIEWS


Jan. 25, 85

Commercial Envelope Mfg. Corp.
Grand Blaine, New York.

- ① Loading dock over flow pumped down to sludge
- ② Overflow pool from ink pot wash machine pumped down to sludge.

Total of 2200 gals removed from both pools by
CPE

- ③ Sludge in ink pot wash discharge pool system was examined no obvious contamination. Sludge very thin not colored. Pool will be filled w with sand.



- ④ Loading dock storm drains over flow pool cement cap has been removed + pool widened + exposed. There are two 4-6" white piped entering pool side by side from the direction (West) of the visible loading dock storm drain.

There is sludge at the bottom of the pool which will be removed.

There are no other apparent overflow pipes from the excavated overflow pool. The pool is a typical leaching pool, approx. 20-25 ft. deep.


- ⑤ The garbage in the compactor still contains ink soaked rags + some empty ink cans, discolored water (pink) is standing in the loading dock.

Daniel O'J.

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
INDUSTRIAL WASTE AND HAZARDOUS MATERIALS CONTROL
15 HORSEBLOCK PLACE, FARMINGVILLE, N.Y. 11738
(516) 451-4633

| | | | | | |
|-----------------------------------------------------|--|------------------------------------------------|--|-------------------|--|
| NAME OF FACILITY | | OWNER/OFFICER | | PAGE ____ OF ____ | |
| COMPANY NAME: <u>Commercial Envelope Mfg. Corp.</u> | | CONTACT | | TEL. | |
| PLANT ADDRESS: <u>Grand Blvd</u> | | VILLAGE: <u>Deer Park</u> TOWN: <u>Bab. NY</u> | | ZIP | |
| MAILING ADDRESS | | | | | |

| | | | | | | | |
|------|------|--------------------|-------|----------|-----|---------------|----------------|
| DATE | TIME | ORIG. PERIODIC RE. | WASTE | NO WASTE | H&H | SEWAGE SYSTEM | PUBLIC PRIVATE |
|------|------|--------------------|-------|----------|-----|---------------|----------------|



REFERENCE NO. 4



PROJECT NOTE

TO: Commercial Envelope Mfg. Co., Inc. fileDATE: 27 June 1994FROM: J.D. HingsavageW.O. NO.: 04200-022-081-0006-02SUBJECT: Assorted groundwater monitoring information

Attached are letters and groundwater sampling results previously not included in either
the PA or SI

JDM



November 26, 1985

Mr. James Maloney, P.E.
Suffolk County Department of Health Services
15 Horseblock Place
Farmingville, New York 11738

Re: Commercial Envelope Manufacturing Company

Dear Mr. Maloney:

Pursuant to Condition 15 of an Order of Consent which is expected to be issued shortly, we are submitting herewith a proposal to determine the quality of ground water at selected locations beneath the Commercial Envelope Manufacturing Company, Inc. in Deer Park, New York. Specifically, the investigation will be directed toward determining whether activities at the site have caused a significant degradation of ground-water quality.

The direction of ground-water flow beneath the site is approximately south-southeast. The water table is estimated to be 25 to 35 feet below land surface. We plan to install three wells on the property, one upgradient and two downgradient of alleged contamination points. Proposed locations are shown on the accompanying sketch map. At this time, we see no reason to install wells off-site.

The wells will be installed by means of a hollow-stem auger rig and will consist of 1-1/4- or 2-inch diameter PVC casing and screen. Five feet of screen will be used in each well, with the top of the screen set several feet below the water table. Because the wells will be developed and sampled with a bailer, a five-foot section of casing will be attached to the bottom of the screen to serve as a sump.

The wells will be finished at land surface and equipped with protective steel casing and a locking meter box or equivalent to preventing unauthorized access. The tops of the casings will be surveyed to mean sea level; water-level measurements taken subsequently will be used to establish the elevation of the water table and the direction of ground-water flow.

Samples will be taken from the wells after three to five times the volume of water standing in the casing has been removed. The samples will be analyzed for volatile organic compounds (VOCs) by EPA method 624 and for selected metals. Analyses will be run for the following metals:

| <u>Metal</u> | <u>Detection Limit (mg/L)</u> |
|--------------|-------------------------------|
| Barium | 0.1 |
| Cadmium | 0.005 |
| Chromium | 0.02 |
| Copper | 0.02 |
| Iron | 0.02 |
| Lead | 0.05 |
| Nickel | 0.03 |
| Silver | 0.01 |
| Zinc | 0.01 |

Samples collected for metals analysis will be passed through a 0.45-micron filter upon collection, prior to preservation and transport to the laboratory.

The analytes selected represent constituents which are most commonly used at the plant site, according to findings of the SCDOHS. Although additional analytes might be considered, their presence exclusive of those given above is most unlikely; therefore, such analyses are unwarranted at this time.

It should be noted that, given the highly industrialized nature of the area, the existence of ground-water contamination is possible. Unless contamination levels are significantly higher in the downgradient wells than in the upgradient well, any such contamination should not be attributed to site activities.


If you have any questions regarding the preceding, please let us know.

Sincerely,

GERAGHTY & MILLER, INC.



Douglas R. MacCallum
Senior Scientist



Michael J. McEachern
Associate


cc: S. Cohen, Esq.

DRM/vk

Grav Blvd.

APPROXIMATE LOCATIONS OF
PROPOSED TEST WELLS

TW



Commercial Envelope Wdg. Co.
900 Grand Blvd. Deer Park, N.Y.

APPENDIX

A

PAGE 1 OF 1

ORDER ON CONSENT # _____

SCOUT LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. CB70378/1

03/16/87

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Andy Barber

SOURCE OF SAMPLE: Project #N0852WS1

COLLECTED BY: Client

DATE COL'D: 02/17/87 RECEIVED: 02/27/87

SAMPLE: Water sample, DP1

ANALYTICAL PARAMETERS

| | | |
|-----------------------|------|----|
| Chloromethane | ug/L | <1 |
| Bromomethane | ug/L | <1 |
| Dichlorodifluomethane | ug/L | <1 |
| Vinyl Chloride | ug/L | <1 |
| Chloroethane | ug/L | <1 |
| Methylene Chloride | ug/L | <2 |
| Trichlorofluomethane | ug/L | <2 |
| 11 Dichloroethene | ug/L | <2 |
| 11 Dichloroethane | ug/L | <2 |
| 12 Dichloroethene | ug/L | <2 |
| Chloroform | ug/L | <1 |
| 12 Dichloroethane | ug/L | <2 |
| 111 Trichloroethane | ug/L | 2 |
| Carbon Tetrachloride | ug/L | <1 |
| Bromodichloromethane | ug/L | <1 |
| 12 Dichloropropane | ug/L | <2 |
| 13 Dichloropropene | ug/L | <2 |
| Trichloroethylene | ug/L | <1 |
| Chlorodibromomethane | ug/L | <1 |
| 112 Trichloroethane | ug/L | <2 |
| c 13 Dichloropropene | ug/L | <2 |
| 2chloroethvinylether | ug/L | <2 |
| Bromoform | ug/L | <2 |
| 1122Tetrachloroethan | ug/L | <2 |
| Tetrachloroethane | ug/L | <1 |

ANALYTICAL PARAMETERS

| | | |
|--------------------|------|----|
| Chlorobenzene | ug/L | <1 |
| 13 Dichlorobenzene | ug/L | <2 |
| 12 Dichlorobenzene | ug/L | <2 |
| 14 Dichlorobenzene | ug/L | <2 |
| Benzene | ug/L | <1 |
| Toluene | ug/L | 5 |
| Ethyl Benzene | ug/L | <1 |

| | | |
|----------------|------|--------|
| Barium as Ba | mg/L | 0.10 |
| Cadmium as Cd | mg/L | 0.001 |
| Chromium as Cr | mg/L | <0.02 |
| Copper as Cu | mg/L | <0.02 |
| Iron as Fe | mg/L | <0.05 |
| Lead as Pb | mg/L | <0.005 |
| Nickel as Ni | mg/L | <0.10 |
| Silver as Ag | mg/L | <0.01 |
| Zinc as Zn | mg/L | 0.12 |

CC:

REMARKS:

DIRECTOR

2-23-87 TEST LABORATORIES INC

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. N. BAYLON, N.Y. 11703 (516) 422-5777

LAB NO. C870378/2

03/16/87

Geraghty & Miller, Inc.

125 East Bethpage Rd.

Plainview, NY 11803

ATTN: Andy Barber

SOURCE OF SAMPLE: Project #N0852WS1

COLLECTED BY: Client

DATE COL'D: 02/27/87 RECEIVED: 02/27/87

SAMPLE: Water sample, DP3

ANALYTICAL PARAMETERS

| | | |
|-----------------------|------|----|
| Chloromethane | ug/L | <1 |
| Bromomethane | ug/L | <1 |
| Dichlorodifluomethane | ug/L | <1 |
| Vinyl Chloride | ug/L | <1 |
| Chloroethane | ug/L | <1 |
| Methylene Chloride | ug/L | <2 |
| Trichlorofluomethane | ug/L | 11 |
| 11 Dichloroethene | ug/L | <2 |
| 11 Dichloroethane | ug/L | <2 |
| 12 Dichloroethene | ug/L | <2 |
| Chloroform | ug/L | <1 |
| 12 Dichloroethane | ug/L | <2 |
| 111 Trichloroethane | ug/L | <1 |
| Carbon Tetrachloride | ug/L | <1 |
| Bromodichloromethane | ug/L | <1 |
| 12 Dichloropropene | ug/L | <2 |
| t 13 Dichloropropene | ug/L | <2 |
| Trichloroethylene | ug/L | <1 |
| Chlorodibromomethane | ug/L | <1 |
| 112 Trichloroethane | ug/L | <2 |
| c 13 Dichloropropene | ug/L | <2 |
| 2chloroethvinylether | ug/L | <2 |
| Bromoform | ug/L | <2 |
| 1122Tetrachloroethan | ug/L | <2 |
| Tetrachloroethene | ug/L | 5 |

ANALYTICAL PARAMETERS

| | | |
|--------------------|------|----|
| Chlorobenzene | ug/L | <1 |
| 13 Dichlorobenzene | ug/L | <2 |
| 12 Dichlorobenzene | ug/L | <2 |
| 14 Dichlorobenzene | ug/L | <2 |
| Benzene | ug/L | <1 |
| Toluene | ug/L | <2 |
| Ethyl Benzene | ug/L | <1 |

cc:

REMARKS:

DIRECTOR

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C881533/1

07/21/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Douglas Newton

SOURCE OF SAMPLE: Job NY0985GW01, Deerpark, NY
COLLECTED BY: Client DATE COL'D: 06/29/88 RECEIVED: 06/29/88

SAMPLE: Water sample, DP-1

ANALYTICAL PARAMETERS

| | | |
|-----------------------|------|----|
| Chloromethane | ug/L | <1 |
| Bromomethane | ug/L | <1 |
| Dichlorodifluomethane | ug/L | <1 |
| Vinyl Chloride | ug/L | <1 |
| Chloroethane | ug/L | <1 |
| Methylene Chloride | ug/L | <2 |
| Trichlorofluomethane | ug/L | <2 |
| 11 Dichloroethene | ug/L | <2 |
| 11 Dichloroethane | ug/L | <2 |
| 12 Dichloroethene | ug/L | <2 |
| Chloroform | ug/L | <1 |
| 12 Dichloroethane | ug/L | <2 |
| 111 Trichloroethane | ug/L | <1 |
| Carbon Tetrachloride | ug/L | <1 |
| Bromodichloromethane | ug/L | <1 |
| 12 Dichloropropane | ug/L | <2 |
| t 13 Dichloropropene | ug/L | <2 |
| Trichloroethylene | ug/L | <1 |
| Chlorodibromomethane | ug/L | <1 |
| 112 Trichloroethane | ug/L | <2 |
| c 13 Dichloropropene | ug/L | <2 |
| 2chloroethvinylether | ug/L | <2 |
| Bromoform | ug/L | <2 |
| 1122Tetrachloroethan | ug/L | <2 |
| Tetrachloroethene | ug/L | <1 |

cc:

REMARKS:

ANALYTICAL PARAMETERS

| | | |
|--------------------|------|-------|
| Chlorobenzene | ug/L | <1 |
| 13 Dichlorobenzene | ug/L | <2 |
| 12 Dichlorobenzene | ug/L | <2 |
| 14 Dichlorobenzene | ug/L | <2 |
| Benzene | ug/L | <1 |
| Toluene | ug/L | <2 |
| Ethyl Benzene | ug/L | <1 |
| m Xylene | ug/L | <2 |
| o+p Xylene | ug/L | <4 |
| Barium as Ba | mg/L | <0.05 |
| Cadmium as Cd | mg/L | <0.00 |
| Chromium as Cr | mg/L | <0.00 |
| Copper as Cu | mg/L | <0.02 |
| Iron as Fe | mg/L | 0.05 |
| Lead as Pb | mg/L | <0.00 |
| Nickel as Ni | mg/L | <0.1 |
| Silver as Ag | mg/L | <0.00 |
| Zinc as Zn | mg/L | <0.02 |

RECEIVED
AT EA

NOV 27 1989

FILE NO. 52501

LJE FHI

GAR

MIC

DIRECTOR

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C881533/2

07/21/88

Geraghty & Miller, Inc.
125 East Bethpage Rd.
Plainview, NY 11803

ATTN: Douglas Newton

SOURCE OF SAMPLE: Job NY0985GW01, Deerpark, NY
COLLECTED BY: Client DATE COL'D: 06/29/88 RECEIVED: 06/29/88

SAMPLE: Water sample, DP-2

ANALYTICAL PARAMETERS

| | | |
|-------------------------|------|----|
| Chloromethane | ug/L | <1 |
| Bromomethane | ug/L | <1 |
| Dichlorodifluoromethane | ug/L | <1 |
| Vinyl Chloride | ug/L | <1 |
| Chloroethane | ug/L | <1 |
| Methylene Chloride | ug/L | <2 |
| Trichlorofluoromethane | ug/L | <2 |
| 11 Dichloroethene | ug/L | <2 |
| 11 Dichloroethane | ug/L | <2 |
| 12 Dichloroethene | ug/L | 17 |
| Chloroform | ug/L | <1 |
| 12 Dichloroethane | ug/L | <2 |
| 111 Trichloroethane | ug/L | <1 |
| Carbon Tetrachloride | ug/L | <1 |
| Bromodichloromethane | ug/L | <1 |
| 12 Dichloropropane | ug/L | <2 |
| t 13 Dichloropropene | ug/L | <2 |
| Trichloroethylene | ug/L | 4 |
| Chlorodibromomethane | ug/L | <1 |
| 112 Trichloroethane | ug/L | <2 |
| c 13 Dichloropropene | ug/L | <2 |
| 2chloroethvinylether | ug/L | <2 |
| Bromoform | ug/L | <2 |
| 1122Tetrachloroethan | ug/L | <2 |
| Tetrachloroethene | ug/L | 32 |

ANALYTICAL PARAMETERS

| | | |
|--------------------|------|--------|
| Chlorobenzene | ug/L | <1 |
| 13 Dichlorobenzene | ug/L | <2 |
| 12 Dichlorobenzene | ug/L | <2 |
| 14 Dichlorobenzene | ug/L | <2 |
| Benzene | ug/L | <1 |
| Toluene | ug/L | <2 |
| Ethyl Benzene | ug/L | <1 |
| m Xylene | ug/L | <2 |
| o+p Xylene | ug/L | <4 |
| Barium as Ba | mg/L | <0.05 |
| Cadmium as Cd | mg/L | <0.001 |
| Chromium as Cr | mg/L | <0.005 |
| Copper as Cu | mg/L | <0.02 |
| Iron as Fe | mg/L | 17 |
| Lead as Pb | mg/L | <0.005 |
| Nickel as Ni | mg/L | <0.1 |
| Silver as Ag | mg/L | <0.001 |
| Zinc as Zn | mg/L | <0.02 |

cc:

REMARKS:

DIRECTOR

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C891533/3

07/21/88

Geraghty & Miller, Inc.
125 East Bathpage Rd.
Plainview, NY 11803

ATTN: Douglas Newton

SOURCE OF SAMPLE: Job NY0985GW01, Deerpark, NY
COLLECTED BY: Client DATE COL'D: 06/29/88 RECEIVED: 06/29/88

SAMPLE: Water sample, DP-3

ANALYTICAL PARAMETERS

| | | |
|-----------------------|------|----|
| Chloromethane | ug/L | <1 |
| Bromomethane | ug/L | <1 |
| Dichlorodifluomethane | ug/L | <1 |
| Vinyl Chloride | ug/L | <1 |
| Chloroethane | ug/L | <1 |
| Methylene Chloride | ug/L | <2 |
| Trichlorofluomethane | ug/L | <2 |
| 11 Dichloroethene | ug/L | <2 |
| 11 Dichloroethane | ug/L | <2 |
| 12 Dichloroethene | ug/L | <2 |
| Chloroform | ug/L | <1 |
| 12 Dichloroethane | ug/L | <2 |
| 111 Trichloroethane | ug/L | <1 |
| Carbon Tetrachloride | ug/L | <1 |
| Bromodichloromethane | ug/L | <1 |
| 12 Dichloropropane | ug/L | <2 |
| t 13 Dichloropropene | ug/L | <2 |
| Trichloroethylene | ug/L | <1 |
| Chlorodibromomethane | ug/L | <1 |
| 112 Trichloroethane | ug/L | <2 |
| c 13 Dichloropropene | ug/L | <2 |
| 2chloroethvinylether | ug/L | <2 |
| Bromoform | ug/L | <2 |
| 1122Tetrachloroethan | ug/L | <2 |
| Tetrachloroethene | ug/L | <1 |

ANALYTICAL PARAMETERS

| | | |
|--------------------|------|-------|
| Chlorobenzene | ug/L | <1 |
| 13 Dichlorobenzene | ug/L | <2 |
| 12 Dichlorobenzene | ug/L | <2 |
| 14 Dichlorobenzene | ug/L | <2 |
| Benzene | ug/L | <1 |
| Toluene | ug/L | <2 |
| Ethyl Benzene | ug/L | <1 |
| m Xylene | ug/L | <2 |
| o+p Xylene | ug/L | <4 |
| Barium as Ba | mg/L | 0.31 |
| Cadmium as Cd | mg/L | <0.00 |
| Chromium as Cr | mg/L | <0.00 |
| Copper as Cu | mg/L | <0.00 |
| Iron as Fe | mg/L | 0.05 |
| Lead as Pb | mg/L | <0.00 |
| Nickel as Ni | mg/L | <0.1 |
| Silver as Ag | mg/L | <0.00 |
| Zinc as Zn | mg/L | <0.00 |

cc:

REMARKS:

DIRECTOR 

REFERENCE NO. 5



PROJECT NOTE

TO: Commercial Envelope Mfg. Co., Inc. fileDATE: 28 June 1994FROM: D.D. MinsavageW.O. NO.: 09200-022-081-00016-02SUBJECT: Assorted sampling results

Attached are various (unrelated) sampling results which were not previously included in either the PA or SI.


DDM

COUNTY OF SUFFOLK



PETER F. COHALAN
SUFFOLK COUNTY EXECUTIVE

DEPARTMENT OF HEALTH SERVICES

DAVID HARRIS, M.D., M.P.H.
COMMISSIONER

CERTIFIED MAIL-R.R.R.
P 623 150 306

March 27, 1986

Commercial Envelope
900 Grand Boulevard
Deer Park, New York 11729

Attention: Ira B. Kristel, President

Gentlemen:

This correspondence is to inform you that on February 27, 1986, a representative of this department secured soil samples approximately two (2) feet below grade, in the area where excavation is being accomplished on the west side of the building.

Review of the laboratory results showed that the following metal compounds are in excess of existing groundwater standards and guidelines:

| | | | |
|--------------|-----------|--------|-----------|
| Copper | 865.0 ppm | Nickel | 25.0 ppm |
| Chromium-Tot | 37.0 ppm | Lead | 166.0 ppm |

These unsatisfactory conditions constitute violations of the New York State Environmental Conservation Law and Article 12 of the Suffolk County Sanitary Code promulgated to reduce groundwater contamination. Under the Suffolk County Sanitary Code, you may be subject to the imposition of a \$500 civil penalty for each day that these contaminants are allowed to leach out of the sanitary system. Please be advised that these compounds are considered hazardous and toxic and should not have been discharged to the ground or any sanitary or storm drain leaching pools. Said contaminated soil should be transported and disposed of only by an approved licensed industrial waste hauler. Therefore, it is expected that an immediate evaluation of your waste disposal practices be initiated to prevent further unpermitted discharges.

(continued . . .)

002

Commercial Envelope
March 27, 1986
Page 2

Furthermore, due to the excessive nature of this discharge, you are directed to have any liquids, solids and contaminated soil excavated and removed by an industrial waste hauler by April 18, 1986. A list of approved scavengers may be obtained by contacting the Solid Waste Section of the New York State Department of Environmental Conservation located at the State University at Stony Brook, New York, telephone number 516-751-7900. Kindly notify this office three (3) working days in advance of the clean-up date so that one of our representatives may be present.

Since an industrial waste generator's permit may be required before clean-up is accomplished, you should immediately contact the U.S.E.P.A., Permit Administration Branch Region 2, Room 432, 26 Federal Plaza, New York, New York 10278, or by telephoning 212-264-9881 to expedite your request so that this department's directive could be executed within the time frame allotted.

We wish to express our deep concern regarding this discharge and that it is most important that you act expeditiously in eliminating this practice.

Very truly yours,



D. C. Gobbi
Bureau of Environmental Pollution Control

DCG/lc

NOTICE OF VIOLATION
COUNTY OF SUFFOLK



CERTIFIED MAIL - R.R.R.

PETER F. COHALAN
SUFFOLK COUNTY EXECUTIVE

DEPARTMENT OF HEALTH SERVICES

Commercial Envelope Mfg. Corp.
900 Grand Blvd.
Deer Park, New York 11729

Date January 15, 1985

SPDES NO. _____

Lab. No. IW-1084031

Field No. I-DO-10-24

ATTENTION: Mr. Ira Krystel, President

Gentlemen:

On 10/24/84 samples of industrial waste were taken from your SURFACE OF LIQUID DISCHARGING UP THRU GROUND SURFACE, PURPLE/GRAY IN COLOR, ACTIVE FLOW. Upon analysis, the following parameters were found in concentrations above the maximum allowed in your SPDES Permit or in groundwater effluent standards:


| | | | |
|-----------------------|---------|----------------------------|---------|
| 1. Methylene Chloride | 930 ppb | 6. Xylene(s) | 310 ppb |
| 2. p-Ethyltoluene | 120 ppb | 7. 1,3,5 Trimethylbenzene | 78 ppb |
| 3. n-Decane | 87 ppb | 8. 1,2,4 Trimethylbenzene | 170 ppb |
| 4. n-Undecane | 100 ppb | 9. p-Diethylbenzene | 50 ppb |
| 5. Toluene | 580 ppb | 10. Methyl-Isobutyl Ketone | 270 ppb |

Please be advised that these unsatisfactory conditions constitute violations of the N.Y.S. Environmental Conservation Law and/or the Suffolk County Sanitary Code. Please be further advised that the discharge of any water from an industrial process to the groundwater of Suffolk County without having first obtained a State Pollutant Discharge Elimination System (SPDES) Permit for that discharge is also a violation of the N.Y.S. E.C.L. and/or the Suffolk County Sanitary Code, Article 12.

If you do not already possess a valid SPDES Permit for the above discharge, then you should apply immediately through this office for said permit.

Since the above-noted violations may subject you to legal action, it is expected that these violations cease immediately. Violations of the Suffolk County Sanitary Code are subject to the imposition of a civil penalty of up to Five Hundred (\$500) dollars per violation. E.C.L. violations are also subject to a civil penalty. A reinspection in the near future will determine your compliance in this matter.

Very truly yours,


John H. Finkenberg, Sr. Sanitarian
Environmental Pollution Control

15 Horseblock Pl. (SEE REVERSE SIDE FOR STANDARDS)
Farmingville, NY 11738

(516) 451-4628

004

1W-1084031
10-24-84 By FA
NO. 10010/24

DATE COMPLETED 12-21-84
EXAMINED BY K. J. J. J.
E.R.C. 1/4/85 O.C.

SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
DIVISION OF MEDICAL LEGAL INVESTIGATIONS & FORENSIC SCIENCES
PUBLIC HEALTH LABORATORY

TRACE ORGANIC ANALYSIS OF INDUSTRIAL WASTE

Name Commercial Envelope Mfg Co.

Location Grand Blvd. Deer Park, NY

Point of Collection surface of liquid discharge on three ground

Remarks: surface, purple/gray in color, active 24 hr

| Compound | ppb | Compound | ppb |
|--------------------------------|-----|---------------------------------|-----|
| Methylene Chloride..... | 930 | Cis Dichloroethylene..... | 216 |
| Freon 113..... | 24 | Benzene..... | 219 |
| Chloroform..... | 25 | Toluene..... | 280 |
| 1,1,1 Trichloroethane..... | 22 | Chlorobenzene..... | 212 |
| Carbon Tetrachloride..... | 21 | Ethylbenzene..... | 36 |
| 1,1,2 Trichloroethylene..... | 25 | Xylene(s)..... | 210 |
| Bromodichloromethane..... | 23 | Bromobenzene..... | 216 |
| 1,1,2 Trichloroethane..... | 25 | Chlorotoluene(s)..... | 212 |
| Chlorodibromomethane..... | 26 | 1,3,5 Trimethylbenzene..... | 72 |
| Tetrachloroethylene..... | 32 | 1,2,4 Trimethylbenzene..... | 170 |
| Bromoform..... | 25 | m,p-Dichlorobenzene..... | 216 |
| 1,1,2,2 Tetrachloroethane..... | 24 | o-Dichlorobenzene..... | 216 |
| Octane..... | 240 | p-Diethylbenzene..... | 50 |
| Styrene..... | 210 | 1,2,4,5 Tetramethylbenzene..... | 28 |
| n-Nonane..... | 240 | 1,2,4 Trichlorobenzene..... | 212 |
| p-Ethyltoluene..... | 120 | 1,2,3 Trichlorobenzene..... | 212 |
| n-Decane..... | 25 | | |
| n-Undecane..... | 100 | | |
| | | Methyl Isobutyl Ketone..... | 270 |

MAXIMUM TESTING

During transport of the sample from collection point to laboratory, the chain of custody must not be broken. The sample should be delivered by the sample collector or a designated representative who will sign for the receipt, integrity, and transfer of the sample during shipment.

| | SIGNATURE | AFFILIATION | DATE | TIME |
|-------------------|--------------------|-------------|----------|----------|
| 1. Collected by | | | | |
| 2. Transferred to | Francis G. Arinola | SCPHS-PHC | 10-24-84 | 12:40 AM |
| 3. Transferred to | | | | |
| 4. Transferred to | | | | |

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. CB71959

09/29/87

Chemical Management Inc.
340 Eastern Parkway
Farmingdale, NY 11735

ATTN: Jack Leibel

SOURCE OF SAMPLE: Commercial Envelope

COLLECTED BY: Client

DATE COL'D:

RECEIVED: 09/11/87

SAMPLE: Liquid waste, composite of "2" & "3"

ANALYTICAL PARAMETERS

| | | |
|--------------------|-------|--------|
| % Solids | | 42.0 |
| % Suspended Solids | | 42.0 |
| % Dissolved Solids | | <0.1 |
| % Ash | | 2.2 |
| Specific Gravity | | 1.1 |
| pH | units | 8.1 |
| Flash Point | deg C | >87* |
| COD | mg/Kg | 110000 |
| Oil and Grease | mg/Kg | 4200 |
| Phenols as Phenol | mg/Kg | 29 ppb |
| Cyanide as CN | mg/Kg | <2 |
| Fluoride as F | mg/Kg | <16 |
| Aluminum as Al | mg/Kg | 1100 |
| Arsenic as As | mg/Kg | <0.15 |
| Barium as Ba | mg/Kg | 140 |
| Cadmium as Cd | mg/Kg | 0.10 |
| Chromium as Cr | mg/Kg | 120 |
| Copper as Cu | mg/Kg | 550 |
| Iron as Fe | mg/Kg | 60 |
| Lead as Pb | mg/Kg | 300 |
| Mercury as Hg | mg/Kg | 0.052 |
| Nickel as Ni | mg/Kg | 0.50 |
| Selenium as Se | mg/Kg | 0.13 |
| Silver as Ag | mg/Kg | 0.15 |

ANALYTICAL PARAMETERS

| | | |
|------------|-------|-----|
| Tin as Sn | mg/Kg | 1.2 |
| Zinc as Zn | mg/Kg | 130 |

cc:

REMARKS: *Sample boiled at 87 degrees C without flashing.
Page 1 of 2.

DIRECTOR

COTEST LABORATORIES, INC.**ENVIRONMENTAL TESTING****377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777**

LAB NO: C871959

09/29/87

Chemical Management, Inc.

340 Eastern Parkway

Farmingdale, NY 11735

ATTN: Jack Leibel

SOURCE OF SAMPLE: Commercial Envelope (metals by eptox)

COLLECTED BY: Client

DATE COL'D:

RECEIVED: 09/11/87

SAMPLE: EP Extract of liquid waste

ANALYTICAL PARAMETERS

| | | |
|--------------------|-------|--------|
| Aluminum as Al | mg/L* | 0.095 |
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 0.75 |
| Cadmium as Cd | mg/L* | <0.001 |
| Chromium hex as Cr | mg/L* | <0.02 |
| Chromium as Cr | mg/L* | 0.41 |
| Copper as Cu | mg/L* | 0.22 |
| Iron as Fe | mg/L* | 0.16 |
| Lead as Pb | mg/L* | 0.63 |
| Mercury as Hg | mg/L* | <0.001 |
| Nickel as Ni | mg/L* | <0.10 |
| Selenium as Se | mg/L* | <0.005 |
| Silver as Ag | mg/L* | <0.01 |
| Tin as Sn | mg/L* | <0.05 |

ANALYTICAL PARAMETERS

cc:

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).


Page 2 of 2.

DIRECTOR

rn=


6941

007



eder associates
consulting engineers, p.c.

November 1, 1988
File #525-1



Ms. Tanya Hermos
New York State Department
of Environmental Conservation
SUNY - Building 40
Stonybrook, New York 11794

Dear Ms. Hermos:

Enclosed please find the laboratory results for drum sampling at the Commercial Envelope facility in Deer Park, New York. All samples are composites of four or five drums each, and are made up as follows:

| | |
|----------------|---------|
| Composite A | 5 Drums |
| Composite B | 5 Drums |
| Composite C | 5 Drums |
| Composite D | 5 Drums |
| Composite E | 5 Drums |
| Composite DS-A | 4 Drums |
| Composite DS-B | 4 Drums |
| Composite DS-C | 4 Drums |
| Composite DS-D | 4 Drums |
| Composite E-2 | 5 Drums |

If you have any further questions, feel free to call me at (516) 671-8440.

Very truly yours,

EDER ASSOCIATES CONSULTING ENGINEERS, P.C.

Nicholas A. Andrianas, P.E.
Senior Project Manager

NAA/cj
Enc.

cc: S. Kristel

#4825C

008

85 FOREST AVENUE • LOCUST VALLEY, NEW YORK 11560 • (516) 671-8440
2317 INTERNATIONAL LANE • MADISON, WISCONSIN 53704 • (608) 244-8885

LEONARD J. EDER, P. E. • FREDERICK H. INYARD, P. E. • STEPHEN J. OSMUNDSEN, P. E. • GARY A. ROZMUS, P. E.
JOHN MCGUIRE, P. E. • JORGE MOLINA, ING. • WILLIAM J. CUNNINGHAM, P. E. • JOSEPH B. HELLMANN, P. E.

ECOTEST LABORATORIES, INC.**ENVIRONMENTAL TESTING****377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777**

LAB NO. C082060/1

09/27/88

Commercial Envelope Mfg. Co. Inc.
900 Grand Blvd.
Deer Park, NY 11729
ATTN: Steven Kristel

PO# CE 19918

SOURCE OF SAMPLE: Same as above (eptox metals)
COLLECTED BY: Client DATE COL'D: 08/31/88 RECEIVED: 08/31/88

SAMPLE: Ink waste comp A, drum storage

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | 0.009 |
| Barium as Ba | mg/L* | 27 |
| Cadmium as Cd | mg/L* | 0.040 |
| Chromium as Cr | mg/L* | 0.30 |
| Lead as Pb | mg/L* | 1.3 |
| Mercury as Hg | mg/L* | <0.001 |
| Selenium as Se | mg/L* | 0.005 |
| Silver as Ag | mg/L* | 0.46 |
| Cyanide as CN | mg/L | <2 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >95** |
| pH | units | 7.2 |


ANALYTICAL PARAMETERS

cc: Jim Valenti, Eder Assoc.

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).
**Sample boiled at 95 degrees C, with no flash.

009

DIRECTOR



ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C882060/2

09/27/88

Commercial Envelope Mfg. Co. Inc.

900 Grand Blvd.

Deer Park, NY 11729

ATTN: Steven Kristel

PO# CE 19910

SOURCE OF SAMPLE: Same as above (leptox metals)
COLLECTED BY: Client DATE COL'D: 08/31/88 RECEIVED: 08/31/88

SAMPLE: Ink waste comp B, drum storage

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 7.3 |
| Cadmium as Cd | mg/L* | 0.25 |
| Chromium as Cr | mg/L* | 0.33 |
| Lead as Pb | mg/L* | 0.21 |
| Mercury as Hg | mg/L* | <0.001 |
| Selenium as Se | mg/L* | <0.025 |
| Silver as Ag | mg/L* | 0.04 |

| | | |
|---------------|-------|-------|
| Cyanide as CN | mg/L | <2 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >94** |
| pH | units | 4.9 |


ANALYTICAL PARAMETERS

cc: Jim Valenti, Eder Assoc.

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).
**Sample boiled at 94 degrees C, with no flash.

010

DIRECTOR



ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C882040/3

09/27/88

Commercial Envelope Mfg. Co. Inc.

900 Grand Blvd.

Deer Park, NY 11729

ATTN: Steven Kristel

PO# CE 19918

SOURCE OF SAMPLE: Same as above (leptox metals)
COLLECTED BY: Client DATE COL'D: 08/31/88 RECEIVED: 08/31/88

SAMPLE: Ink waste comp C, drum storage

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 0.5 |
| Cadmium as Cd | mg/L* | 0.36 |
| Chromium as Cr | mg/L* | 0.27 |
| Lead as Pb | mg/L* | 1.0 |
| Mercury as Hg | mg/L* | 0.001 |
| Selenium as Se | mg/L* | <0.025 |
| Silver as Ag | mg/L* | 0.04 |

| | | |
|---------------|-------|-------|
| Cyanide as CN | mg/L | <2 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >90** |
| pH | units | 4.9 |


ANALYTICAL PARAMETERS

cc: Jim Valenti, Eder Assoc.

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).
**Sample boiled at 90 degrees C, with no flash.

011

DIRECTOR



ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C882060/4

07/27/88

Commercial Envelope Mfg. Co. Inc.

900 Grand Blvd.

Deer Park, NY 11729

ATTN: Steven Kristel

PO# CE 19918

SOURCE OF SAMPLE: Same as above (leptox metals)
COLLECTED BY: Client DATE COL'D: 08/31/88 RECEIVED: 08/31/88

SAMPLE: Ink waste comp D, drum storage

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 0.72 |
| Cadmium as Cd | mg/L* | 0.002 |
| Chromium as Cr | mg/L* | 0.02 |
| Lead as Pb | mg/L* | <0.01 |
| Mercury as Hg | mg/L* | <0.001 |
| Selenium as Se | mg/L* | <0.005 |
| Silver as Ag | mg/L* | <0.01 |

| | | |
|---------------|-------|-------|
| Cyanide as CN | mg/Kg | <2 |
| Sulfide as S | mg/Kg | <2 |
| Flash Point | deg C | >64** |
| pH | units | 6.0 |


ANALYTICAL PARAMETERS

cc: Jim Valenti, Eder Assoc.

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).
**Sample boiled at 64 degrees C, with no flash.

012

DIRECTOR



ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C082060/5

09/27/88

Commercial Envelope Mfg. Co. Inc.

900 Grand Blvd.

Deer Park, NY 11729

ATTN: Steven Kristel

PO# CE 19918

SOURCE OF SAMPLE: Same as above (leptox metals)
COLLECTED BY: Client DATE COL'D: 08/31/88 RECEIVED: 08/31/88

SAMPLE: Ink waste comp E, drum storage

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|---------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 0.18 |
| Cadmium as Cd | mg/L* | 0.17 |
| Chromium as Cr | mg/L* | 870 |
| Lead as Pb | mg/L* | 0.13 |
| Mercury as Hg | mg/L* | 0.00095 |
| Selenium as Se | mg/L* | <0.025 |
| Silver as Ag | mg/L* | 0.03 |

| | | |
|---------------|-------|-------|
| Cyanide as CN | mg/L | <2 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >94** |
| pH | units | 3.9 |

ANALYTICAL PARAMETERS

cc: Jim Valenti, Eder Assoc.

REMARKS: *Analysis performed on EP Extract according to USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).
**Sample boiled at 94 degrees C, with no flash.

013

DIRECTOR

James R. Spurr

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C882153/1

10/07/88

Commercial Envelope Mfg. Co., Inc.
900 Grand Blvd.
Deer Park, NY 11729
ATTN: Steven Kristel

PO# 20100

SOURCE OF SAMPLE: Project # 525-1 (eptox metals)
COLLECTED BY: Client DATE COL'D: RECEIVED: 09/13/88

SAMPLE: Drum comp. XA

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 0.39 |
| Cadmium as Cd | mg/L* | 0.014 |
| Chromium as Cr | mg/L* | 0.98 |
| Lead as Pb | mg/L* | 0.032 |
| Mercury as Hg | mg/L* | 0.0023 |
| Selenium as Se | mg/L* | <0.005 |
| Silver as Ag | mg/L* | <0.01 |
| Cyanide as CN | mg/L | 27 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >80** |
| pH | units | 4.5 |

ANALYTICAL PARAMETERS

| | |
|-------------|-----|
| OCT 12 1988 | |
| FILE NO. | |
| LVE | FHI |
| SJO | GAR |
| WJC | |
| OTHER | JEV |

cc: Eder Assoc., James Valenti

REMARKS: *Analysis performed on EP Extract according to USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).
**Sample boiled at 80 degrees C, with no flash.

014

DIRECTOR

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C882153/2

10/07/88

Commercial Envelope Mfg. Co., Inc.
900 Grand Blvd.

Deer Park, NY 11729

ATTN: Steven Kristel

PO# 20100

SOURCE OF SAMPLE: Project # 525-1

(eptox metals)

COLLECTED BY: Client DATE COL'D:

RECEIVED: 09/13/88

SAMPLE: Drum comp. 5B

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 0.24 |
| Cadmium as Cd | mg/L* | <0.001 |
| Chromium as Cr | mg/L* | 0.05 |
| Lead as Pb | mg/L* | 0.12 |
| Mercury as Hg | mg/L* | <0.001 |
| Selenium as Se | mg/L* | <0.005 |
| Silver as Ag | mg/L* | <0.01 |

| | | |
|---------------|-------|------|
| Cyanide as CN | mg/L | <2 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >100 |
| pH | units | 5.0 |

ANALYTICAL PARAMETERS

cc: Eder Assoc., James Valenti

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).

015

DIRECTOR

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C882153/3

10/07/88

Commercial Envelope Mfg. Co., Inc.
900 Grand Blvd.
Deer Park, NY 11729

ATTN: Steven Kristel

PO# 20100

SOURCE OF SAMPLE: Project # 525-1 (eptox metals)
COLLECTED BY: Client DATE COL'D: RECEIVED: 09/13/88

SAMPLE: Drum comp. SC

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | 0.30 |
| Cadmium as Cd | mg/L* | 0.046 |
| Chromium as Cr | mg/L* | 0.06 |
| Lead as Pb | mg/L* | 0.050 |
| Mercury as Hg | mg/L* | 0.0027 |
| Selenium as Se | mg/L* | <0.005 |
| Silver as Ag | mg/L* | 0.01 |

| | | |
|---------------|-------|------|
| Cyanide as CN | mg/L | <2 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >100 |
| pH | units | 9.2 |


ANALYTICAL PARAMETERS

cc: Eder Assoc., James Valenti

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen.II).

016

DIRECTOR



rn=

8716

ECOTEST LABORATORIES, INC.

ENVIRONMENTAL TESTING

377 SHEFFIELD AVE. • N. BABYLON, N.Y. 11703 • (516) 422-5777

LAB NO. C882153/4

10/07/88

Commercial Envelope Mfg. Co., Inc.
900 Grand Blvd.

Deer Park, NY 11729
ATTN: Steven Kristel

PO# 20100

SOURCE OF SAMPLE: Project # 525-1
COLLECTED BY: Client DATE COL'D: (eptox metals)
RECEIVED: 09/13/88

SAMPLE: Drum comp. SD

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | <0.05 |
| Cadmium as Cd | mg/L* | 0.022 |
| Chromium as Cr | mg/L* | 0.05 |
| Lead as Pb | mg/L* | 0.014 |
| Mercury as Hg | mg/L* | 0.0018 |
| Selenium as Se | mg/L* | <0.005 |
| Silver as Ag | mg/L* | <0.01 |

| | | |
|---------------|-------|------|
| Cyanide as CN | mg/L | <2 |
| Sulfide as S | mg/L | <2 |
| Flash Point | deg C | >100 |
| pH | units | 8.1 |

ANALYTICAL PARAMETERS

cc:Eder Assoc., James Valenti

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen.II).

017

DIRECTOR

rn=

8717

EcoTest Laboratories Inc
377 Sheffield Ave
North Babylon NY 11703
516 422-5777

LAB NO. C882352

10/25/88

Eder Associates, Consulting Engineers P.C
85 Forest Avenue
Locust Valley, NY 11560

ATTN:

SOURCE OF SAMPLE: Commercial Envelope
COLLECTED BY: Client DATE COL'D:

RECEIVED: 10/04/88

SAMPLE: Drums 21-25, comp E-2

ANALYTICAL PARAMETERS

| | | |
|----------------|-------|--------|
| Arsenic as As | mg/L* | <0.005 |
| Barium as Ba | mg/L* | <0.05 |
| Cadmium as Cd | mg/L* | 0.007 |
| Chromium as Cr | mg/L* | 20 |
| Lead as Pb | mg/L* | 0.70 |
| Mercury as Hg | mg/L* | <0.001 |
| Selenium as Se | mg/L* | <0.005 |
| Silver as Ag | mg/L* | <0.01 |

| | | |
|---------------|-------|-----|
| Cyanide as CN | mg/L | 28 |
| Sulfide as S | mg/L | 3.2 |
| Flash Point | deg C | 58 |
| pH | units | 4.0 |

ANALYTICAL PARAMETERS

cc:

REMARKS: *Analysis performed on EP Extract according to
USEPA EP Toxicity procedure (40 CFR Part 261-Appen. II).

REFERENCE NO. 6



PROJECT NOTE

TO: Commercial Envelope Mfg. Co., Inc. fileDATE: 28 June 1994FROM: D. D. MinsavageW.O. NO.: 04200-022-081-0006-02SUBJECT: CEM's incinerator.

Attached are several documents referring to CEM's on site incinerator and its use in disposing of/destrating waste water.

February 20, 1986:
File #525-1



eder associates
consulting engineers, p.c.

Mr. Joseph Fichera
New York State Department
of Environmental Conservation
Building 40
SUNY
Stony Brook, New York 11794

RECEIVED
FEB 21 1986
SOLID WASTE MANAGEMENT
DEC REGION I

Re: Commercial Envelope Manufacturing Company
Deer Park, New York

Dear Mr. Fichera:

Commercial Envelope Manufacturing Company (CEM) is engaged in the business of producing and printing envelopes. An industrial wastewater is generated and incinerated on-site.

In April 1985, CEM filed a "Process, Exhaust or Ventilation System Application For a Certificate to Operate" the on-site incinerator. The application was submitted to the Suffolk County Department of Health Services (SCDHS) for review and approval.

I am enclosing an evaluation of CEM's wastewater streams which indicates that they are not hazardous within the meaning and intent of New York regulations. If NYSDEC concurs, CEM should be allowed to use the on site incinerator to dispose of its wastewater.

I am now requesting that NYSDEC review the attached documentation and determine whether: 1) the wastewater is a hazardous waste; and 2) whether a Part 370 Permit is required for the incinerator.

Please advise me of your decision in writing.

If you have any questions, please contact our office.

Thank you for your cooperation and timely response to this question.

Very truly yours,

EDER ASSOCIATES CONSULTING ENGINEERS, P.C.

Nicholas A. Andrianas
Project Engineer

NAA/tg
Attmt.

cc: S. Cohen
J. Williams

85 FOREST AVENUE • LOCUST VALLEY, NEW YORK 11560 • (516) 671-8440

LEONARD J. EDER, P. E. • FREDERICK H. INYARD, P. E. • STEPHEN J. OSMUNDSEN, P. E. • GARY A. ROZMUS, P. E.
JOHN MCGUIRE, P. E. • JORGE MOLINA, ING. • WILLIAM J. CUNNINGHAM, P. E. • JOSEPH B. HELLMANN, P. E.

002

ATTACHMENT A

Eder Associates' review of Commercial Envelope Manufacturing Company (CEM) operations supplemented by chemical data furnished by others indicates that wastewater generated at the facility is not hazardous.

Wastewater Generation and Storage

CEM produces and prints envelopes. The majority of inks utilized at the facility are water based. A small percentage of alcohol (ethanol) based inks are also used. There are two sources of wastewater at the CEM facility: 1) the printing equipment wash stations; and 2) the developing and plate making rooms. The printing equipment wash stations are mainly used to clean equipment when changing ink colors and include two wash sinks and an ink pot washing machine. Ink pots and printing equipment are washed with water at these stations. The ink pots and printing equipment are rinsed with ethanol when alcohol based inks are used. The washwater is pumped to a 2,000 gallon aboveground holding tank in the plant. The washwater is pumped to the incinerator on a batch basis.

The facility uses water based glues. Glue rollers are washed with water at the glue machines. This washwater is collected in small containers and manually transferred to the printing equipment wash stations, from which it is pumped to the 2,000 gallon wastewater holding tank.

Wastewater generated by rinsing operations in the plate making and developing rooms consists mainly of water with traces of inorganic salts, polymer, detergent and isopropyl alcohol. These constituents are derived from the plate making developer and gum raw materials. The wastewater drains by gravity to a collection sump in the plate making room. An automatic sump pump transfers the wastewater to the 2,000 gallon holding tank.

Wastewater Sampling

Representative wastewater samples from the 2,000 gallon holding tank were collected by H2M/Holzmacher, McLendon and Murrell P.C. (Melville, New York) during December 1984 and February 1985. According to plant personnel, the processes generating the wastewater have not been changed since the samples were collected. Therefore, the samples would be representative of wastewater presently generated and stored in the 2,000 gallon holding tank.

Wastewater Characterization

The waste generation processes were reviewed to determine whether the waste is a listed waste as defined in Section 371.4 of 6NYCRR part 371 "Identification and Listing of Hazardous Wastes" or a mixture of a solid waste and a listed waste as defined in Section 371.1 (d)(1)(ii)(c) and (d). The wastewater generated at the site is not a listed waste. The EP toxic metals which characterize raw materials and waste are limited to cadmium, chromium, lead and silver.

Although the wastewater is not a listed hazardous waste, it could be hazardous if it exhibits the waste characteristics defined in Section 371.3. The samples collected by H2M were analyzed by the H2M Laboratory. The parameters that were analyzed included the EP toxic metals present in the wastewater and pH. Based on the nature of the processes generating the waste, the wastewater should not exhibit the characteristics of ignitability or reactivity, and these characteristics were not evaluated.

The results of the EP toxicity tests and pH analyses are presented in Table 1. Documentation of the laboratory analyses is enclosed with this attachment. The wastewater sample is identified on the December 4, 1984 laboratory report as Sample ID No. 2 "Tank Waste". Samples identified as ID No. 1, "Developer Rinse" and ID No. 3, "Wash Station" are samples of the wastewaters that are transferred to and stored in

the 2,000 gallon wastewater holding tank. The wastewater samples are identified as "Wastewater Holding Tank" on each of the February 1985 laboratory reports. Based on the test results in Table 1, the wastewater is neither an EP toxic, nor a corrosive hazardous waste.

Based on the process operations generating the wastewater at the CEM plant and the wastewater sample results, the wastewater is not a listed waste nor does it exhibit the characteristics of hazardous waste. In our judgement, the wastewater is not a hazardous waste.

COMMERCIAL ENVELOPE MANUFACTURING COMPANY
DEER PARK, NEW YORK

TABLE 1

RESULTS OF WASTEWATER ANALYSES DONE BY H2M CORPORATION

EP TOX

| <u>Parameter</u> | <u>Concentration mg/l</u> | | | |
|------------------|---------------------------|-------------------------|--------------------------|--------------------------|
| | <u>December 4, 1984</u> | <u>February 8, 1985</u> | <u>February 11, 1985</u> | <u>February 15, 1985</u> |
| Cadmium 1.0 | 0.10 | LT 0.02 | LT 0.02 | 0.0016 |
| Chromium (T) 5.0 | 0.70 | 0.12 | 0.07 | 0.03 |
| Lead 5.0 | 3.00 | 0.114 | 0.238 | 0.0228 |
| Silver 5.0 | 2.80 | 0.48 | 0.06 | 0.29 |

Legend:

LT = less than



Environmental Engineers & Scientists

HOLZMACHER, McLENDON and MURRELL, P.C.

575 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11747 (516) 694-3040

WATER RESOURCES • WATER SUPPLY & TREATMENT • SEWERAGE & TREATMENT • ECOLOGICAL & IMPACT STUDIES
MODEL STUDIES • PILOT PLANT STUDIES • WATER/WASTE WATER LABORATORY AND ANALYTICAL SERVICES

LABORATORY REPORT

LAB NO. 466475

PROJECT NO. CEMC 84-01 MS

COLLECTED BY RSI 03

DATE RECEIVED - 12/ 4/84

CLIENT'S NAME AND ADDRESS

COMMERICAL ENVELOPE INC.

900 GRAND BLVD

DEER PARK, NY

TYPE OF SAMPLE - MISCELLANEOUS

DATE COLLECTED - 12/ 4/84

SPECIAL SAMPLES

| LAB NO. | SAMPLE ID INFORMATION | PH | SILVER | CADMIUM | COPPER | NICKEL | CHROM- IUM |
|---------|-----------------------|------|--------|---------|--------|--------|---------------|
| 466475 | #1 - DEVELOPER RINSE | 5.60 | <0.02 | | | | |
| 466476 | #2 - TANK WASTE | 6.80 | 2.80 | 0.10 | 31.2 | 0.30 | 0.70 |
| 466477 | #3 - WASH STATION | 12.2 | 4.00 | 0.10 | 32.9 | 0.30 | 0.80 |
| 466478 | #4 - TRUCK BAY | 4.40 | 2.30 | <0.10 | 5.50 | 0.40 | 0.20 |
| 466479 | #5 - POOL SAMPLE | 6.10 | <0.20 | <0.10 | 0.60 | 0.20 | <0.20 |

From
TANK

MAXIMUM PENDING

207

REMARKS - REPORTS & INVOICES TO RSI

COPIES TO MDF 03

ALL RESULTS IN (MG/L) EXCEPT AS NOTED BY 1 (UG/L) OR 2 (PERCENT) AND

1. COLI BACT. & FECAL COLI (MPN/100ML)

COLOR, ODOR, TURBIDITY & PH (UNITS)

APC & FECAL STREPT (COUNTS/ML)

DATE REPORTED 12/12/84

AM



Environmental Engineers & Scientists

HOLZMACHER, McLENDON and MURRELL, P.C.

575 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11747 (516) 694-3040

WATER RESOURCES • WATER SUPPLY & TREATMENT • SEWERAGE & TREATMENT • ECOLOGICAL & IMPACT STUDIES
 MODEL STUDIES • PILOT PLANT STUDIES • WATER/WASTE WATER LABORATORY AND ANALYTICAL SERVICES

LABORATORY REPORT

LAB NO. 466475

PROJECT NO. CEMC 84-01 H9

COLLECTED BY RST 03

CLIENT'S NAME AND ADDRESS

COMMERICAL ENVELOPE INC.

900 GRAND BLVD

DEER PARK, NY

TYPE OF SAMPLE - MISCELLANEOUS

DATE COLLECTED - 12/ 4/84

DATE RECEIVED - 12/ 4/84

SPECIAL SAMPLES

| LAB NO. | SAMPLE ID INFORMATION | LEAD | IRON |
|---------|-----------------------|-------|------|
| 466475 | 01 - DEVELOPER RINSE | | |
| 466476 | 02 - TANK WASTE | 3.00 | 193. |
| 466477 | 03 - WASH STATION | 1.00 | 6.20 |
| 466478 | 04 - TRUCK BAY | 1.00 | 30.5 |
| 466479 | 05 - POOL SAMPLE | <0.20 | |

REMARKS - REPORTS & INVOICES TO RSI

COPIES TO HDF 03

ALL RESULTS IN (MG/L) EXCEPT AS NOTED BY % (UM/L) OR % (PERCENT) AND

T.COLI BACT. & FECAL COLI (MPN/100ML)

COLOR, ODOR, TURBIDITY & PH (UNITS)

APC & FECAL STREP (COUNTS/ML)

DATE REPORTED 12/12/84



Environmental Engineers & Scientists

HOLZMACHER, McLENDON and MURRELL, P.C.

575 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11747 (516) 694-3040

WATER RESOURCES • WATER SUPPLY & TREATMENT • SEWERAGE & TREATMENT • ECOLOGICAL & IMPACT STUDIES
MODEL STUDIES • PILOT PLANT STUDIES • WATER/WASTE WATER LABORATORY AND ANALYTICAL SERVICES

LABORATORY REPORT

LAB NO. 551226

PROJECT NO. CENC 84-01

CLIENT'S NAME AND ADDRESS

COMMERCIAL ENVELOPE, INC.

900 GRAND BLVD.

DEER PARK, N.Y. 11729

TYPE OF SAMPLE - MISCELLANEOUS

DATE COLLECTED - 2/ 8/85

COLLECTED BY RST 03

DATE RECEIVED - 2/ 8/85

WASTEWATER HOLDING TANK

| PARAM-ETER | RESULT | PARAM-ETER | RESULT |
|------------|--------|------------|--------|
|------------|--------|------------|--------|

| | | | |
|----|------|-----------|------|
| PH | 4.90 | CHLOR-IDE | 80.0 |
|----|------|-----------|------|

| | | | |
|--------|------|--------|------|
| SILVER | 0.48 | GREASE | 95.4 |
|--------|------|--------|------|

| | | | |
|---------|-------|---------|------|
| CADMIUM | <0.02 | PHENOLS | 1.60 |
|---------|-------|---------|------|

| | | | |
|------|-------|------|------|
| LEAD | 114.4 | ZINC | 1.41 |
|------|-------|------|------|

| | | | |
|--------|------|--|--|
| COPPER | 0.97 | | |
|--------|------|--|--|

| | | | |
|-----------|------|--|--|
| CHROM-IUM | 0.12 | | |
|-----------|------|--|--|

| | | | |
|------|------|--|--|
| IRON | 6.90 | | |
|------|------|--|--|

| | | | |
|----------------|------|--|--|
| T. DISS SOLIDS | 1210 | | |
|----------------|------|--|--|

| | | | |
|--------------|------|--|--|
| SUSP. SOLIDS | 1770 | | |
|--------------|------|--|--|

REMARKS - RPTS. & INVOICES TO RSI,
RUSH, NEED BY 2/15/85

ALL RESULTS IN (MG/L) EXCEPT AS NOTED BY # (UG/L) OR % (PERCENT) AND
T. COLI BACT. & FECAL COLI (MPN/100ML)
COLOR, ODOR, TURBIDITY & PH (UNITS)
CAPC & FECAL STREP (COUNTS/ML)
OSPEC.COND. (UMHOS) SETT.SOLIDS (ML/L)

DATE REPORTED 2/25/85

[Signature]



Environmental Engineers & Scientists

HOLZMACHER, McLENDON and MURRELL, P.C.

575 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11747 (516) 694-3040

LABORATORY REPORT

LAB NO. 551292

PROJECT NO. CEMC 84-01

WATER RESOURCES • WATER SUPPLY & TREATMENT • SEWERAGE & TREATMENT • ECOLOGICAL & IMPACT STUDIES
MODEL STUDIES • PILOT PLANT STUDIES • WATER/WASTE WATER LABORATORY AND ANALYTICAL SERVICES

CLIENT'S NAME AND ADDRESS

COMMERCIAL ENVELOPE, INC.

900 GRAND BLVD

DEER PARK, NY 11729

TYPE OF SAMPLE - MISCELLANEOUS

DATE COLLECTED - 2/11/85

COLLECTED BY RSI 03

DATE RECEIVED - 2/11/85

WASTEWATER HOLDING TANK

| PARAM-ETER | RESULT | PARAM-ETER | RESULT |
|------------|--------|------------|--------|
|------------|--------|------------|--------|

| | | | |
|----|------|------|------|
| PH | 5.20 | ZINC | 1.18 |
|----|------|------|------|

| | | | |
|--------|------|--|--|
| SILVER | 0.06 | | |
|--------|------|--|--|

| | | | |
|---------|-------|--|--|
| CADMIUM | <0.02 | | |
|---------|-------|--|--|

| | | | |
|------|-------|------|------------------|
| LEAD | 238.4 | MG/L | = 238 MG/L = PPM |
|------|-------|------|------------------|

| | | | |
|--------|------|--|--|
| COPPER | 4.13 | | |
|--------|------|--|--|

| | | | |
|-----------|------|--|--|
| CHROM-IUM | 0.07 | | |
|-----------|------|--|--|

| | | | |
|------|------|--|--|
| IRON | 6.60 | | |
|------|------|--|--|

| | | | |
|---------|--|--|--|
| T. DISS | | | |
|---------|--|--|--|

| | | | |
|--------|------|--|--|
| SOLIDS | 1960 | | |
|--------|------|--|--|

| | | | |
|-------|--|--|--|
| SUSP. | | | |
|-------|--|--|--|

| | | | |
|--------|------|--|--|
| SOLIDS | 1970 | | |
|--------|------|--|--|

REMARKS - RPTS. & INVOICES TO RSI

RESULTS IN (MG/L) EXCEPT AS NOTED BY * (UG/L) OR % (PERCENT) AND

T. COLI BACT. & FECAL COLI (MPN/100ML)

COLOR, ODOR, TURBIDITY & PH (UNITS)

APC & FECAL STREP (COUNTS/ML)

SPEC. COND. (UMHOB) SETT. SOLIDS (ML/L)

DATE REPORTED 4/15/85

Jm Slaw

Environmental Engineers & Scientists

JOHN J. MACHNER, MCLENDON and MURRELL, P.C.
100 HUNTER ROAD, MELVILLE, NEW YORK 11747 (516) 494-3040

LABORATORY REPORT

CONCRETE PIPELINE TAP

200 BRAND BLVD

DEER PARK NY 11729

TYPE OF SAMPLE: MISCELLANEOUS
DATE COLLECTED: 2/15/85

DATE RECEIVED: 2/15/85

WASTEWATER HOLDING TANK

| PARAMETER | RESULT | PARAMETER | RESULT |
|-----------|--------|-----------|--------|
|-----------|--------|-----------|--------|

| | | | |
|----|------|------|------|
| PH | 6.50 | ATNG | 0.48 |
|----|------|------|------|

SILVER

CADMIUM

LEAD

COPPER

CHROMIUM

IRON

BUSP

SOLIDS

DISS

GREASE

REMARKS - REPORTS & INVOICES TO RRT

ALL RESULTS IN (MG/L) EXCEPT AS NOTED BY 1 (UG/L) OR % (PERCENT) AND
T. BOLD FACT: 1. FECAL COLI (MPN/100ML)
COLOR: 1. HATCHER TURBIDITY 1. PH (UNITS)
AND 1. Fecal Bacteria (COUNTS/ML)
SPECTROPHOTOMETRY: 1. BETT. COLYDOR

DATE REPORTED: 2/16/85

Division of Solid/Hazardous Waste
Building 40, SUNY
Stony Brook, New York 11794
(516) 751-2617

File

March 27, 1986

Mr. Nicholas A. Andrianas
Eder Associates
Consulting Engineers, P.C.
83 Forest Avenue
Locust Valley, New York 11560

Division of Solid/Hazardous Waste
Building 40, SUNY
Stony Brook, New York 11794
(516) 751-2617

Re: Commercial Envelope Manufacturing Company, Deer Park, New York

Dear Mr. Andrianas:

We have reviewed the documentation of the above subject facility that you sent to this office on February 21, 1986. In addition, we met with you and Alan Kristel on March 14, 1986, and saw the operation of producing and printing envelopes.

Upon further review of Part 373 regulations, we have determined the following:

1. The waste water is non-hazardous, as it is not a listed waste.
2. The waste water is non-hazardous, as it is not a characteristic waste.
3. A Part 373 permit is not required for the incinerator.

However, apparently the county had sampled the bottom of the incinerator (solid sample taken February 27, 1986) and this was analyzed. The EP Toxicity test suggests this sludge may be a characteristic waste as levels of lead were 130 ppm (greater than 5 ppm), levels of chromium were 74 ppm (greater than 5 ppm), and cadmium was 12 ppm (greater than 1 ppm). This sludge should be properly disposed of by a licensed/permitted waste hauler.

Also, we had noted on the March 14, 1986, visit that there were approximately 20-25 drums stored towards the center of the main building. Most of these drums were unmarked and could not be identified. They should be sampled, analyzed/identified, and properly disposed of by Commercial Envelope.

Nicholas A. Andrianas
Commercial Envelope Manufacturing Company

2.

If you have any further questions in regards to these matters, please contact our office.

Very truly yours,

Joseph C. Fichera
Assistant Sanitary Engineer

JCF:dm

cc: J. Williams, SCID
J. Soderberg, SCID
D. Orlig, SCID
R. Secherer, NYSDEC

May 22, 1986
File #525-1



eder associates
consulting engineers, p.c.

Mr. Joseph Fichera
New York State Department of
Environmental Conservation
Building 40
SUNY
Stonybrook, New York 11794

Re: Commercial Envelope Manufacturing Company
Deer Park, New York
Request For Hazardous Waste Identification

Dear Mr. Fichera:

Commercial Envelope Manufacturing Company (CEM) abandoned three (3) ink waste tanks, per Article 12 of the Suffolk County Sanitary Code, in April, 1986. These tanks contained industrial wastewater generated from producing and printing envelopes. Prior to abandonment, the wastewater was collected and is being stored on-site in 180, 55-gallon drums.

Enclosed are the results of the analyses of this wastewater. One liquid sample was collected from each of the three tanks. The samples are identified as Liquid 01, 02 and 03 in the laboratory report. The laboratory report includes analysis of the characteristics of hazardous waste and of suspected organic contaminants. The analytical results indicate that the wastewater is not hazardous within the meaning and intent of the New York State Regulations. CEM would like to use its on-site liquid incinerator to dispose of this wastewater.

We are requesting that NYSDEC review the attached documentation and determine whether: (1) the wastewater is a hazardous waste; and (2) whether a Part 370 Permit is required for the on-site incineration of this waste.

The Suffolk County Department of Health Services requires a determination as to whether a Part 370 Permit is required. This determination is required, since we are concurrently applying for a "Certificate to Operate", a process and exhaust and/or ventilation system pursuant to 6NYCRR Part 201, for incineration of this wastewater.

The removal of the wastewater from the tanks and the abandonment of the tanks was performed under a Consent Order between CEM and Suffolk County. An expeditious response by your office to resolve this matter would be appreciated. For your assistance, a copy of this letter is being forwarded to Mr. Jim Moran of the New York State Department of Environmental Conservation in Albany for review by the hazardous waste identification staff.

Continued . . .

85 FOREST AVENUE • LOCUST VALLEY, NEW YORK 11560 • (516) 671-8440

LEONARD J. EDER, P. E. • FREDERICK H. INYARD, P. E. • STEPHEN J. OSMUNDSEN, P. E. • GARY A. ROZMUS, P. E.
JOHN McGUIRE, P. E. • JORGE MOLINA, ING. • WILLIAM J. CUNNINGHAM, P. E. • JOSEPH B. HELLMANN, P. E.

Mr. Joseph Fichera
New York State Department of
Environmental Conservation
May 22, 1986

-2-


Please forward your response to our request in writing to our office
and to:

Jeffrey K. Williams
Suffolk County Department of
Health Services
Assistant Public Health Engineer
Pollution Control
15 Horseblock Place
Farmingville, New York 11738

We thank you in advance for your timely response to our request. If
you have any questions, please contact our office.

Very truly yours,

EDER ASSOCIATES CONSULTING ENGINEERS, P.C.


Nicholas A. Andrianas
Project Engineer

NAA/td
Enc.

cc: S. Cohen
J. Moran
J. Williams



nytest environmental inc.

REPORT OF TESTS

Date: May 16, 1986

Lab. No.: 86-11915(A)

| | |
|--------------------|---------------------------------------------------|
| Client | Eder Associates |
| Material | Three (3) Solid & Three (3) Liquid Samples |
| Identification | See the Following Page (Samples Received 3/20/86) |
| Client's Order No. | Pending |
| Submitted for | <u>Chemical Analysis</u> |

(For Results, see the following page)

Report reviewed by:

Adrian D'Netto
GCMS Supervisor

Report reviewed by:

Peggy Sacks *B*
Q.C. Manager

To:

Eder Associates
85 Forest Avenue
Locust Valley, N.Y. 11560

Att: Mr. Gregory Rorech


ef

Encl.: (Chain of Custody)

CERTIFICATIONWe certify that this report is a true
report of results obtained from our
tests of this material.

Respectfully submitted,

Nyttest Environmental Inc.


Remo Gigante, Laboratory Director

Report on sample(s) furnished by client applies to sample(s). Report on sample(s) obtained by us applies only to lot sampled. Information contained herein is not to be used for reproduction except by special permission. Sample(s) will be retained for thirty days maximum after date of report unless specifically requested otherwise by client. In the event that there are portions or parts of sample(s) remaining after Nytest has completed the required tests, Nytest shall have the option of returning such sample(s) to the client at the client's expense.



Page: 2.

Lab. No. 86-11915(A)

| | Sample Identification | | | | | |
|----------------------------|-----------------------|---------------------|---------------------|-------------------|-------------------|-------------------|
| | 01 <u>Liquid</u> | 02 <u>Liquid</u> | 03 <u>Liquid</u> | 04 <u>Soil</u> | 05 <u>Soil</u> | 06 <u>Soil</u> |
| <u>Results in ppb</u> | | | | | | |
| Trans-1,2-Dichloroethylene | ND | ND | ND | ND | ND | ND |
| Cis-1,2-Dichloroethylene | ND | ND | ND | ND | ND | ND |
| Ethylbenzene | ND | ND | ND | ND | ND | ND |
| Nonane | 19340 | 5040 | ND | ND | ND | ND |
| Undecane | ND | 33804 | ND | 124 | 9623 | ND |
| 1,1,2-Trichloroethylene | ND | ND | ND | ND | ND | ND |
| 1,3,5-Trimethylbenzene | 9313 | 7728 | 2630 | ND | ND | ND |
| 1,2,4,5-Tetramethylbenzene | 4151 | 3753 | 1095 | ND | ND | ND |
| Tetrachloroethylene | 28 | 12 | 19 | ND | ND | ND |
| Toluene | ND | ND | ND | ND | 205 | ND |
| Total Xylenes | ND | ND | ND | ND | ND | ND |
| Decane | 59703 | 38836 | ND | 207 | 3642 | ND |
| Methylene Chloride | 39 | 3 | 94 | 800 | ND | 809 |
| p-Ethyl toluene | ND | ND | 1994 | ND | ND | ND |
| 1,2,4-Trimethylbenzene | 19196 | 18031 | ND | ND | ND | ND |
| p-Diethylbenzene | ND | ND | ND | ND | ND | ND |

ND = None Detected



nytest environmental inc.

CHAIN OF CUSTODY RECORD

| PROJECT NO. | | PROJECT NAME | | NO. OF CONTAINERS | | ANALYSIS | | | | | | | | | | | REMARKS |
|-----------------|---------|--------------|------|-------------------|-----------------|----------|--------------|---------|--------|----------|--------|----------|-----------|---------|-------|--------------------------------------------------------|-------------------------|
| CLIENT NAME: | | LAB.# | | | | NITROGEN | OIL & GREASE | CYANIDE | PHENOL | VOLATILE | METALS | ORGANICS | BACTERIAL | TOC/COD | OTHER | UNPRESERVED | ADDITIONAL REQUIREMENTS |
| SAMPLE I.D. NO. | DATE | TIME | COMP | GRAB | SAMPLE LOCATION | | | | | | | | | | | | For All |
| 01 | 3-17-86 | 9:10 AM | | X | Tank One | | | | | X | X | | | X | | Reactivity | |
| 02 | 3-18-86 | 2:55 PM | | X | Tank Two | | | | | X | X | | | X | | Corrosivity | |
| 03 | 3-17-86 | 12:05 PM | | X | Tank Three | | | | | X | X | | | X | | Ignitability | |
| 04 | 3-17-86 | 11:15 AM | | X | Tank One | | | | | X | X | | | X | | EP tox metals | |
| 05 | 3-20-86 | 9:50 AM | | X | Tank Two | | | | | X | X | | | X | | Trans-1,2-Dichloroethene, | |
| 06 | 3-17-86 | 12:40 PM | | X | Tank Three | | | | | X | X | | | X | | 1,2-Dichloroethene, Ethylbenzene, | |
| | | | | | | | | | | | | | | | | 1,1,2-Trichloroethene, 1,3,5-Trimethylbenzene, Toluene | |
| | | | | | | | | | | | | | | | | 1,2,4,5-Tetrachlorobenzene, Xylene, | |
| | | | | | | | | | | | | | | | | Tetrachloroethene, Chloride, | |
| | | | | | | | | | | | | | | | | p-Ethyltoluene, p-dichlorobenzene | |
| | | | | | | | | | | | | | | | | 1,2,4-Trimethylbenzene | |
| | | | | | | | | | | | | | | | | 1,3,5-Trimethylbenzene | |
| | | | | | | | | | | | | | | | | Nonane, Decane, Undecane | |

| Shipped Via: | | Agent of: | | Agent of: | |
|-----------------------------|--------------|-----------------------------|-----------|-----------------------------|-----------------|
| Relinquished by (Signature) | Date/Time | Relinquished by (Signature) | Date/Time | Relinquished by (Signature) | Date/Time |
| Gregory Rorech | 3-20-86 1:15 | Eder Associates | | Gregory Rorech | 3/20/86 1:15 |
| Relinquished by (Signature) | Date/Time | Relinquished by (Signature) | Date/Time | Relinquished by (Signature) | Date/Time |
| Ken Minkoff | 3-20-86 2:01 | Eder Associates | | Ken Minkoff | 3/20/86 2:01 |
| Relinquished by (Signature) | Date/Time | Relinquished by (Signature) | Date/Time | Relinquished by (Signature) | Date/Time |
| Caroline Paul | 3/20/86 | Caroline Paul | | Caroline Paul | 3-20-86 3:40 PM |

Remarks: Gregory Rorech 671-8440



nytest environmental

LAB. NO.: 86-11915(B)

P.O. NO.: Pending

REPORT OF ANALYSIS

- FOR -

EDER ASSOCIATES
85 FOREST AVENUE
LOCUST VALLEY, NY 11560

MAY 16, 1986

019



Page CONTENTS

Contract 86-11915(B)

TABLE OF CONTENTS

| | <u>Page No.</u> |
|---------------------------------------|-----------------|
| 1.0 REFERENCES | 1 |
| 2.0 TEST DESCRIPTION | 1 - 2 |
| 3.0 TEST REQUIREMENTS | 2 |
| 4.0 SAMPLE IDENTIFICATION | 2 |
| 5.0 SAMPLE IDENTIFICATION AND RESULTS | 3 - 8 |
| 6.0 CONCLUSION | 9 |
| 7.0 CERTIFICATION AND SIGNATURES | 9 |



Page 1.

Lab No 86-11915(B)

1.0 References

- 1.1 Client purchase order number: Pending
- 1.2 Lab. No. 86-11915(B)
- 1.3 Identification and listing of Hazardous Waste. Federal Register, Vol. 45 No. 98, May 19, 1980
- 1.4 Handbook for analytical Quality Control in Water-Wastewater Laboratories - EPA-600/4-79-019, March, 1979

2.0 Description of Tests

2.1 Ignitability: Ref. 1.3 para. 261.21

Identifies materials that pose a fire hazard due to being ignitable under routine storage, disposal, and transportation. This characteristic is measured by the closed cup flash point.

Wastes exhibiting flash point below 60°C (140°F) must be handled as hazardous waste.

2.2 Corrosivity: Ref. 1.3 para. 261.22

Identifies materials which require special containers and handling because of their ability to corrode standard materials. Aqueous samples are considered corrosive if the pH is less than or equal to 2.0, or greater than or equal to 12.5. Any liquid sample which is capable of corroding SAE 1020 steel at a rate greater than 0.25 inches per year at a test temperature of 55°C (130°F) is considered corrosive.

021



Page 2.

Lab No 86-11915(B)

2.0 Description of Tests

2.3 Reactivity: Ref. 1.3 para 261.23

Identifies materials that tend to react spontaneously, to react vigorously with air or water, or are explosive.

2.4 E P Toxicity: Ref. 1.3 para. 261.24

Identifies materials whose constituents may have a tendency to leach or migrate when disposed of improperly. The liquid phase of a sample is separated. The solid phase is extracted at pH 5 with aqueous acetic acid for 24 hours. The extract is combined with the liquid phase and analyzed.

3.0 Test Requirements

1. Corrosivity
2. Ignitability
3. Reactivity
4. E P Toxicity - Table 1

4.0 Sample Identification

Submitted samples of liquid and soil received 3/20/86 and identified as:

| | |
|-----------|------------|
| 01 Liquid | Tank One |
| 02 Liquid | Tank Two |
| 03 Liquid | Tank Three |
| 04 Soil | Tank One |
| 05 Soil | Tank Two |
| 06 Soil | Tank Three |

022

5.0 Sample Identification and Results

5.1 Sample Marked 01 Liquid

Date sampled: 3/17/86

Collected by: Eder Associates

Date Received by Nytest Environmental Inc.: 3/20/86

| <u>5.1.1 Results</u> | <u>Max. Allowable Levels</u> | <u>Found</u> |
|----------------------------|------------------------------|--------------|
| pH @ 20°C | 2-12.5 | 7.90 |
| Reactivity to Sulfide, ppm | - | < 1 |
| Reactivity to Cyanide, ppm | - | < 1 |
| Corrosivity inches/year | 0.25 | < 0.01 |
| Ignitability °F, PM | 140 | > 212 |

E P Toxicity (PPM)

| | | |
|----------|-------|--------|
| Arsenic | 5.0 | < 0.05 |
| Barium | 100.0 | < 1.0 |
| Cadmium | 1.0 | < 0.01 |
| Chromium | 5.0 | < 0.05 |
| Lead | 5.0 | < 0.05 |
| Mercury | 0.2 | < 0.02 |
| Selenium | 1.0 | < 0.01 |
| Silver | 5.0 | < 0.05 |

< = Less than

> = Greater than



Page 4

Lab. No. 86-11915(8)

5.0 Sample Identification and Results5.2 Sample Marked 02 Liquid

Date sampled: 3/17/86

Collected by: Eder Associates

Date Received by Neytest Environmental Inc.: 3/20/86

| 5.2.1 <u>Results</u> | <u>Max. Allowable Levels</u> | <u>Found</u> |
|----------------------------|------------------------------|--------------|
| pH @ 20°C | 2-12.5 | 7.60 |
| Reactivity to Sulfide, ppm | - | < 1 |
| Reactivity to Cyanide, ppm | - | < 1 |
| Corrosivity inches/year | 0.25 | < 0.01 |
| Ignitability °F, PM | 140 | > 212 |

E P Toxicity (PPM)

| | | |
|----------|-------|--------|
| Arsenic | 5.0 | < 0.05 |
| Barium | 100.0 | < 1.0 |
| Cadmium | 1.0 | < 0.01 |
| Chromium | 5.0 | < 0.05 |
| Lead | 5.0 | < 0.05 |
| Mercury | 0.2 | < 0.02 |
| Selenium | 1.0 | < 0.01 |
| Silver | 5.0 | < 0.05 |

< = Less than

> = Greater than

024

227/1449

5.0 Sample Identification and Results5.3 Sample Marked 03 Liquid

Date sampled: 3/17/86

Collected by: Eder Associates

Date Received by Nytest Environmental Inc.: 3/20/86

| 5.3.1 <u>Results</u> | <u>Max. Allowable Levels</u> | <u>Found</u> |
|----------------------------|------------------------------|--------------|
| pH @ 20°C | 2-12.5 | 8.10 |
| Reactivity to Sulfide, ppm | - | < 1 |
| Reactivity to Cyanide, ppm | - | < 1 |
| Corrosivity inches/year | 0.25 | < 0.01 |
| Ignitability °F, PM | 140 | >212 |

E P Toxicity (PPM)

| | | |
|----------|-------|--------|
| Arsenic | 5.0 | < 0.05 |
| Barium | 100.0 | < 1.0 |
| Cadmium | 1.0 | < 0.01 |
| Chromium | 5.0 | < 0.05 |
| Lead | 5.0 | < 0.05 |
| Mercury | 0.2 | < 0.02 |
| Selenium | 1.0 | < 0.01 |
| Silver | 5.0 | < 0.05 |

< = Less than

> = Greater than



Lab. No. 86-11915(B)

5.4 Sample Marked 04 Soil

Date Received by Nytest Environmental Inc.: 3/20/86

Found

| | | |
|----------------------------|--------|--------|
| pH @ 20°C | 2-12.5 | 9.0 |
| Reactivity to Sulfide, ppm | - | < 1 |
| Reactivity to Cyanide, ppm | - | < 1 |
| Corrosivity inches/year | 0.25 | < 0.01 |
| Ignitability °F, PM | 140 | >212 |

E P Toxicity (PPM)

| | | |
|----------|-------|--------|
| Arsenic | 5.0 | < 0.05 |
| Barium | 100.0 | 1.16 |
| Cadmium | 1.0 | < 0.01 |
| Chromium | 5.0 | < 0.05 |
| Lead | 5.0 | 4.36 |
| Mercury | 0.2 | < 0.02 |
| Selenium | 1.0 | < 0.01 |
| Silver | 5.0 | < 0.05 |

> = Greater than

326

2014.19



Page 7

Lab No. 86-11915(B)

5.0 Sample Identification and Results5.5 Sample Marked 05 Soil

Date sampled: 3/17/86

Collected by: Eder Associates

Date Received by Nytest Environmental Inc.: 3/20/86

| 5.5.1 <u>Results</u> | <u>Max. Allowable Levels</u> | <u>Found</u> |
|----------------------------|------------------------------|--------------|
| pH @ 20°C | 2-12.5 | 7.4 |
| Reactivity to Sulfide, ppm | - | < 1 |
| Reactivity to Cyanide, ppm | - | < 1 |
| Corrosivity inches/year | 0.25 | < 0.01 |
| Ignitability °F, PM | 140 | >212 |

E P Toxicity (PPM)

| | | |
|----------|-------|--------|
| Arsenic | 5.0 | < 0.05 |
| Barium | 100.0 | < 1.0 |
| Cadmium | 1.0 | < 0.01 |
| Chromium | 5.0 | < 0.05 |
| Lead | 5.0 | 1.11 |
| Mercury | 0.2 | < 0.02 |
| Selenium | 1.0 | < 0.01 |
| Silver | 5.0 | < 0.05 |

< = Less than

> = Greater than

327



Page 18

File No. 86-11915(B)

5.0 Sample Identification and Results5.6 Sample Marked 06 Soil

Date sampled: 3/17/86

Collected by: Eder Associates

Date Received by Nytest Environmental Inc.: 3/20/86

| 5.6.1 <u>Results</u> | <u>Max. Allowable Levels</u> | <u>Found</u> |
|----------------------------|------------------------------|--------------|
| pH @ 20°C | 2-12.5 | 8.5 |
| Reactivity to Sulfide, ppm | - | < 1 |
| Reactivity to Cyanide, ppm | - | < 1 |
| Corrosivity inches/year | 0.25 | < 0.01 |
| Ignitability °F, PM | 140 | >212 |

E P Toxicity (PPM)

| | | |
|----------|-------|--------|
| Arsenic | 5.0 | < 0.05 |
| Barium | 100.0 | < 1.0 |
| Cadmium | 1.0 | < 0.01 |
| Chromium | 5.0 | < 0.05 |
| Lead | 5.0 | 0.14 |
| Mercury | 0.2 | < 0.02 |
| Selenium | 1.0 | < 0.01 |
| Silver | 5.0 | < 0.05 |

< = Less than

> = Greater than

328



Page 9

Lab. No. 86-11915(B)

6.0 CONCLUSION

Samples do not exhibit characteristics of reactivity, corrosivity, ignitability or toxicity for metals.

7.0 CERTIFICATION AND SIGNATURES

Report prepared by:

Adrian D'Netto
GCMS Supervisor

Report reviewed by:

Peggy Sacks *PS*
Q.C. Manager

Att: Mr. Gregory Rorech

bm

We certify that this report is a true report of results obtained from our tests of this material.

Respectfully submitted,

Nytest Environmental Inc.

Remo Gigante
Remo Gigante
Laboratory Director

Report on sample(s) furnished by client applies to sample(s). Report on sample(s) obtained by us applies only to lot sampled. Information contained herein is not to be used for reproduction except by special permission. Sample(s) will be retained for thirty days maximum after date of report unless specifically requested otherwise by client. In the event that there are portions or parts of sample(s) remaining after Nytest has completed the required tests, Nytest shall have the option of returning such sample(s) to the client at the client's expense.

SOLID WASTE MANAGEMENT
DECISION 1

JUN 16 1986

file ✓
Commercial
Envelope

Mr. Nicholas A. Andrianas
Project Engineer
Eder Associates Consulting Engineers, P.C.
85 Forest Avenue
Locust Valley, New York 11560

Dear Mr. Andrianas:

Your letter of May 22, 1986 to Mr. Fichera of the Department of Environmental Conservation (DEC) Region 1, describes your plans, on behalf of your client, to incinerate on-site the aqueous wastewater decanted from abandoned ink waste tanks. The sludge from these ink waste tanks, which were shown to be a characteristic hazardous waste, were already disposed of at a TSDF. The removal of these tanks and their contents are part of a consent order.


As presented, the data does not clearly indicate a hazardous waste since the wastewater is not a characteristic waste, but does contain traces of listed hazardous waste. The trace organics found would meet the intent of the Part 371.1 (d) ii (d)(2) criteria and could be attributed to de minimis losses. Please understand that the decision as to hazardous or non-hazardous rests solely with the generator.

If you have any additional questions, please do not hesitate to contact me at telephone number 518-457-6858.

Sincerely,

James Sibbald Moran, P.E.
Supervisor
Manifest Section
Bureau of Hazardous Waste Operations
Division of Solid and Hazardous Waste

cc: J. Fichera
J. Williams
D. Mafrici



eder associates
consulting engineers, p.c.

June 23, 1986
File #525-1

Via: Federal Express

RECEIVED

JUN 24 1986

S.C. DEPT. OF
HEALTH SERVICES

Mr. Jeffrey K. Williams
Assistant Public Health Engineer
Pollution Control
Suffolk County Department of
Health Services
15 Horseblock Place
Farmingville, New York 11738

Re: Commercial Envelope Manufacturing Company, Inc.
Deer Park, New York

Dear Mr. Williams:

As we informed your office, during our recent telephone conversations and through our May 22, 1986 letter to Mr. Fichera of the New York State Department of Environmental Conservation (NYSDEC), Commercial Envelope Manufacturing (CEM) abandoned three (3) underground ink waste tanks pursuant to Article 12 of the Suffolk County Sanitary Code in April 1986. Prior to abandonment, the wastewater in the tanks was collected and stored on-site in 180 55 gallon drums.

CEM hereby requests permission to dispose of the wastewater in its on-site liquid incinerator. An application for a "Certificate to Operate" the existing incinerator to dispose of wastewater currently generated at CEM was approved by your office. You have requested that CEM supply information describing the wastewater removed from the abandoned tanks, wastewater sampling and analysis performed and estimated contaminant emissions. This information is provided in Attachment A for your review.

We have requested that the NYSDEC determine whether a Part 370 Permit is required for the storage and incineration of the wastewater removed from the underground tanks. This request was submitted by our office on May 22, 1986 to Mr. Joseph Fichera (DEC, Region I) and to Mr. Jim Moran (DEC, Albany). A copy of the request was also submitted to your office. We have been verbally advised by Dr. Max Goldman (DEC, Albany) that the wastewater is non-hazardous. A Part 370 Permit for the storage and incineration is therefore not required.

The removal of the wastewater from the tanks and abandonment of the tanks was performed under a Consent Order between CEM and Suffolk County. Your assistance in expediting this request to incinerate the ink tank wastewater would be appreciated.

Continued . . .

031

85 FOREST AVENUE • LOCUST VALLEY, NEW YORK 11560 • (516) 671-8440

LEONARD J. EDER, P. E. • FREDERICK H. INYARD, P. E. • STEPHEN J. OSMUNDSEN, P. E. • GARY A. ROZMUS, P. E.
JOHN MCGUIRE, P. E. • JORGE MOLINA, ING. • WILLIAM J. CUNNINGHAM, P. E. • JOSEPH B. HELLMANN, P. E.

Mr. Jeffrey K. Williams
Suffolk County Department of
Health Services
June 23, 1986


-2-

Please advise our office in writing of your decision to permit CEM to incinerate this wastewater removed from the abandoned tanks.

If you have any questions, please do not hesitate to contact our office.

Very truly yours,

EDER ASSOCIATES CONSULTING ENGINEERS, P.C.


Nicholas A. Andrianas
Project Engineer

NAA/tg

cc: S. Cohen
J. Fichera

COMMERCIAL ENVELOPE MANUFACTURING COMPANY, INC.
DEER PARK, NEW YORK

ATTACHMENT A

Wastewater Generation

Commercial Envelope Manufacturing (CEM) operated, in the past, three (3) underground ink waste storage tanks. The tanks were used to store wastewater generated by washing of ink printing equipment and by plate making and developing room operations. A description of the wastewater currently generated at CEM is included in Eder Associates' February 20, 1986 letter to Joseph Fichera (NYSDEC). A copy of this letter was submitted to the Suffolk County Department of Health Services (SCDHS). According to plant personnel, the wastewater stored in the ink waste tanks prior to abandonment was generated in the same manner to the wastewater presently generated at CEM.

Wastewater Sampling and Analysis

The wastewater was pumped from the ink waste tanks, decanted and stored in 55 gallon drums by a licensed industrial waste contractor. One grab sample of the liquid was collected from each tank by an engineer from Eder Associates during the pumping operations. The samples were placed in appropriate sample bottles provided by the analytical laboratory and preserved. EPA sampling, analysis and chain of custody protocols were followed. Samples of liquids in the tanks were identified as Liquid 01, 02 and 03. Samples identified as Soil 04, 05 and 06 were collected from the inside of the tanks. The soil in the tanks was removed and disposed of off-site. The samples were collected between March 17 and March 20, 1986.

The samples were analyzed for the characteristics of hazardous waste (EP toxicity, ignitability, reactivity and corrosivity) and for selected organic constituents. The organics analyzed included compounds used at the CEM facility and/or potentially present in the wastewater. The organic analyses includes halogenated, straight chain and cyclic hydrocarbons. The straight chain and cyclic hydrocarbons were analyzed for purposes of comparison to wastewater sampling and analysis performed by SCDHS. The results of the analyses are enclosed. Low concentrations of straight chain and cyclic hydrocarbons organics were detected. Trace concentrations of halogenated organics were detected. No EP toxic metals were detected.

Contaminant Emissions

The CEM facility operates a natural gas fired liquid incinerator. The incinerator runs at 1800°F. Incineration of the straight chain and cyclic hydrocarbons in the wastewater can be expected to completely oxidize the compounds to form carbon dioxide (CO₂) and water (H₂O). These compounds are the normal combustion products of the natural gas used to fire the incinerator. The natural gas flow to the incinerator is 1500 SCFH. A complete description of the incinerator operation was submitted to the SCDHS by Holzmacher, McLendon and Murrell (H2M) in April, 1985.

The main combustion products resulting from the incineration of the chlorinated hydrocarbons are carbon dioxide (CO₂), water (H₂O), hydrochloric acid (HCl) and hypochlorous acid (HClO). The estimated maximum emission of HCl and HClO contaminants were calculated. A summary of the estimated emissions is as follows:

Estimated Contaminant Emissions

| <u>Contaminant</u> | <u>Actual (lb/hr)</u> | <u>Emission Rate Potential (ERP lb/hr)</u> | <u>Actual Annual (lb/yr)</u> |
|--------------------|-----------------------|----------------------------------------------------|----------------------------------|
| Hydrochloric Acid | 1.8×10^{-5} | 1.8×10^{-5} | 0.004 |
| Hypochlorous Acid | 2.6×10^{-5} | 2.6×10^{-5} | 0.006 |

These levels of contaminants should be considered trace emissions. The calculations of contaminants are enclosed with this Attachment.



No EP toxic metals were detected in the wastewater samples, therefore no calculations for emission of metal oxide contaminants were performed.

COMMERCIAL ENVELOPE MANUFACTURING COMPANY, INC.
DEER PARK, NEW YORK

CALCULATIONS OF CONTAMINANT EMISSIONS

| A. <u>Compound</u> | <u>Maximum Wastewater Concentration (mg/l)</u> |
|----------------------------------------------------|----------------------------------------------------|
| Tetrachloroethylene (CCl_2CCl_2) | 0.028 |
| Methylene Chloride (CH_2Cl_2) | 0.094 |

- B. Wastewater Feed Rate: 0.67 gpm
- C. Quantity of Wastewater: 9,900 gal
- D. Reactions Used for Calculations



- E. Input of compound to incineration generating

Tetrachloroethylene:

$$\begin{aligned} &= 0.67 \text{ gal/min} \times 60 \text{ min/hr} \times 3.78 \text{ l/gal} \times 0.028 \text{ mg/l} \\ &\quad \times \text{g/1000 mg} \times \text{lb/454g} \\ &= 9.37 \times 10^{-6} \text{ lb/hr} \end{aligned}$$

$$\text{Molecular Weight} = 166 \text{ lb/lb-mole } (\text{CCl}_2\text{CCl}_2)$$

$$9.37 \times 10^{-6} \text{ lb/hr} \times \text{lb-mole/166 lb}$$

$$= 5.65 \times 10^{-8} \text{ lb-mole/hr}$$

Methylene Chloride

$$\begin{aligned}
 &= 0.67 \text{ gal/min} \times 60 \text{ min/hr} \times 3.78 \text{ l/gal} \times 0.094 \text{ mg/l} \\
 &\quad \times \text{g/1000g} \times \text{lb/454g} \\
 &= 3.15 \times 10^{-5} \text{ lb/hr}
 \end{aligned}$$

$$\text{Molecular Weight} = 84 \text{ lb/lb-mole (CH}_2\text{Cl}_2\text{)}$$

$$= 3.15 \times 10^{-5} \text{ lb/hr} \times \text{lb-mole/84 lb}$$

$$= 3.75 \times 10^{-7} \text{ lb-mole/hr}$$

F. Contaminant Emissions

HCl:

$$\begin{aligned}
 &= 5.65 \times 10^{-8} \text{ lb-mole/hr} \times 2 \times 36.5 \text{ lb/lb-mole} \\
 &\quad + 3.75 \times 10^{-7} \text{ lb-mole/hr} \times 1 \times 36.5 \text{ lb/lb-mole}
 \end{aligned}$$

$$= 1.8 \times 10^{-5} \text{ lb/hr}$$

HClO:

$$\begin{aligned}
 &= 5.65 \times 10^{-8} \text{ lb-mole/hr} \times 2 \times 52.5 \text{ lb/lb-mole} \\
 &\quad + 3.75 \times 10^{-7} \text{ lb-mole/hr} \times 1 \times 52.5 \text{ lb/lb-mole} \\
 &= 2.6 \times 10^{-5} \text{ lb/hr}
 \end{aligned}$$

Annual Emissions:

$$\text{HCl} \quad 3.2 \times 10^{-5} \text{ lb/hr} \times 246 \text{ hrs} = 0.004 \text{ lb/yr}$$

$$\text{HClO} \quad 4.5 \times 10^{-5} \text{ lb/hr} \times 246 \text{ hrs} = 0.006 \text{ lb/yr}$$

COUNTY OF SUFFOLK



PETER F. COHALAN
SUFFOLK COUNTY EXECUTIVE

To Commercial Env
RECEIVED
JUL 7 1986
SOLID WASTE MANAGEMENT
DEC REGION I

DEPARTMENT OF HEALTH SERVICES

DAVID HARRIS, M.D., M.P.H.
COMMISSIONER

June 30, 1986

Mr. Nicholas Andrianas
Eder Associates, P.C.
85 Forest Ave.
Locust Valley, N.Y. 11560

Re: Commercial Envelope Mfg. Co., Inc.
Deer Park *file*

Dear Mr. Andrianas:

Pursuant to your conversation today with Mr. Jeffrey Williams of my staff, I have been informed that the estimated emissions associated with the one time incineration of ink storage tank waste water at the above referenced facility will not exceed acceptable ambient levels for the contaminants listed in your letter dated June 23, 1986.

As such, authorization is hereby granted to Commercial Envelope Mfg. Co., Inc. to evaporate these wastes under the existing Certificate to Operate identified as Emission Point 472000 4428 00001.

If you have any questions regarding this matter please do not hesitate to contact me.

Very truly yours,

William C. Roberts, P.E.
Chief, Bureau of
Environmental Pollution Control

WCR/JKW/rt

cc: Steven Cohen, Esq.
Gold & Wachtel
37th Floor
10 E. 53rd St.
New York, N.Y. 10022
cc: Joseph Fichera
NYSDEC - Stony Brook

038



eder associates
consulting engineers, p.c.

September 12, 1986
File #525-1

Mr. Vincent Frisina, P.E.
Public Health Engineer
Hazardous Materials Management
Suffolk County Department of
Health Services
15 Horseblock Place
Farmingville, New York 11738

Art-12

Re: Commercial Envelope Manufacturing Company, Inc.
Deer Park, New York

Dear Mr. Frisina:

The modifications at the above referenced facility for compliance with Article 12 of the Suffolk County Sanitary Code have been completed.

On behalf of Commercial Envelope, we request that a County representative visit and inspect the facility pursuant to the issuance of "Permit to Operate".

Please contact our office or Mr. Alan Kristel at Commercial Envelope to arrange for a site visit.


Very truly yours,

EDER ASSOCIATES CONSULTING ENGINEERS, P.C.

Nicholas A. Andrianas
Project Engineer

NAA/tg

cc: S. Cohen
A. Kristel



039

85 FOREST AVENUE • LOCUST VALLEY, NEW YORK 11560 • (516) 671-8440

LEONARD J. EDER, P.E. • FREDERICK H. INYARD, P.E. • STEPHEN J. OSMUNDSEN, P.E. • GARY A. ROZMUS, P.E.
JOHN MCGUIRE, P.E. • JORGE MOLINA, ING. • WILLIAM J. CUNNINGHAM, P.E. • JOSEPH B. HELLMANN, P.E.

REFERENCE NO. 7

file

COUNTY OF SUFFOLK



PATRICK G. HALPIN
SUFFOLK COUNTY EXECUTIVE

DEPARTMENT OF HEALTH SERVICES

DAVID HARRIS, M.D., M.P.H.
COMMISSIONER

January 17, 1991

Mr. Joseph Guarino
Town of Babylon
281 Phelps Lane
North Babylon, New York 11703-4006

Re: Subdivision Application #90-02MN
Suffolk County Tax Map #100-67-1-22.2, 24.64, 24.55

Gentlemen:


In response to your letter dated December 19, 1990, I have requested that our Office of Ecology review the environmental assessment report and respond at their earliest convenience.

Due to the fact that Commercial Envelope, a Superfund facility #1-52-103, is located on this parcel, all future owners of any portion of this property should be made aware of their possible liability in the event that an environmental cleanup is required. In addition to being a Superfund site, Commercial Envelope also performed a cleanup and a limited groundwater study in accordance with an Order on Consent with Suffolk County Department of Health Services #IW-85-67. Although, monitoring wells at the site revealed trace organic contamination, the report submitted by Eder Associates, Commercial Envelope's consultants, stated that the levels found were sporadic and in up stream wells as well as down stream wells. No positive identification could be made as to the source of contaminants found.

In January 1986, the facility also experienced a problem with the mistaken delivery of thousands of gallons of fuel oil to a monitoring well on the west side of the building instead of the fill line to the fuel tank. This cleanup was performed under DEC supervision. The spill number for the incident is 85-3538. I would suggest that you contact the appropriate people at the New York State DEC for further information regarding the fuel oil spill and the present status with regard to the Superfund investigation.

Sincerely,

Robert Seyfarth, Senior Public Health Sanitarian
Inspection Services
Environmental Engineering & Pollution Control



ARTHUR G. PITTS, Supervisor

Town of Babylon

281 Phelps Lane, North Babylon, New York 11703-4006

**TOWN OF BABYLON
ENVIRONMENTAL QUALITY REVIEW ACT
(TOBEQRA) CHAPTER 114-5(B)(1)
LEAD AGENCY COORDINATION
NOTIFICATION**

DATE December 19, 1990

TO: Mr. James Pim
S. C. Dept. of Health Services
15 Horseblock Road
Farmingville, N. Y. 11738

IDENTIFIED AS:

X

INVOLVED AGENCY
INTERESTED AGENCY

APPLICANT: Subdiv. Appl. No. 90-025mn SCTM#100-67-1-22.2, 24.64,
24.55
M.A.S. Blvd. Associates
S/s Grand Blvd., 300' w/o Jeffryn
Deer Park, New York

PROPOSAL: Subdivide an already developed industrial site into two
parcels. Parcel one will include a building with two
businesses, E.L.M. Freight Handlers, Inc. and Commercial
Envelope, a manufacturing operation on the superfund
list. Parcel two will include a vacant lot and Pepsi
Cola warehouse.

TOBEQRA STATUS: X TYPE I UNLISTED

YOU HAVE BEEN CONTACTED TO SOLICIT YOUR INTEREST IN:

REQUESTING LEAD AGENCY STATUS
X SUBMITTING ANY COMMENTS ON THE PROPOSAL

LEAD AGENCY COORDINATION TIME FRAME: STARTS 12/19/90
ENDS 1/17/91

THE Planning Board OF THE TOWN OF BABYLON WILL
BE ASSUMING LEAD AGENCY STATUS UPON COMPLETION OF THE THIRTY DAY
LEAD AGENCY COORDINATION. IF YOU HAVE ANY QUESTIONS CONTACT
Joseph Guarino at 422-7640 TOWN OF BABYLON, DEPARTMENT OF
ENVIRONMENTAL CONTROL. PART I OF THE TOBEQRA LONG ENVIRONMENTAL
ASSESSMENT FORM IS ENCLOSED FOR YOUR REVIEW.

cc: Evan R. Liblit, Commissioner, TOBDEC
Jean l. Gilman, Deputy Commissioner, TOBDEC
Lynn Iacona, Deputy Town Attorney
Darrel Conway, Assistant Town Attorney
Karen Finkenberg, Sr. Engineering Aide, Planning & Development
Robert Longman, Planner, Planning & Development
Thomas Young, Chairman, Planning Board

JG:vl

PART 1—PROJECT INFORMATION

Prepared by Project Sponsor

NOTICE: This document is designed to assist in determining whether the action proposed may have a significant effect on the environment. Please complete the entire form, Parts A through E. Answers to these questions will be considered as part of the application for approval and may be subject to further verification and public review. Provide any additional information you believe will be needed to complete Parts 2 and 3.

It is expected that completion of the full EAF will be dependent on information currently available and will not involve new studies, research or investigation. If information requiring such additional work is unavailable, so indicate and specify each instance.

| | | | |
|---------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------|--------------------------|
| NAME OF ACTION <u>Subdivision</u> | | | |
| LOCATION OF ACTION (Include Street Address, Municipality and County) <u>900 Grand Blvd. Deer Park, NY Town of Babylon Suffolk County</u> | | | |
| NAME OF APPLICANT/SPONSOR <u>M.A.S. Boulevard Associates</u> | | BUSINESS TELEPHONE <u>(516) 242-2500</u> | |
| ADDRESS <u>900 Grand Blvd.</u> | | | |
| CITY/PO <u>Deer Park</u> | | STATE <u>NY</u> | ZIP CODE <u>11729</u> |
| NAME OF OWNER (if different) <u>- Same -</u> | | BUSINESS TELEPHONE <u>(516) 242-2500</u> | |
| ADDRESS <u>-</u> | | | |
| CITY/PO <u>-</u> | | STATE <u>-</u> | ZIP CODE <u>-</u> |
| DESCRIPTION OF ACTION <u>Subdivision of 2 buildings on into INTO 2 SEPARATE PARCELS.</u> | | | |

Please Complete Each Question—Indicate N.A. if not applicable

A. Site Description

Physical setting of overall project, both developed and undeveloped areas.

1. Present land use: ☐ Urban ☒ Industrial ☐ Commercial ☐ Residential (suburban) ☐ Rural (non-farm)
☐ Forest ☐ Agriculture ☐ Other _____

2. Total acreage of project area: 12.313 acres.

APPROXIMATE ACREAGE

| | PRESENTLY | AFTER COMPLETION |
|-------------------------------------------------------------|------------------|------------------|
| Meadow or Brushland (Non-agricultural) | <u>0</u> acres | <u>0</u> acres |
| Forested | <u>0</u> acres | <u>0</u> acres |
| Agricultural (Includes orchards, cropland, pasture, etc.) | <u>0</u> acres | <u>0</u> acres |
| Wetland (Freshwater or tidal as per Articles 24, 25 of ECL) | <u>0</u> acres | <u>0</u> acres |
| Water Surface Area | <u>0</u> acres | <u>0</u> acres |
| Unvegetated (Rock, earth or fill) | <u>0</u> acres | <u>0</u> acres |
| Roads, buildings and other paved surfaces | <u>9.5</u> acres | <u>9.5</u> acres |
| Other (Indicate type) <u>LANDSCAPING</u> | <u>2.8</u> acres | <u>2.8</u> acres |

3. What is predominant soil type(s) on project site? CUT and Fill Land
- a. Soil drainage: ☒ Well drained 100 % of site ☐ Moderately well drained _____ % of site
☐ Poorly drained _____ % of site
- b. If any agricultural land is involved, how many acres of soil are classified within soil group 1 through 4 of the NYS Land Classification System? NA acres. (See 1 NYCRR 370).
4. Are there bedrock outcroppings on project site? ☐ Yes ☒ No
- a. What is depth to bedrock? _____ (in feet)

Approximate percentage of proposed project site with slopes: ☒ 0-10% 16 % ☐ 10-15% ☐ 15% or greater % (16)

Is project substantially contiguous to, or contain a building, site, or district, listed on the State or the National Registers of Historic Places? ☐ Yes ☒ No

Is project substantially contiguous to a site listed on the Register of National Natural Landmarks? ☐ Yes ☒ No

What is the depth of the water table? 16.4 (in feet)

Is site located over a primary, principal, or sole source aquifer? ☒ Yes ☐ No (16)

Do hunting, fishing or shell fishing opportunities presently exist in the project area? ☐ Yes ☒ No

Does project site contain any species of plant or animal life that is identified as threatened or endangered?
☐ Yes ☒ No According to _____
Identify each species _____

Are there any unique or unusual land forms on the project site? (i.e., cliffs, dunes, other geological formations)
☐ Yes ☒ No Describe _____

Is the project site presently used by the community or neighborhood as an open space or recreation area?
☐ Yes ☒ No If yes, explain _____

Does the present site include scenic views known to be important to the community?
☐ Yes ☒ No

Streams within or contiguous to project area: None
a. Name of Stream and name of River to which it is tributary _____

Lakes, ponds, wetland areas within or contiguous to project area:
a. Name None b. Size (In acres) _____

Is the site served by existing public utilities? ☒ Yes ☐ No
a) If Yes, does sufficient capacity exist to allow connection? ☐ Yes ☐ No
b) If Yes, will improvements be necessary to allow connection? ☐ Yes ☒ No

Is the site located in an agricultural district certified pursuant to Agriculture and Markets Law, Article 25-AA, Section 303 and 304? ☐ Yes ☒ No

Is the site located in or substantially contiguous to a Critical Environmental Area designated pursuant to Article 8 of the ECL, and 6 NYCRR 617? ☐ Yes ☒ No

Has the site ever been used for the disposal of solid or hazardous wastes? ☒ Yes ☐ No (16)

Project Description

Physical dimensions and scale of project (fill in dimensions as appropriate)

a. Total contiguous acreage owned or controlled by project sponsor 12.313 acres.

b. Project acreage to be developed: 12.313 acres initially; 12.313 acres ultimately (16)

c. Project acreage to remain undeveloped 1 acres.

d. Length of project, in miles: NA (If appropriate)

e. If the project is an expansion, indicate percent of expansion proposed NA %.

f. Number of off-street parking spaces existing 375; proposed 375

g. Maximum vehicular trips generated per hour 12 (upon completion of project)?

h. If residential: Number and type of housing units: NA
One Family Two Family Multiple Family Condominium
Initially _____
Ultimately _____

i. Dimensions (in feet) of largest proposed structure NA height; _____ width; _____ length.

j. Linear feet of frontage along a public thoroughfare project will occupy is? 1275 ft.

2. How much natural material (i.e., rock, earth, etc.) will be removed from the site? None tons/cubic yards
3. Will disturbed areas be reclaimed? ☐ Yes ☐ No ☐ N/A
- a. If yes, for what intended purpose is the site being reclaimed? No Construction, Existing Buildings.
- b. Will topsoil be stockpiled for reclamation? ☐ Yes ☐ No
- c. Will upper subsoil be stockpiled for reclamation? ☐ Yes ☐ No
4. How many acres of vegetation (trees, shrubs, ground covers) will be removed from site? None acres.
5. Will any mature forest (over 100 years old) or other locally-important vegetation be removed by this project? ☐ Yes ☒ No
6. If single phase project: Anticipated period of construction 0 ~~12~~ months, (including demolition).
7. If multi-phased: NA
- a. Total number of phases anticipated 1 (number).
- b. Anticipated date of commencement phase 1 1 month 1 year, (including demolition).
- c. Approximate completion date of final phase 1 month 1 year.
- d. Is phase 1 functionally dependent on subsequent phases? ☐ Yes ☐ No
8. Will blasting occur during construction? ☐ Yes ☒ No
9. Number of jobs generated: during construction NA; after project is complete 1
10. Number of jobs eliminated by this project NA
11. Will project require relocation of any projects or facilities? ☐ Yes ☒ No If yes, explain _____
12. Is surface liquid waste disposal involved? ☐ Yes ☒ No
- a. If yes, indicate type of waste (sewage, industrial, etc.) and amount _____
- b. Name of water body into which effluent will be discharged _____
13. Is subsurface liquid waste disposal involved? ☒ Yes ☐ No Type sewage 16
14. Will surface area of an existing water body increase or decrease by proposal? ☐ Yes ☒ No
- Explain _____
15. Is project or any portion of project located in a 100 year flood plain? ☐ Yes ☒ No
16. Will the project generate solid waste? ☒ Yes ☐ No 16
- a. If yes, what is the amount per month _____ tons
- b. If yes, will an existing solid waste facility be used? ☐ Yes ☐ No
- c. If yes, give name _____; location _____
- d. Will any wastes not go into a sewage disposal system or into a sanitary landfill? ☐ Yes ☐ No
- e. If Yes, explain _____
17. Will the project involve the disposal of solid waste? ☐ Yes ☒ No
- a. If yes, what is the anticipated rate of disposal? _____ tons/month.
- b. If yes, what is the anticipated site life? _____ years.
18. Will project use herbicides or pesticides? ☐ Yes ☒ No
19. Will project routinely produce odors (more than one hour per day)? ☐ Yes ☒ No
20. Will project produce operating noise exceeding the local ambient noise levels? ☐ Yes ☒ No
21. Will project result in an increase in energy use? ☐ Yes ☒ No
- If yes, indicate type(s) _____
22. If water supply is from wells, indicate pumping capacity NA gallons/minute.
23. Total anticipated water usage per day 7579 gallons/day.
24. Does project involve Local, State or Federal funding? ☐ Yes ☒ No
- If Yes, explain _____

Approvals Required:

Type

Submittal
Date

- | | |
|--------------------------------------------|---------------------------------------------------------------------|
| City, Town, Village Board | <input type="checkbox"/> Yes <input type="checkbox"/> No |
| City, <u>Town</u> , Village Planning Board | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| City, Town Zoning Board | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| City, <u>County</u> Health Department | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| Other Local Agencies | <input type="checkbox"/> Yes <input type="checkbox"/> No |
| Other Regional Agencies | <input type="checkbox"/> Yes <input type="checkbox"/> No |
| State Agencies | <input type="checkbox"/> Yes <input type="checkbox"/> No |
| Federal Agencies | <input type="checkbox"/> Yes <input type="checkbox"/> No |

SUBDIVISION
VARIANCE (JG)
SUBDIVISION
APPROVED

C. Zoning and Planning Information

- Does proposed action involve a planning or zoning decision? ☒ Yes ☐ No
If Yes, indicate decision required:
☐ zoning amendment ☒ zoning variance ☐ special use permit ☒ subdivision ☐ site plan
☐ new/revision of master plan ☐ resource management plan ☐ other _____
- What is the zoning classification(s) of the site? INDUSTRIAL
- What is the maximum potential development of the site if developed as permitted by the present zoning?
SITE IS DEVELOPED
- What is the proposed zoning of the site? NO CHANGE PROPOSED
- What is the maximum potential development of the site if developed as permitted by the proposed zoning?
NA
- Is the proposed action consistent with the recommended uses in adopted local land use plans? ☒ Yes ☐ No
- What are the predominant land use(s) and zoning classifications within a 1/4 mile radius of proposed action?
Ga - INDUSTRIAL (JG)
- Is the proposed action compatible with adjoining/surrounding land uses within a 1/4 mile? ☒ Yes ☐ No
- If the proposed action is the subdivision of land, how many lots are proposed? 2
a. What is the minimum lot size proposed? 5.285 AC
- Will proposed action require any authorization(s) for the formation of sewer or water districts? ☐ Yes ☒ No
- Will the proposed action create a demand for any community provided services (recreation, education, police, fire protection)? ☐ Yes ☒ No
a. If yes, is existing capacity sufficient to handle projected demand? ☐ Yes ☐ No
- Will the proposed action result in the generation of traffic significantly above present levels? ☐ Yes ☒ No
a. If yes, is the existing road network adequate to handle the additional traffic? ☐ Yes ☐ No

D. Informational Details

Attach any additional information as may be needed to clarify your project. If there are or may be any adverse impacts associated with your proposal, please discuss such impacts and the measures which you propose to mitigate or avoid them.

E. Verification

I certify that the information provided above is true to the best of my knowledge.

Applicant/Sponsor Name Herrnstadt Schneck Date 12-18-90
Signature [Signature] Title Land Surveyor

If the action is in the Coastal Area, and you are a state agency, complete the Coastal Assessment Form before proceeding with this assessment.

REFERENCE NO. 8

COUNTY OF SUFFOLK



ROBERT J. GAFFNEY
SUFFOLK COUNTY EXECUTIVE

DEPARTMENT OF HEALTH SERVICES

MARY E. HIBBERD, M.D., M.P.H.
COMMISSIONER

MEMORANDUM

TO: Robert Capp, P.E.
NYSDEC - Stony Brook

FROM: Robert Seyfarth *RS*

DATE: January 28, 1993

SUBJECT: **COMMERCIAL ENVELOPE - DEER PARK
FACILITY ID #472000442800001**

Please be advised that this office has received an odor complaint for the above-referenced facility.

In accordance with this department's agreement with your unit, I am forwarding a Notice of Compliance Determination, completed by Robert Morcerf of my staff, for follow-up and enforcement action as you deem necessary. I am also enclosing a copy of the complaint investigation itself.

RS:lc
Enclosure

cc: Laurie McClosky/Marlin Art

Commercial

SUFFOLK COUNTY DEPT. OF HEALTH SERVICES
UNIFORM COMPLAINT FIELD REPORT

Envelope

Air Pollution ☐
Hazardous Material & Industrial
Waste ☒
Internal Ventilation ☐
Sewage Treatment ☐
Assigned to Zone No. ☐

SCDHS No. SW 91-83 Letter ☐
SPILL No. ☐ Telephone ☒
DOT No. ☐ Person ☐
Date 6-19-91 Time 4 pm
COMPLAINANT IDENTITY CONFIDENTIAL

Referred by: ☐ Phone ☐
Complainant Transi
Address ☐ (T.V.H.) ☐ Phone ☐

Complaint Against Envelope Facilities
Address 910 Grand Blvd (T.V.H.) Beer Park Phone ☐
Cross street Burt W. Abram

Nature of Request A foamy substance is emitted out of the east side of the building every time it rains.
RCV'D by AC Assigned to ☐ Date ☐

| Persons Interviewed | Address | Phone |
|--------------------------|--------------------------|--------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Information Obtained from Interviewed Individuals:
TO INSPECTORS: Please do not use proper names in this section.

No Response

S. .OLK COUNTY DEPT. OF HEALTH SERVICES
UNIFORM COMPLAINT FIELD REPORT

Air Pollution ☒
Hazardous Material & Industrial
Waste ☐
Internal Ventilation ☐
Sewage Treatment ☐
Assigned to Zone No. ☐

SCDHS No. A93-07 Letter ☐
SPILL No. ☐ Telephone ☒
DOT No. ☐ Person ☐
Date 1-21-93 Time 1:pm
COMPLAINANT IDENTITY CONFIDENTIAL

Complaint Against Business Envelopes
Address Grand Blvd (T.V.H.) Green Park Phone ☐
Cross street ☐

Nature of Request Summers are very hot. Getting into
complainant's building.

RCVD by L.C. Assigned to ☐ Date ☐

Information Obtained from Interviewed Individuals:

TO INSPECTORS: Please do not use proper names in this section.

Q # Stated that they thought it was a gas odor
and they called Liko. Liko ~~called~~ came down
and stated that the odor appeared to be coming
from the incinerator

Inspector's Observations

1/22/93 - No visible smoke noted at the time of my visit. Incinerator did not appear to be in use at this time

1/25/93 - Same as above

Name of Responsible Individuals

Address


Tel. No.

Inspector's Recommendation to Persons Concerned None


Information Related by Inspector to Complainant: Will forward complaint info to NYS DEC via NOCD. Will monitor s. to.

Sketch:

Grand Bud.



Incinerator Stack



Inspectors Signature

Ralph Morcerf
MORCERF

Date

1/26/93

Inspected on 1/25/93 AT : AM/PM time

NOTICE OF COMPLIANCE DETERMINATION

INSPECTION PERFORMED BY (print) MORCERF TITLE Sanitarian Scotts

DEC REPRESENTATIVE'S SIGNATURE _____ DATE _____

DEC RESERVES THE RIGHT TO TAKE FURTHER ENFORCEMENT ACTION FOR ANY VIOLATION NOTED IN THIS NOCD OR ANY OTHER VIOLATION OF THE ENVIRONMENTAL CONSERVATION LAW

for further information please contact -

Robert Capp
name

DEC Engineer
title

754-7900
phone no.

REFERENCE NO. 9

PHONE CONVERSATION RECORD

Conversation with:

Name Cindy

Company Tax Assessors Office

Address _____

Phone (516) 957-3014

Subject Ownership of site

Date April / 15 / 1994

Time 11:40 AM/PM

☒ Originator Placed Call

☐ Originator Received Call

W.O. NO. 04200-022-081-0006

Notes: Called to confirm/update ownership of property. Property at 900 Grand Boulevard in Deer Park, formerly District 100, Section 67, Block 1, Lots 22.02, 24.55 and 24.65 is now Lot 22.23. The lots were apportioned/joined in July 1992. The property is 7.1 acres and is owned by MAS Boulevard Association (mailing address: 900 Grand Boulevard, Deer Park). The computer files do not go back to 1986; MAS Boulevard Associates purchased property prior to July 1992, all computer records indicate MAS as owner/ no change in ownership. Any apportionment questions should go to Mary Ann

☒ File _____

☐ Tickle File _____ / _____ / _____

☐ Follow-Up By: _____

☐ Copy/Route To: _____

Follow-Up-Action: DDM

Originator's Initials DDM

REFERENCE NO. 10



- LEGEND**
- - Public/municipal well/well field
 - B - Brentwood Water District
 - D - Dix Hills Water District
 - S - Suffolk County Water Authority

SCALE 1:24,000

1000 0 1000 2000 3000 4000 5000 6000 7000 FEET

1 KILOMETER

CONTOUR INTERVAL 5 FEET
NATIONAL GEODETIC VERTICAL DATUM OF 1929
DEPTH CURVES AND SOUNDINGS IN FEET—DATUM IS MEAN LOW WATER
THE RELATIONSHIP BETWEEN THE TWO DATUMS IS VARIABLE
SHORLING SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER
THE MEAN RANGE OF TIDE IS APPROXIMATELY 1:3 FEET

| | | | |
|---------------------------------------------------------------------------------|--|-------------------------------|--|
| WESTON MANAGERS DESIGNERS/CONSULTANTS | | FOUR-MILE VICINITY MAP | |
| SITE NAME: COMMERCIAL ENVELOPE MFG. CO., INC. DEER PARK, NY | | | |
| DATE: 11 MAY 1994 | | SCALE: 1"=2,000' | |
| UGCS QUAD: | | GREENLAWN, NY | |

REFERENCE NO. 11



PROJECT NOTE

TO: Commercial Envelope Mfg. Co. Inc. file DATE: 20 June 1994
 FROM: D. D. Mirsavage W.O. NO.: 04200-022-081-0006-02
 SUBJECT: Potable water sources within 4 miles of the site.

Three public/municipal water systems supply drinking water to people living within 4 miles of the site. Each of the public/municipal systems obtains water from groundwater wells; some of the wells are located within 4 miles of the site. All of the public/municipal wells located within 4 miles of the site obtain water from the Glacial or Magothly aquifers. The populations served by these wells is presented below:

Dix Hills Water District - serves 30,000 people, operates 15 wells: 8 Glacial, 7 Magothly [Attachment A]

2-3 miles: Plant #10 - 1 well; Magothly - serves ~2,000 people (D-10)

3-4 miles: Plant #3 - 3 wells (D-3(3)); Glacial

Plant #4 - 1 well (D-4); Glacial

Plant #8 - 1 well (D-8); Glacial

5 wells, serve ~10,000 people

Plant #6 - 3 wells (D-6(3)); Magothly

Plant #9 - 2 wells (D-9(2)); Magothly

5 wells, serve ~10,000 people

Brentwood Water District - serves 6,500 connections ~ 12,760 people, operates 5 wells - all Magothly

2-3 miles: Well field #1 - 2 wells (B-1(2)); Magothly, serve ~7,904 people

3-4 miles: Well field #2 - 2 wells (B-2(2)); Magothly

Well field #3 - 1 well (B-3); Magothly

3 wells, serve ~11,856 people.

[Attachments B and C]

Suffolk County Water Authority - serves 308,352 connections ~ 937,390 people, operates 404 wells

[Attachments C-E]

1/2 - 1 mile: Brook Avenue - 4 wells (S-B(4)); Magothly

Industry Court - 2 wells (S-I(2)); Magothly

6 wells, serve ~13,922 people

1-2 miles: Locust Drive - 3 wells (S-L(3)); 2 Glacial, serve ~4,640 people

1 Magothly

Bay Shore - 2 wells (S-B'(2)); Magothly

Plymouth Street - 3 wells (S-P(3)); Magothly

Harvest Lane - 4 wells (S-H(4)); Magothly

10 wells, serve ~23,203 people

(continued)



PROJECT NOTE

TO: Commercial Envelope Mfg Co, Inc. fileDATE: 20 June 1994FROM: J.D. MinsavageW.O. NO.: 04200-022-081-0006-02SUBJECT: Potable water sources within 4 miles of the siteSuffolk County Water Authority (continued) -

2-3 miles: Adams Avenue - 2 wells (S-A(2)); Magothy

August Road - 3 wells (S-A'(3)); Magothy

East Forks Road - 2 wells (S-E(2)); Magothy

Enjay Boulevard - 3 wells (S-E'(3)); Magothy

Sunrise Highway - 3 wells (S-S'(3)); Magothy

Thomas Avenue - 2 wells (S-T(2)); Magothy

Wyandanch Avenue - 2 wells (S-W(2)); Magothy

17 wells, serve ~ 39,445 people

3-4 miles: Circle Drive - 4 wells (S-C(4)); Magothy

Gordon Avenue - 2 wells (S-G(2)); Magothy

Prospect Avenue - 3 wells (S-P'(3)); Magothy

Smith Street - 3 wells (S-S(3)); Magothy

Union Boulevard - 3 wells (S-U(3)); Magothy

15 wells, serve ~ 34,804 people

The calculation of the number of people served by each aquifer is presented below:

Glacial aquifer:

0 - 1/4 mile = 0

1/4 - 1/2 mile = 0

1/2 - 1 mile = 0

1 - 2 miles = 4,640 (Suffolk County)

2 - 3 miles = 0

3 - 4 miles = 10,000 (Dix Hills)

Magothy Aquifer:

0 - 1/4 mile = 0

1/4 - 1/2 mile = 0

1/2 - 1 mile = 13,922 (Suffolk County)

The nearest potable well is the Brook Avenue wellfield, located approximately 0.8 mile south-southwest of the site.

(continued)



PROJECT NOTE

TO: Commercial Envelope Mfg Co Inc. file

DATE: 20 June 1994

FROM: D.D. Minsavage

W.O. NO.: 04200-022-081-0006-02

SUBJECT: Potable water sources within 4 miles of the site.

Magothy Aquifer (continued):

1-2 miles = 23,203 (Suffolk County)

2-3 miles = 2,000 (Dix Hills)

7,904 (Brentwood)

+39,445 (Suffolk County)

 $\Sigma = 49,349$

3-4 miles = 10,000 (Dix Hills)

11,856 (Brentwood)

+34,804 (Suffolk County)

 $\Sigma = 56,660$

The public/municipal wells have been plotted on the "Four-Mile Map" for Commercial Envelope Mfg Co. Inc.

A printout of wells located within 4 miles of the site confirms that all wells are drawing from either the Glacial or Magothy aquifers [Attachment F]. Also, no private/domestic wells are indicated on the printout.

PHONE CONVERSATION RECORD

Conversation with:

Name Vinny Candura

Company Dix Hills Water District

Address _____

Phone (514) 421-1812

Subject Groundwater was within 4 miles of the site

Date June / 13 / 1994

Time 8:25 AM PM

☒ Originator Placed Call

☐ Originator Received Call

W.O. NO. 04200-022-081-0006-02

Notes: Dix Hills operates 15 wells and supplies water to 7,900 plus service connections or approximately 30,000 people. Dix Hills does not purchase or sell bulk quantities of water to/from other systems; emergency interconnections only.

• Plant #1: Caledonia Rd by Wolf Hill on northeast corner (south of park)
2 wells - glacial

• Plant #5: between Danny and Norman off Vanderbilt : 1 well - glacial

• Plant #7: Elkland Rd, ~500ft west of Woodmont : 1 well - Magoghy

• Plant #9: Thorn Grove; below Empire, not quite at southern bend : 2 wells - Magoghy

• Plant #8: Ryder, between South Hollow and Wright : 1 well - glacial

• Plant #6: Deer Park Ave; between Landview and Tiana : 3 wells - Magoghy

• Plant #4: Intersection of Herter and Colby : 1 well - glacial

• Plant #3: Carl's Straight Path opposite Sweetwater (on east) : 3 wells - glacial

• Plant #10: Intersection of Seneca and Otsego : 1 well - Magoghy

Plant #10 is located ~2.4 miles northwest of the site (1 well)

Plants #3, 4, 6, 8 and 9 are located 3 to 4 miles from the site (10 wells)

Plants #1, 5 and 7 are located >4 miles from the site (4 wells)

☒ File Commercial Envelope

☐ Tickle File _____

☐ Follow-Up By: _____

☐ Copy/Route To: _____

Follow-Up-Action: _____

Originator's Initials DDM

BRENTWOOD WATER DISTRICT
TOWN OF ISLIP

51 THIRD AVENUE • P.O. BOX 2
BRENTWOOD, NEW YORK 11717



ATTACHMENT B

FRANCIS X. PIPINO
Superintendent

April 18th, 1994

Weston
Raritan Plaza
4th Floor Raritan Center
Edison, N.J. 08837

Attention: Diane Donovan Minsavage

Dear Ms. Savage:

As per your request regarding EPA contract no. 68-W9-0022, please be advised of the following:

- (1) Source is ground water
- (A) Total number of active wells = 5
- (B) Main office - well field #1, 51 Third Avenue, First Street to the East
 - Well 1-3, Magothy, 550'
 - Well 1-4, Magothy, 750'

Well Field #2 Morris Street, Lincoln Avenue to the East

- Well 2-2, Magothy, 436'
- Well 2-3, Magothy, 755'


Well Field #3 American Blvd., 2nd Avenue, to the North

- Well 3-1, Magothy, 905'

- (2) All source wells cover 100% of the District
- (3) Total services 6,500
 - All residences and businesses are connected to the system
- (4) The entire system is interconnected
- (5) We do not sell water in bulk

If you have any further questions feel free to call the office.

Very truly yours,


Michael H. Nelson
Assistant Superintendent
BRENTWOOD WATER DISTRICT

90-GU8

ATTACHMENT C

10/91

**1990 CENSUS POPULATION AND GROUP QUARTERS COUNTS,
VACANCY STATUS, AND PERSONS PER UNIT**

FOR

ALL GOVERNMENTAL UNITS

Prepared by: New York State, Dept. of Economic Development, State Data Center

1990 Census Population and Group Quarter Counts, Vacancy Status and Persons Per Occupied Housing Units
For
New York State Minor Civil Divisions by County and Places.

| Area Name | Total Population | Total Group Quarters Population | Institutional Group Quarters Population | Percent Total Group Quarters Population | Total Housing Units | Total Vacant Housing Units | Percent Vacant Housing Units | Persons Per Occupied Housing Units |
|---------------------------------|---------------------|------------------------------------------|--------------------------------------------------|-----------------------------------------------------|---------------------------|-------------------------------------|---------------------------------------|------------------------------------------------|
| Suffolk County..... | 1,321,864 | 29,394 | 16,882 | 2.22 | 481,317 | 56,598 | 11.76 | 3.04 ← |
| Babylon town..... | 202,889 | 2,957 | 1,471 | 1.46 | 66,819 | 2,313 | 3.46 | 3.10 |
| Amityville village..... | 9,286 | 920 | 859 | 9.91 | 3,300 | 148 | 4.48 | 2.65 |
| Babylon village..... | 12,249 | 200 | 200 | 1.63 | 4,536 | 180 | 3.97 | 2.77 |
| Copague CDP..... | 20,769 | 44 | 0 | 0.21 | 7,067 | 135 | 1.91 | 2.99 |
| Deer Park CDP..... | 28,840 | 0 | 0 | 0.00 | 9,616 | 200 | 2.08 | 3.06 |
| East Farmingdale CDP..... | 4,510 | 51 | 0 | 1.13 | 1,495 | 51 | 3.41 | 3.09 |
| Lindenhurst village..... | 26,879 | 141 | 11 | 0.52 | 8,847 | 247 | 2.79 | 3.11 |
| North Amityville CDP..... | 13,849 | 226 | 0 | 1.63 | 4,316 | 325 | 7.53 | 3.41 |
| North Babylon CDP..... | 18,081 | 0 | 0 | 0.00 | 6,123 | 183 | 2.99 | 3.04 |
| North Lindenhurst CDP..... | 10,563 | 8 | 0 | 0.08 | 3,404 | 81 | 2.38 | 3.18 |
| West Babylon CDP..... | 42,410 | 468 | 394 | 1.10 | 13,799 | 357 | 2.59 | 3.12 |
| Wheatley Heights CDP..... | 5,027 | 38 | 7 | 0.76 | 1,449 | 18 | 1.24 | 3.49 |
| Wyandanch CDP..... | 8,950 | 71 | 0 | 0.79 | 2,362 | 143 | 6.05 | 4.00 |
| Brookhaven town..... | 407,779 | 10,790 | 3,700 | 2.65 | 140,677 | 11,585 | 8.24 | 3.08 |
| Belle Terre village..... | 839 | 0 | 0 | 0.00 | 280 | 12 | 4.29 | 3.13 |
| Bellport village..... | 2,572 | 0 | 0 | 0.00 | 1,120 | 130 | 11.61 | 2.60 |
| Blue Point CDP..... | 4,230 | 59 | 19 | 1.39 | 1,548 | 91 | 5.88 | 2.86 |
| Brookhaven CDP..... | 3,118 | 171 | 171 | 5.48 | 1,097 | 87 | 7.93 | 2.92 |
| Calverton CDP (pt.)..... | 1,093 | 0 | 0 | 0.00 | 420 | 46 | 10.95 | 2.92 |
| Centereach CDP..... | 26,720 | 233 | 188 | 0.87 | 7,801 | 181 | 2.32 | 3.48 |
| Center Moriches CDP..... | 5,987 | 34 | 31 | 0.57 | 2,316 | 221 | 9.54 | 2.84 |
| Coram CDP..... | 30,111 | 417 | 316 | 1.38 | 10,737 | 607 | 5.65 | 2.93 |
| East Moriches CDP..... | 4,021 | 130 | 109 | 3.23 | 1,542 | 242 | 15.69 | 2.99 |
| East Patchogue CDP..... | 20,195 | 539 | 471 | 2.67 | 7,446 | 373 | 5.01 | 2.78 |
| East Shoreham CDP..... | 5,461 | 114 | 104 | 2.09 | 1,671 | 79 | 4.73 | 3.36 |
| Farmingville CDP..... | 14,842 | 73 | 0 | 0.49 | 4,560 | 195 | 4.28 | 3.38 |
| Holbrook CDP (pt.)..... | 5,063 | 12 | 0 | 0.24 | 1,474 | 33 | 2.24 | 3.51 |
| Holtsville CDP (pt.)..... | 12,530 | 12 | 12 | 0.10 | 3,749 | 101 | 2.69 | 3.43 |
| Lake Grove village..... | 9,612 | 94 | 93 | 0.98 | 3,301 | 230 | 6.97 | 3.10 |
| Lake Ronkonkoma CDP (pt.)..... | 14,708 | 445 | 236 | 3.03 | 4,864 | 166 | 3.41 | 3.04 |
| Manorville CDP..... | 6,198 | 33 | 33 | 0.53 | 2,567 | 248 | 9.66 | 2.66 |
| Mastic CDP (pt.)..... | 13,642 | 14 | 10 | 0.10 | 4,188 | 300 | 7.16 | 3.51 |
| Mastic Beach CDP..... | 10,293 | 0 | 0 | 0.00 | 4,212 | 846 | 20.09 | 3.06 |
| Medford CDP..... | 21,274 | 56 | 9 | 0.26 | 6,458 | 235 | 3.64 | 3.41 |
| Middle Island CDP..... | 7,848 | 316 | 296 | 4.03 | 3,184 | 320 | 10.05 | 2.63 |
| Miller Place CDP..... | 9,315 | 42 | 10 | 0.45 | 3,039 | 167 | 5.50 | 3.23 |
| Mount Sinai CDP..... | 8,023 | 26 | 26 | 0.32 | 2,559 | 163 | 6.37 | 3.34 |
| North Bellport CDP..... | 8,182 | 39 | 0 | 0.48 | 2,231 | 132 | 5.92 | 3.88 |
| North Patchogue CDP..... | 7,374 | 65 | 43 | 0.88 | 2,640 | 163 | 6.17 | 2.95 |
| Old Field village..... | 765 | 12 | 12 | 1.57 | 325 | 52 | 16.00 | 2.76 |
| Patchogue village..... | 11,060 | 192 | 0 | 1.74 | 4,844 | 414 | 8.55 | 2.45 |
| Poquott village..... | 770 | 0 | 0 | 0.00 | 313 | 39 | 12.46 | 2.81 |
| Port Jefferson village..... | 7,455 | 550 | 465 | 7.38 | 2,908 | 289 | 9.94 | 2.64 |
| Port Jefferson Station CDP..... | 7,232 | 92 | 43 | 1.27 | 2,602 | 135 | 5.19 | 2.89 |
| Ridge CDP..... | 11,734 | 192 | 127 | 1.64 | 5,349 | 455 | 8.51 | 2.36 |
| Rocky Point CDP..... | 8,596 | 15 | 0 | 0.17 | 3,870 | 724 | 18.71 | 2.73 |
| Selden CDP..... | 20,608 | 60 | 12 | 0.29 | 6,425 | 225 | 3.50 | 3.31 |
| Setauket-East Setauket CDP..... | 13,634 | 9 | 0 | 0.07 | 4,595 | 189 | 4.11 | 3.09 |
| Shirley CDP..... | 22,936 | 40 | 0 | 0.17 | 7,021 | 521 | 7.42 | 3.52 |
| Shoreham village..... | 540 | 0 | 0 | 0.00 | 204 | 24 | 11.76 | 3.00 |
| Sound Beach CDP..... | 9,102 | 40 | 0 | 0.44 | 3,575 | 479 | 13.40 | 2.93 |
| Stony Brook CDP (pt.)..... | 13,726 | 62 | 0 | 0.45 | 4,757 | 238 | 5.00 | 3.02 |
| Terryville CDP..... | 10,275 | 33 | 0 | 0.32 | 3,020 | 98 | 3.25 | 3.51 |
| Yaphank CDP..... | 4,637 | 893 | 857 | 19.26 | 1,506 | 107 | 7.10 | 2.68 |
| East Hampton town..... | 16,132 | 150 | 19 | 0.93 | 17,068 | 10,186 | 59.68 | 2.32 |
| East Hampton village..... | 1,402 | 19 | 19 | 1.36 | 1,684 | 1,010 | 59.98 | 2.05 |
| East Hampton North CDP..... | 2,780 | 0 | 0 | 0.00 | 1,889 | 688 | 36.42 | 2.31 |
| Montauk CDP..... | 3,001 | 124 | 0 | 4.13 | 3,996 | 2,755 | 68.94 | 2.32 |
| Northwest Harbor CDP..... | 2,167 | 0 | 0 | 0.00 | 2,310 | 1,425 | 61.69 | 2.45 |
| Sag Harbor village (pt.)..... | 858 | 1 | 0 | 0.12 | 782 | 397 | 50.77 | 2.23 |
| Springs CDP..... | 4,355 | 6 | 0 | 0.14 | 3,459 | 1,672 | 48.34 | 2.43 |
| Huntington town..... | 191,474 | 3,017 | 2,592 | 1.58 | 64,842 | 1,981 | 3.06 | 3.00 |
| Asharoken village..... | 807 | 13 | 0 | 1.61 | 346 | 45 | 13.01 | 2.64 |
| Centerport CDP..... | 5,333 | 45 | 45 | 0.84 | 2,042 | 88 | 4.31 | 2.71 |
| Cold Spring Harbor CDP..... | 4,789 | 0 | 0 | 0.00 | 1,747 | 71 | 4.06 | 2.86 |

1990 Census Population and Group Quarter Counts, Vacancy Status and Persons Per Occupied Housing Units
For
New York State Minor Civil Divisions by County and Places.

| Area Name | Total Population | Total Group Quarters Population | Institutional Group Quarters Population | Percent Total Group Quarters Population | Total Housing Units | Total Vacant Housing Units | Percent Vacant Housing Units | Persons Per Occupied Housing Units |
|---------------------------------|---------------------|------------------------------------------|--------------------------------------------------|-----------------------------------------------------|---------------------------|-------------------------------------|---------------------------------------|------------------------------------------------|
| Comack CDP (pt.)..... | 12,210 | 300 | 300 | 2.46 | 3,731 | 59 | 1.58 | 3.24 |
| Dix Hills CDP..... | 25,849 | 194 | 116 | 0.75 | 7,698 | 125 | 1.62 | 3.39 |
| East Northport CDP..... | 20,411 | 95 | 85 | 0.47 | 6,970 | 177 | 2.54 | 2.99 |
| Eatons Neck CDP..... | 1,499 | 0 | 0 | 0.00 | 563 | 50 | 8.88 | 2.92 |
| Elwood CDP..... | 10,916 | 92 | 47 | 0.84 | 3,387 | 70 | 2.07 | 3.26 |
| Fort Salonga CDP (pt.)..... | 5,602 | 0 | 0 | 0.00 | 1,957 | 108 | 5.52 | 3.03 |
| Greenlawn CDP..... | 13,208 | 312 | 312 | 2.36 | 4,421 | 89 | 2.01 | 2.98 |
| Halesite CDP..... | 2,687 | 0 | 0 | 0.00 | 1,004 | 34 | 3.39 | 2.77 |
| Huntington CDP..... | 18,243 | 208 | 167 | 1.14 | 7,013 | 252 | 3.59 | 2.67 |
| Huntington Bay village..... | 1,521 | 0 | 0 | 0.00 | 542 | 27 | 4.98 | 2.95 |
| Huntington Station CDP..... | 28,247 | 166 | 47 | 0.59 | 9,968 | 377 | 3.78 | 2.93 |
| Lloyd Harbor village..... | 3,343 | 77 | 18 | 2.30 | 1,106 | 68 | 6.15 | 3.15 |
| Melville CDP..... | 12,586 | 57 | 0 | 0.45 | 4,014 | 91 | 2.27 | 3.19 |
| Northport village..... | 7,572 | 46 | 43 | 0.61 | 3,010 | 129 | 4.29 | 2.61 |
| South Huntington CDP..... | 9,624 | 340 | 340 | 3.53 | 3,297 | 82 | 2.49 | 2.89 |
| West Hills CDP..... | 5,849 | 0 | 0 | 0.00 | 1,993 | 37 | 1.86 | 2.99 |
| Islip town..... | 299,587 | 6,657 | 4,457 | 2.22 | 95,314 | 5,588 | 5.86 | 3.26 |
| Bayport CDP..... | 7,702 | 47 | 47 | 0.61 | 2,755 | 195 | 7.08 | 2.99 |
| Bay Shore CDP..... | 21,279 | 283 | 146 | 1.33 | 7,938 | 524 | 6.60 | 2.83 |
| Baywood CDP..... | 7,351 | 10 | 10 | 0.14 | 2,214 | 42 | 1.90 | 3.38 |
| Bohemia CDP..... | 9,556 | 177 | 155 | 1.85 | 3,200 | 106 | 3.31 | 3.03 |
| Brentwood CDP..... | 45,218 | 639 | 213 | 1.41 | 12,023 | 248 | 2.06 | 3.79 |
| Brightwaters village..... | 3,265 | 10 | 10 | 0.31 | 1,150 | 30 | 2.61 | 2.91 |
| Central Islip CDP..... | 26,028 | 119 | 23 | 0.46 | 7,697 | 301 | 3.91 | 3.50 |
| East Islip CDP..... | 14,325 | 170 | 160 | 1.19 | 4,670 | 100 | 2.14 | 3.10 |
| Hauppauge CDP (pt.)..... | 9,593 | 112 | 0 | 1.17 | 3,183 | 128 | 4.02 | 3.10 |
| Holbrook CDP (pt.)..... | 20,210 | 38 | 37 | 0.19 | 6,156 | 160 | 2.60 | 3.36 |
| Holtsville CDP (pt.)..... | 2,442 | 0 | 0 | 0.00 | 783 | 26 | 3.32 | 3.23 |
| Islandia village..... | 2,769 | 2 | 0 | 0.07 | 930 | 50 | 5.38 | 3.14 |
| Islip CDP..... | 18,924 | 105 | 105 | 0.55 | 6,458 | 355 | 5.50 | 3.08 |
| Islip Terrace CDP..... | 5,530 | 0 | 0 | 0.00 | 1,667 | 34 | 2.04 | 3.39 |
| North Bay Shore CDP..... | 12,799 | 46 | 0 | 0.36 | 3,464 | 78 | 2.25 | 3.77 |
| North Great River CDP..... | 3,964 | 0 | 0 | 0.00 | 1,125 | 18 | 1.60 | 3.58 |
| Oakdale CDP..... | 7,875 | 226 | 0 | 2.87 | 2,772 | 133 | 4.80 | 2.90 |
| Ocean Beach village..... | 131 | 0 | 0 | 0.00 | 574 | 514 | 89.55 | 2.18 |
| Ronkonkoma CDP..... | 20,391 | 60 | 45 | 0.29 | 6,522 | 190 | 2.91 | 3.21 |
| Saltaire village..... | 38 | 0 | 0 | 0.00 | 373 | 358 | 95.98 | 2.53 |
| Sayville CDP..... | 16,550 | 199 | 157 | 1.20 | 5,560 | 152 | 2.73 | 3.02 |
| West Bay Shore CDP..... | 4,907 | 0 | 0 | 0.00 | 1,788 | 104 | 5.82 | 2.91 |
| West Islip CDP..... | 28,419 | 328 | 328 | 1.15 | 8,657 | 187 | 2.16 | 3.32 |
| West Sayville CDP..... | 4,680 | 114 | 66 | 2.44 | 1,884 | 361 | 19.16 | 3.00 |
| Poospatuck Reservation..... | 136 | 0 | 0 | 0.00 | 46 | 1 | 2.17 | 3.02 |
| Natic CDP (pt.)..... | 136 | 0 | 0 | 0.00 | 46 | 1 | 2.17 | 3.02 |
| Riverhead town..... | 23,011 | 733 | 472 | 3.19 | 10,801 | 2,065 | 19.12 | 2.55 |
| Aquebogue CDP..... | 2,060 | 10 | 0 | 0.49 | 956 | 149 | 15.59 | 2.54 |
| Calverton CDP (pt.)..... | 3,666 | 55 | 0 | 1.50 | 1,921 | 188 | 9.79 | 2.08 |
| Jamesport CDP..... | 1,532 | 56 | 0 | 3.66 | 962 | 393 | 40.85 | 2.59 |
| Riverhead CDP..... | 8,814 | 448 | 361 | 5.08 | 3,536 | 313 | 8.85 | 2.60 |
| Wading River CDP..... | 5,317 | 134 | 111 | 2.52 | 2,142 | 331 | 15.45 | 2.86 |
| Shelter Island town..... | 2,263 | 0 | 0 | 0.00 | 2,148 | 1,131 | 52.65 | 2.23 |
| Dering Harbor village..... | 28 | 0 | 0 | 0.00 | 27 | 14 | 51.85 | 2.15 |
| Shelter Island CDP..... | 1,193 | 0 | 0 | 0.00 | 871 | 375 | 43.05 | 2.41 |
| Shelter Island Heights CDP..... | 1,042 | 0 | 0 | 0.00 | 1,250 | 742 | 59.36 | 2.05 |
| Shinnecock Reservation..... | 375 | 0 | 0 | 0.00 | 173 | 38 | 21.97 | 2.78 |
| Smithtown town..... | 113,406 | 3,280 | 3,213 | 2.89 | 36,828 | 1,263 | 3.43 | 3.10 |
| Comack CDP (pt.)..... | 23,914 | 59 | 31 | 0.25 | 7,572 | 140 | 1.85 | 3.21 |
| Fort Salonga CDP (pt.)..... | 3,574 | 26 | 0 | 0.73 | 1,174 | 57 | 4.86 | 3.18 |
| Hauppauge CDP (pt.)..... | 10,157 | 3 | 3 | 0.03 | 3,414 | 95 | 2.78 | 3.06 |
| Head of the Harbor village..... | 1,354 | 0 | 0 | 0.00 | 465 | 27 | 5.81 | 3.09 |
| Kings Park CDP..... | 17,773 | 2,052 | 2,052 | 11.55 | 5,591 | 260 | 4.65 | 2.95 |
| Lake Ronkonkoma CDP (pt.)..... | 4,289 | 35 | 35 | 0.82 | 1,401 | 72 | 5.14 | 3.20 |
| Nesconset CDP..... | 10,712 | 234 | 234 | 2.18 | 3,308 | 130 | 3.93 | 3.30 |
| Nissequoque village..... | 1,620 | 0 | 0 | 0.00 | 576 | 38 | 6.60 | 3.01 |
| St. James CDP..... | 12,703 | 476 | 476 | 3.75 | 4,428 | 172 | 3.88 | 2.87 |
| Smithtown CDP..... | 25,638 | 395 | 382 | 1.54 | 8,360 | 261 | 3.12 | 3.12 |
| Stony Brook CDP (pt.)..... | 0 | 0 | 0 | 0.00 | 0 | 0 | 0.00 | 0.00 |

1990 Census Population and Group Quarter Counts, Vacancy Status and Persons Per Occupied Housing Units
For
New York State Minor Civil Divisions by County and Places.

| Area Name | Total Population | Total Group Quarters Population | Institutional Group Quarters Population | Percent Total Group Quarters Population | Total Housing Units | Total Vacant Housing Units | Percent Vacant Housing Units | Persons Per Occupied Housing Units |
|------------------------------------|---------------------|------------------------------------------|--------------------------------------------------|-----------------------------------------------------|---------------------------|-------------------------------------|---------------------------------------|------------------------------------------------|
| Village of the Branch village..... | 1,669 | 0 | 0 | 0.00 | 538 | 11 | 2.04 | 3.17 |
| Southampton town..... | 44,976 | 1,594 | 790 | 3.54 | 33,622 | 15,593 | 46.38 | 2.41 |
| Bridgehampton CDP..... | 1,997 | 21 | 0 | 1.05 | 1,573 | 811 | 51.56 | 2.59 |
| East Quogue CDP..... | 4,372 | 12 | 12 | 0.27 | 2,985 | 1,204 | 40.34 | 2.45 |
| Flanders CDP..... | 3,231 | 32 | 12 | 0.99 | 1,459 | 336 | 23.03 | 2.85 |
| Hampton Bays CDP..... | 7,893 | 136 | 10 | 1.72 | 5,227 | 1,951 | 37.33 | 2.37 |
| North Haven village..... | 713 | 0 | 0 | 0.00 | 505 | 198 | 39.21 | 2.32 |
| North Sea CDP..... | 2,530 | 0 | 0 | 0.00 | 2,198 | 1,132 | 51.50 | 2.37 |
| Noyack CDP..... | 2,059 | 0 | 0 | 0.00 | 1,854 | 951 | 51.29 | 2.28 |
| Pine Valley village..... | 1,486 | 658 | 656 | 44.28 | 357 | 59 | 16.53 | 2.78 |
| Quogue village..... | 898 | 0 | 0 | 0.00 | 1,282 | 905 | 70.59 | 2.38 |
| Remsenburg-Speonk CDP..... | 1,851 | 12 | 12 | 0.65 | 1,208 | 491 | 40.65 | 2.56 |
| Riverside CDP..... | 1,300 | 0 | 0 | 0.00 | 700 | 66 | 9.43 | 2.05 |
| Sag Harbor village (pt.)..... | 1,276 | 0 | 0 | 0.00 | 957 | 359 | 37.51 | 2.13 |
| Shinnecock Hills CDP..... | 2,847 | 574 | 0 | 20.16 | 2,261 | 1,240 | 54.84 | 2.23 |
| Southampton village..... | 3,980 | 88 | 88 | 2.21 | 2,980 | 1,291 | 43.32 | 2.30 |
| Southampton CDP..... | 1,302 | 25 | 0 | 1.92 | 685 | 185 | 27.01 | 2.55 |
| Watermill CDP..... | 1,893 | 10 | 0 | 0.53 | 1,703 | 958 | 56.25 | 2.53 |
| Westhampton CDP..... | 2,129 | 26 | 0 | 1.22 | 1,486 | 667 | 44.89 | 2.57 |
| Westhampton Beach village..... | 1,571 | 0 | 0 | 0.00 | 2,485 | 1,777 | 71.51 | 2.22 |
| Southold town..... | 19,836 | 216 | 168 | 1.09 | 12,979 | 4,854 | 37.40 | 2.41 |
| Cutchogue CDP..... | 2,627 | 12 | 0 | 0.46 | 1,586 | 538 | 33.92 | 2.50 |
| Greenport village..... | 2,070 | 20 | 3 | 0.97 | 1,134 | 270 | 23.81 | 2.37 |
| Greenport West CDP..... | 1,614 | 150 | 150 | 9.29 | 1,128 | 487 | 43.17 | 2.28 |
| Laurel CDP..... | 1,094 | 0 | 0 | 0.00 | 641 | 233 | 36.35 | 2.68 |
| Mattituck CDP..... | 3,902 | 0 | 0 | 0.00 | 2,191 | 712 | 32.50 | 2.64 |
| Peconic CDP..... | 1,100 | 0 | 0 | 0.00 | 639 | 219 | 34.27 | 2.62 |
| Southold CDP..... | 5,192 | 16 | 0 | 0.31 | 3,539 | 1,290 | 36.45 | 2.30 |
| Sullivan County..... | 69,277 | 5,419 | 2,829 | 7.82 | 41,814 | 17,238 | 41.23 | 2.60 |
| Bethel town..... | 3,693 | 291 | 23 | 7.88 | 3,693 | 2,363 | 63.99 | 2.56 |
| Callicoon town..... | 3,024 | 255 | 22 | 8.43 | 1,648 | 541 | 32.83 | 2.50 |
| Jeffersonville village..... | 484 | 22 | 22 | 4.55 | 253 | 40 | 15.81 | 2.17 |
| Cochecton town..... | 1,318 | 17 | 17 | 1.29 | 889 | 385 | 43.31 | 2.58 |
| Delaware town..... | 2,633 | 361 | 38 | 13.71 | 1,244 | 356 | 28.62 | 2.56 |
| Fallsburg town..... | 11,445 | 2,631 | 1,922 | 22.99 | 6,322 | 3,075 | 48.64 | 2.71 |
| South Fallsburg CDP..... | 2,115 | 241 | 0 | 11.39 | 1,335 | 645 | 48.31 | 2.72 |
| Woodridge village..... | 783 | 8 | 8 | 1.02 | 476 | 145 | 30.46 | 2.34 |
| Forestburgh town..... | 614 | 0 | 0 | 0.00 | 465 | 262 | 52.04 | 2.75 |
| Fremont town..... | 1,332 | 1 | 0 | 0.08 | 1,084 | 585 | 53.97 | 2.67 |
| Highland town..... | 2,147 | 126 | 23 | 5.87 | 1,521 | 701 | 46.09 | 2.46 |
| Liberty town..... | 9,825 | 663 | 317 | 6.75 | 4,966 | 1,372 | 27.63 | 2.55 |
| Liberty village..... | 4,128 | 241 | 231 | 5.84 | 1,827 | 254 | 13.90 | 2.47 |
| Lumberland town..... | 1,425 | 0 | 0 | 0.00 | 1,276 | 700 | 54.86 | 2.47 |
| Mamakating town..... | 9,792 | 11 | 0 | 0.11 | 5,391 | 1,826 | 33.87 | 2.74 |
| Bloomingsburg village..... | 316 | 0 | 0 | 0.00 | 149 | 27 | 18.12 | 2.59 |
| Wurtsboro village..... | 1,048 | 0 | 0 | 0.00 | 461 | 68 | 14.75 | 2.67 |
| Neversink town..... | 2,951 | 0 | 0 | 0.00 | 1,558 | 471 | 30.23 | 2.71 |
| Rockland town..... | 4,096 | 39 | 27 | 0.95 | 2,428 | 925 | 38.10 | 2.70 |
| Livingston Manor CDP..... | 1,482 | 0 | 0 | 0.00 | 603 | 74 | 12.27 | 2.80 |
| Thompson town..... | 13,711 | 925 | 440 | 6.75 | 8,331 | 3,198 | 38.39 | 2.49 |
| Monticello village..... | 6,597 | 439 | 262 | 6.65 | 3,043 | 494 | 16.23 | 2.42 |
| Tusten town..... | 1,271 | 99 | 0 | 7.79 | 998 | 498 | 49.90 | 2.34 |
| Tioga County..... | 52,337 | 363 | 318 | 0.69 | 20,254 | 1,416 | 6.99 | 2.76 |
| Barton town..... | 8,925 | 200 | 180 | 2.24 | 3,667 | 275 | 7.50 | 2.57 |
| Waverly village..... | 4,787 | 200 | 180 | 4.18 | 2,017 | 129 | 6.40 | 2.43 |
| Berkshire town..... | 1,303 | 0 | 0 | 0.00 | 475 | 29 | 6.11 | 2.92 |
| Candor town..... | 5,310 | 0 | 0 | 0.00 | 2,041 | 156 | 7.64 | 2.82 |
| Candor village..... | 869 | 0 | 0 | 0.00 | 344 | 25 | 7.27 | 2.72 |
| Newark Valley town..... | 4,189 | 0 | 0 | 0.00 | 1,540 | 110 | 7.14 | 2.93 |
| Newark Valley village..... | 1,082 | 0 | 0 | 0.00 | 454 | 45 | 9.91 | 2.65 |
| Nichols town..... | 2,525 | 0 | 0 | 0.00 | 932 | 59 | 6.33 | 2.89 |
| Nichols village..... | 573 | 0 | 0 | 0.00 | 206 | 10 | 4.85 | 2.92 |
| Owego town..... | 21,279 | 141 | 138 | 0.66 | 8,071 | 454 | 5.63 | 2.78 |
| Apalachin CDP..... | 1,208 | 0 | 0 | 0.00 | 482 | 33 | 6.85 | 2.69 |

**SUFFOLK COUNTY WATER AUTHORITY**

Edward J. Rosavitch, P.E.
Chief Engineer

Mailing Address - P.O. Box 38, Oakdale, NY 11769-0901
(516) 563-0202
Fax No.: (516) 589-5277

May 31, 1994

Ms. Diane Donovan Minsavage
Roy F. Weston, Inc.
Raritan Plaza I
4th Floor, Raritan Center
Edison, New Jersey 08837

Re: May 9, 1994 Correspondence

Dear Ms. Minsavage:

In response to your above-referenced inquiry, I offer the following information:

1. All water supplied for potable use by the SCWA is derived from wells, and no well or wellfield supplies more than 40% of the total pumpage for the Authority. All districts are interconnected to the maximum extent possible. However, there are a few isolated areas within the Authority's distribution system that are not interconnected, particularly in eastern Suffolk County. The distribution system surrounding your area of interest is fully interconnected to other neighboring SCWA supply areas.
2. As of May 31, 1993, the Authority operated 404 wells system-wide.
3. As of May 31, 1993, the Authority served 308,352 connections. Individual wells exist throughout the Authority's service area, particularly in Eastern Suffolk County. For the area of interest, the vast majority of the residences and businesses use SCWA water, but some private wells undoubtedly exist. Information on the location of residences and businesses that use individual wells for their supply is best obtained from the Suffolk County Department of Health Services.
4. There are three water districts which are supplied with water by the SCWA at wholesale cost: the Stony Brook Water District, the St. James Water District, and the Smithtown Water District. None of these districts are located in your area of interest.

Continued . . .

- 2 -

5. The following table summarizes your requested information. All wells are screened in the Magothy aquifer except where noted.

| <u>Well & Well Field</u> | <u>Depth</u> | <u>Screened Interval</u> |
|---------------------------------------------|--------------|--------------------------|
| <i>Babylon District</i> | | |
| Adams Avenue #1 | 538 | 472-535 |
| Adams Avenue #2 | 515 | 454-512 |
| August Road #1 | Retired | |
| August Road #2 | 600 | 545-597 |
| August Road #3 | 627 | 555-624 |
| August Road #4 | 636 | 560-633 |
| Brook Avenue #1A | 449 | 385-445 |
| Brook Avenue #2 | 440 | 364-437 |
| Brook Avenue #3 | 308 | 244-304 |
| Brook Avenue #4 | 362 | 269-359 |
| Circle Drive #1 | 201 | 171-201 |
| Circle Drive #2 | 234 | 203-234 |
| Circle Drive #3 | 621 | 546-618 |
| Circle Drive #4 | 534 | 470-531 |
| Deer Park/LIRR Site Name & Location Unknown | | |
| Gordon Avenue #1 | 660 | 585-657 |
| Gordon Avenue #2 | 660 | 585-657 |
| Plymouth Street #1 | 377 | 288-374 |
| Plymouth Street #2A | 229 | 185-225 |
| Plymouth Street #3 | 415 | 346-416 |
| Prospect Avenue #1 | 676 | 605-672 |
| Prospect Avenue #2 | 674 | 603-671 |
| Prospect Avenue #3 | 440 | 310-438 |
| Smith Street #6 | 500 | 445-497 |
| Smith Street #7 | 336 | 272-333 |
| Smith Street #8 | 315 | 251-311 |
| Wyandanch Avenue #1A | 611 | 535-608 |
| Wyandanch Avenue #2 | 625 | 556-622 |
| <i>Bay Shore District</i> | | |
| Bay Shore Road #1 | 463 | 388-460 |
| Bay Shore Road #2 | 460 | 386-456 |
| East Forks Road #4 | 306 | 232-303 |
| East Forks Road #5 | 800 | 725-797 |
| Emjay Boulevard #1 | 608 | 541-604 |
| Emjay Boulevard #2 | 660 | 594-656 |
| Emjay Boulevard #3 | 634 | 529-631 |
| Harvest Lane #1 | 455 | 405-452 |
| Harvest Lane #1A | 467 | 379-464 |
| Harvest Lane #2 | 465 | 377-462 |
| Harvest Lane #3 | 623 | 514-619 |
| Landscape Drive | Future Site | |

Continued . . .

May 31, 1994

- 3 -

| <u>Well & Well Field</u> | <u>Depth</u> | <u>Screened Interval</u> |
|------------------------------------|--------------|--------------------------|
| <i>Bay Shore District (Cont'd)</i> | | |
| Locust Drive #1 | 128 | 94-125 (Glacial Aquifer) |
| Locust Drive #2 | 130 | 96-127 (Glacial Aquifer) |
| Locust Drive #3 | 611 | 516-607 |
| Locust Drive Tank Site | Future Site | |
| North Clinton Avenue | Future Site | |
| Sunrise Highway #1 | 233 | 179-229 |
| Sunrise Highway #2 | 308 | 218-305 |
| Sunrise Highway #3 | 718 | 612-715 |
| Raleigh Lane | Future Site | |
| Thomas Avenue #1 | 713 | 649-709 |
| Thomas Avenue #2 | 667 | 603-663 |
| Union Boulevard #1 | 731 | 659-728 |
| Union Boulevard #2 | 600 | 469-597 |
| Union Boulevard #3 | 721 | 657-718 |

I hope the above is satisfactory for your needs.

Sincerely,



E. J. Rosavitch, P.E.
Executive Director/Chief Engineer
Waterworks Division

EJR:SRC:dmc.

cc: S. R. Dassler
S. R. Colabufo, CPG

PHONE CONVERSATION RECORD

Conversation with:

Name Mr. Daffner

Company Suffolk County Water Authority

Address _____

Phone (516) 513-0202

Subject Deer Park / LIRR wellfield

Date June / 10 / 1994

Time 11:40 AM/PM

☒ Originator Placed Call

☐ Originator Received Call

W.O. NO. 04200-022-081-0006-02

Notes: The Deer Park / LIRR wellfield is referred to as the "Industry Court" field;
these are two wells and a stand-pipe. Well info is as follows:

Well #1, depth = 283' 4" - Magotley

Well #2, depth = 654' 5" - Magotley

DDM

☒ File Commercial Envelope

☐ Tickle File _____ / _____ / _____

☐ Follow-Up By: _____

☐ Copy/Route To: _____


Follow-Up-Action: _____

Originator's Initials DDM



United States Department of the Interior

GEOLOGICAL SURVEY
Water Resources Division
5 Aerial Way
Syosset, New York 11791
(516) 938-8830



May 31, 1994

Dennis J. Foerter
Roy F. Weston, Inc
Raritan Plaza 1
4th Floor, Raritan Center
Edison, New Jersey 08837-3616

Dear Mr. Foerter:

Enclosed is a printout of the well location and header data that you requested for the 4 mile radius search around 2 areas in Nassau and Suffolk Counties, New York. Also enclosed is the associated codes for the data.

The enclosed information is provisional and may be subject to revision at any time. In addition, the U.S. Geological Survey's computer database may not include every well within the requested retrieval area, or contain a complete record of data collected at each well site. Therefore, it is advisable to check with other federal, state and local agencies if a complete data record is required.

The total charge for the work, time and materials involved in completing this request is \$215.57.. A bill requesting payment for the above amount will be mail to you separately.

If you have any questions about the information please feel to contact me at (516) 938-8830.

Sincerely,

Ronald Busciolano
Hydrologist

DESCRIPTION OF HEADER FILE RETRIEVAL INFORMATION

WELL = New York State well identification number (ex. K 2859. 1)

AQUIFER = Code of aquifer in which well is screened (ex. 112GLCLU)

STATION ID = Unique station identification number (U.S.G.S. use only)

LAT-LONG = Latitude and longitude of well

SQ = Sequence number (U.S.G.S. use only)

LSD = Land surface elevation at well, in feet from NGVD of 1929

MP = Measuring point elevation of well, in feet from NGVD of 1929

DEPTH = Total depth of well casing, in feet below land surface

SCREEN TOP = Depth to top of screen, in feet below land surface

SCREEN BOTTOM = Depth to bottom of screen, in feet below land surface

MAX DRILL = Maximum depth well was drilled, in feet below land surface

TOWN = Town code of well

COMM = Community code of well (U.S.G.S. use only)

SWDST = Sewer district code where well is located

ZON = Physiographic zone code of well

HGSTRM = Hagstrom Atlas coordinate of well

WELUS = Primary and secondary well use code of well

AQUIFER CODES

112GLCLU = Upper Glacial Aquifer
112GRDR = Gardiners Clay
112JMCO = Jameco Aquifer
112PGFG = Port Washington Confining Unit
112PGQF = Port Washington Aquifer
112SMTN = Smithtown Clay
11220CL = 20-Foot Clay
211LLYD = Lloyd Aquifer
211MGTY = Magothy Aquifer
211MMGD = Monmouth Greensand
211RNCF = Raritan Confining Unit
400BCPX = Basement Complex (Bedrock)
999MMMM = More Than One Unit

WELL USE CODES

- 1 = Observation
- 2 = Recharge
- 3 = Test
- 4 = Well not used
- 5 = Withdrawl, unspecified
- 6 = Destrcyed
- 7 = Public supply
- 8 = Fire well
- 9 = Not found last time visited
- D = Domestic supply
- P = Plugged

COUNTY LETTER CODES
(for N.Y.S. well numbers)
(ex.- K 1234. 1)

S = Suffolk
N = Nassau
Q = Queens
K = Kings
R = Richmond
B = Bronx
M = Manhattan

MODIFYING LETTERS
(for N.Y.S. well numbers)
(ex.- K 1234. 1T)

D = Diffusion (injection) well
T = Test hole
A-Z = Replacement well with new location (except letters D or T)

HAGSTROM ATLAS LOCATION DESCRIPTION

Column 1 = County letter (ex.- ND1462)

Column 2 = Map coordinate letter (ex.- ND1462)

Column 3-4 = Map coordinate number (ex.- ND1462)

Column 5 = Coordinate box subdivision, east-west direction (ex.- ND1462)

Column 6 = Coordinate box subdivision, north-south direction (ex.- ND1462)

Subdivisions run from 0-9, starting from the upper left corner

ZONE CODES

B = Barrier beach

N = North fork

S = South fork

SEWER DISTRICT CODES

NASSAU COUNTY

- 1 = District #1 (Inwood)
- 2 = District #2 (Bay Park Plant)
- 3 = District #3 (Ceder Creek Plant)

SUFFOLK COUNTY

- 1 = Port Jefferson
- 2 = Holbrook
- 3 = Southwest Sewer District
- 4 = Birchwood/North Shore
- 5 = Strathmore/Huntington
- 6 = Kings Park
- 7 = Medford
- 8 = Strathmore Ridge
- 9 = College Park
- 10 = Stony Brook
- 11 = Selden
- 14 = Parkland
- 15 = Nob Hill

TOWN CODES

- 1 = Hempstead
- 2 = North Hempstead
- 3 = Oyster Bay
- 4 = Babylon
- 5 = Brookhaven
- 6 = East Hampton
- 7 = Huntington
- 8 = Islip
- 9 = Riverhead
- 10 = Shelter Island
- 11 = Smithtown
- 12 = Southampton
- 13 = Southold

WATER LEVEL MEASUREMENT ACCURACY CODES
(AC ON PRINTOUT)

- A = Measured, accurate to within 1 foot
- B = Measured, less accurate than 1 foot
- C = Airline measurement
- D = From driller's log
- E = From electric or other borehole log
- F = Estimated
- G = Reported (non-USGS measurement)
- H = Pressure gage
- I = Questionable measurement

WATER LEVEL MEASUREMENT REMARK CODES
(REMS ON PRINTOUT)

A = Well being pumped
B = Well pumped recently
C = Nearby well being pumped
D = Nearby well pumped recently
E = Estimated
F = Dry
G = Measurement by another agency
H = Recorder measurement
I = Affected by atmospheric pressure
J = Other
K = Tidal
L = Terminated measurement
M = Destroyed
N = Replaced
P = Estimated data
Q = Dewatering in area
R = Measured by airline pressure
U = Unknown data source
V = Plugged well
W = Measurement not within 1 hour of high tide

Commercial Envelope Mfg. Co.

| WELL | AQUIFER | STATION | ID | LAT-LONG | SQ | LSD | MP | DEPTH | --SCREEN-- | | MAX DRILL | TOWN | COMM | SWDST | ZON | HGSTRM | WELUS |
|----------------|----------|-----------------|---------------|----------|-------|--------|-----|-------|------------|--------|--------------|------|------|-------|-----|--------|-------|
| | | | | | | | | | TOP | BOTTOM | | | | | | | |
| 51 S 10373. 1 | 112GLCLU | 404322073165501 | 4043220731655 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SO 740 | |
| 52 S 10377. 1 | 112GLCLU | 404315073164801 | 4043150731648 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SO 751 | |
| 53 S 10766. 1 | 112GLCLU | 404842073172001 | 4048420731720 | 01 | 130.0 | 0.00 | 137 | 132 | 137 | 0 | 10 | 0 | 0 | 0 | 0 | SJ 857 | 5 |
| 54 S 11127. 1 | 112GLCLU | 404453073211201 | 4044530732112 | 01 | 0.0 | 51.71 | 43 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM 530 | |
| 55 S 11204. 1 | | 404433073212701 | 4044330732127 | 01 | 53.0 | 55.16 | 44 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM 512 | 1 |
| 56 S 11240. 1 | 112GLCLU | 404540073211001 | 4045400732110 | 01 | 61.0 | 62.24 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SL 554 | 1 |
| 57 S 11267. 1 | 112GLCLU | 404719073202901 | 4047190732029 | 01 | 110.0 | 0.00 | 102 | 87 | 102 | 0 | 7 | 143 | 0 | 0 | 0 | SK 632 | 5 |
| 58 S 12035. 1 | 112GLCLU | 404527073220901 | 4045270732209 | 01 | 70.0 | 71.32 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SL 494 | 1 |
| 59 S 12141. 1 | 112GLCLU | 404343073154101 | 4043380731540 | 05 | 26.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SO 820 | |
| 60 S 12142. 1 | 112GLCLU | 404343073154102 | 4043380731540 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SO 820 | |
| 61 S 12163. 1 | 112GLCLU | 404821073185601 | 4048210731856 | 01 | 165.0 | 0.00 | 169 | 145 | 155 | 0 | 7 | 133 | 0 | 0 | 0 | SJ 757 | 5 |
| 62 S 12710. 1T | 112GLCLU | 404402073193000 | 4044020731930 | 03 | 40.0 | 41.10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN 610 | |
| 63 S 12873. 1T | | 404558073182501 | 4045580731825 | 01 | 82.0 | 0.00 | 388 | 0 | 0 | 0 | 4 | 159 | 0 | 0 | 0 | SL 727 | 3 |
| 64 S 13534. 1T | 112GLCLU | 404531073150601 | 4045290731504 | 01 | 62.0 | 0.00 | 126 | 89 | 119 | 126 | 8 | 187 | 0 | 0 | 0 | SM 907 | 7 |
| 65 S 13642. 1 | 112GLCLU | 404821073171501 | 4048210731715 | 01 | 90.0 | 0.00 | 95 | 79 | 95 | 0 | 11 | 169 | 0 | 0 | 0 | SK 840 | 5 |
| 66 S 14119. 1 | 112GLCLU | 404527073191501 | 4045270731915 | 01 | 70.0 | 71.29 | 44 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SL 669 | 1 |
| 67 S 14340. 1 | | 404352073205201 | 4043520732052 | 01 | 48.9 | 48.63 | 46 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM 538 | |
| 68 S 14471. 1 | 112GLCLU | 404425073200701 | 4044250732007 | 01 | 44.0 | 45.53 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM 585 | 1 |
| 69 S 15171. 1 | | 404305073172001 | 4043050731720 | 01 | 31.0 | 31.89 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SO 711 | 1 |
| 70 S 15775. 1T | | 404304073163501 | 4043040731635 | 01 | 25.0 | 0.00 | 291 | 0 | 0 | 0 | 8 | 0 | 0 | 0 | 0 | SO 763 | 3 |
| 71 S 15809. 1 | 112GLCLU | 404724073165001 | 4047240731650 | 01 | 100.0 | 0.00 | 153 | 118 | 150 | 0 | 8 | 189 | 0 | 0 | 0 | SK 848 | 5 |
| 72 S 15810. 1 | | 404708073165201 | 4047080731652 | 01 | 90.0 | 0.00 | 202 | 170 | 202 | 202 | 8 | 189 | 0 | 0 | 0 | SL 840 | 5 |
| 73 S 15898. 1 | 112GLCLU | 404536073163301 | 4045370731634 | 01 | 70.0 | 78.41 | 128 | 95 | 128 | 133 | 8 | 190 | 0 | 0 | 0 | SM 823 | 7 |
| 74 S 15914. 1 | 112GLCLU | 404628073204701 | 4046280732047 | 01 | 85.0 | 0.00 | 124 | 113 | 124 | 0 | 7 | 143 | 0 | 0 | 0 | SK 598 | 5 |
| 75 S 16175. 1 | 112GLCLU | 404534073163101 | 4045340731631 | 01 | 70.0 | 73.14 | 130 | 95 | 130 | 130 | 8 | 190 | 0 | 0 | 0 | SM 823 | 7 |
| 76 S 16176. 1 | 112GLCLU | 404528073150601 | 4045280731506 | 01 | 62.0 | 0.00 | 117 | 81 | 117 | 121 | 8 | 202 | 0 | 0 | 0 | SM 907 | 7 |
| 77 S 16256. 1T | 211MGTY | 404402073193202 | 4044020731930 | 02 | 41.0 | 37.14 | 650 | 544 | 597 | 0 | 4 | 164 | 0 | 0 | 0 | SN 610 | 7 |
| 78 S 16483. 1 | | 404322073193201 | 4043220731932 | 01 | 55.5 | 32.88 | 47 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN 595 | |
| 79 S 16484. 1 | | 404259073193801 | 4042590731938 | 01 | 20.0 | 22.19 | 44 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN 538 | 1 |
| 80 S 16608. 1 | | 404733073153601 | 4047330731536 | 01 | 110.0 | 0.00 | 140 | 110 | 140 | 168 | 8 | 189 | 0 | 0 | 0 | SK 929 | 7 |
| 81 S 16700. 1 | 112GLCLU | 404331073192901 | 4043310731929 | 01 | 30.0 | 0.00 | 58 | 47 | 58 | 0 | 4 | 164 | 0 | 0 | 0 | SN 604 | 5 |
| 82 S 17807. 1 | | 404457073194001 | 4044570731940 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM 622 | |
| 83 S 18075. 1T | 211MGTY | 404707073190501 | 4047070731905 | 01 | 110.0 | 0.00 | 627 | 0 | 0 | 0 | 7 | 0 | 0 | 0 | 0 | SK 716 | 3 |
| 84 S 18261. 1 | 211MGTY | 404707073190401 | 4047060731903 | 01 | 110.0 | 108.59 | 388 | 290 | 373 | 388 | 7 | 159 | 0 | 0 | 0 | SK 716 | 7 |
| 85 S 18383. 1 | 112GLCLU | 404335073203201 | 4043350732032 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN 541 | |
| 86 S 18566. 1 | 211MGTY | 404528073150501 | 4045290731505 | 01 | 62.0 | 0.00 | 383 | 322 | 383 | 653 | 4 | 167 | 0 | 0 | 0 | SM 907 | 7 |
| 87 S 18621. 1 | 112GLCLU | 404704073190401 | 4047080731905 | 01 | 110.0 | 110.00 | 201 | 144 | 201 | 250 | 7 | 159 | 0 | 0 | 0 | SK 716 | 7 |
| 88 S 19048. 1 | 211MGTY | 404301073161901 | 4043040731617 | 01 | 25.0 | 0.00 | 727 | 663 | 726 | 735 | 8 | 193 | 0 | 0 | 0 | SO 773 | 7 |
| 89 S 19965. 1 | 112GLCLU | 404225073181201 | 4042250731812 | 01 | 25.0 | 0.00 | 46 | 0 | 0 | 0 | 8 | 209 | 0 | 0 | 0 | SO 655 | 5 |
| 90 S 20318. 1T | 211MGTY | 404733073153101 | 4047330731531 | 01 | 110.0 | 0.00 | 436 | 370 | 430 | 605 | 8 | 189 | 0 | 0 | 0 | SL 920 | 7 |
| 91 S 20566. 1 | 211MGTY | 404317073153601 | 4043460731541 | 01 | 26.0 | 29.64 | 755 | 710 | 772 | 755 | 8 | 187 | 0 | 0 | 0 | SO 820 | 7 |
| 92 S 20635. 1T | 211MGTY | 404402073193201 | 4044020731932 | 01 | 41.0 | 0.00 | 704 | 556 | 626 | 0 | 4 | 164 | 0 | 0 | 0 | SN 610 | 7 |
| 93 S 21006. 1 | 112GLCLU | 404809073191301 | 4048090731913 | 01 | 143.0 | 0.00 | 376 | 310 | 372 | 402 | 7 | 0 | 0 | 0 | 0 | SJ 728 | 7 |
| 94 S 21244. 1 | 211MGTY | 404304073162001 | 4043040731615 | 01 | 23.0 | 27.50 | 602 | 465 | 593 | 730 | 8 | 187 | 0 | 0 | 0 | SO 773 | 7 |
| 95 S 21366. 1 | 211MGTY | 404357073181601 | 4043570731816 | 01 | 43.0 | 46.52 | 470 | 414 | 454 | 470 | 8 | 209 | 0 | 0 | 0 | SN 683 | 7 |
| 96 S 21900. 1 | | 404401073194801 | 4044010731948 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM 599 | |
| 97 S 22389. 1 | 211MGTY | 404357073181502 | 4043570731814 | 02 | 44.9 | 0.00 | 466 | 0 | 465 | 503 | 8 | 209 | 0 | 0 | 0 | SN 683 | 7 |
| 98 S 22548. 1 | 211MGTY | 404705073190701 | 4047080731902 | 01 | 114.0 | 116.68 | 415 | 347 | 403 | 541 | 7 | 159 | 0 | 0 | 0 | SK 716 | 7 |
| 99 S 23045. 1T | | 404502073182201 | 4045020731822 | 01 | 60.0 | 0.00 | 605 | 0 | 0 | 0 | 4 | 159 | 0 | 0 | 0 | SM 704 | |

| | WELL | AQUIFER | STATION ID | LAT-LONG | SQ | LSD | MP | DEPTH | --SCREEN-- | | MAX DRILL | TOWN | COM1 | SWAST | ZON | HUSTON | WFLUB |
|----|------|----------|------------|-----------------|---------------|-----|-------|-------|------------|--------|--------------|------|------|-------|-----|--------|-------|
| | | | | | | | | | TOP | BOTTOM | | | | | | | |
| 1 | S | 17. 1 | | 404342073214501 | 4043420732145 | 01 | 50.0 | 125 | 0 | 0 | 0 | 4 | 166 | 0 | | SH 475 | 3 |
| 2 | S | 18. 1 | | 404512073214201 | 4045120732142 | 01 | 56.0 | 400 | 0 | 0 | 0 | 4 | 167 | 0 | | SL 515 | 3 |
| 3 | S | 19. 1 | 112GLCLU | 404750073194201 | 4047500731942 | 01 | 130.0 | 203 | 0 | 0 | 0 | 7 | 133 | 0 | | | |
| 4 | S | 24. 1 | 211MGTY | 404752073201301 | 4047520732013 | 01 | 150.0 | 132 | 123 | 132 | 0 | 7 | 143 | 0 | | SH 480 | 5 |
| 5 | S | 37. 1 | | 404315073160501 | 4043150731605 | 01 | 53.0 | 620 | 0 | 0 | 0 | 5 | 160 | 0 | | SH 470 | 5 |
| 6 | S | 39. 1 | 211MGTY | 404315073170201 | 4043150731702 | 01 | 32.0 | 200 | 0 | 0 | 0 | 4 | 0 | 0 | | SH 750 | 7 |
| 7 | S | 42. 1 | | 404731073164701 | 4047310731647 | 01 | 120.0 | 1008 | 0 | 0 | 0 | 3 | 149 | 0 | | SK 557 | 3 |
| 8 | S | 61. 1 | | 404638073152601 | 4046380731526 | 01 | 93.0 | 194 | 0 | 0 | 194 | 3 | 149 | 0 | | SL 417 | 7 |
| 9 | S | 62. 1 | | 404640073152101 | 4046400731521 | 01 | 92.0 | 200 | 0 | 0 | 200 | 8 | 139 | 0 | | SL 417 | 7 |
| 10 | S | 78. 1 | | 404415073203101 | 4044150732031 | 01 | 41.0 | 121 | 0 | 0 | 0 | 4 | 157 | 0 | | SH 555 | |
| 11 | S | 83. 1 | | 404350073204701 | 4043500732047 | 01 | 40.0 | 116 | 0 | 0 | 0 | 5 | 0 | 0 | | SH 530 | |
| 12 | S | 291. 1 | | 404450073143001 | 4044500731430 | 01 | 40.0 | 0 | 0 | 0 | 0 | 5 | 0 | 0 | | SH 922 | |
| 13 | S | 302. 1 | 112GLCLU | 404628073143201 | 4046280731432 | 01 | 50.0 | 52 | 0 | 0 | 0 | 8 | 189 | 0 | | SH 960 | 5 |
| 14 | S | 1411. 1 | | 404606073221401 | 4046060732214 | 01 | 0.0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SK 508 | |
| 15 | S | 1723. 1 | 112GLCLU | 404749073161001 | 4047490731610 | 01 | 122.0 | 159 | 0 | 0 | 0 | 3 | 189 | 0 | | SK 596 | 5 |
| 16 | S | 1807. 1 | 112GLCLU | 404319073184601 | 4043190731846 | 01 | 23.0 | 21 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 637 | 6 |
| 17 | S | 1807. 2 | 112GLCLU | 404319073184602 | 4043190731846 | 02 | 24.8 | 10 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 637 | 6 |
| 18 | S | 1807. 3 | 112GLCLU | 404319073184603 | 4043190731846 | 03 | 23.0 | 8 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 637 | 6 |
| 19 | S | 1807. 4 | 112GLCLU | 404319073184604 | 4043190731846 | 04 | 23.0 | 21 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 637 | 6 |
| 20 | S | 1807. 5 | 112GLCLU | 404319073184605 | 4043190731846 | 05 | 23.0 | 6 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 637 | 1 |
| 21 | S | 1809. 1 | 112GLCLU | 404351073164901 | 4043510731649 | 01 | 40.9 | 27 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 766 | 6 |
| 22 | S | 1809. 2 | 112GLCLU | 404351073164902 | 4043510731649 | 02 | 41.5 | 26 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 766 | 6 |
| 23 | S | 1809. 3 | 112GLCLU | 404351073164903 | 4043510731649 | 03 | 42.0 | 25 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 766 | 6 |
| 24 | S | 1809. 4 | 112GLCLU | 404351073164904 | 4043510731649 | 04 | 42.0 | 25 | 0 | 0 | 0 | 8 | 209 | 0 | S | SH 766 | 1 |
| 25 | S | 1810. 1 | 112GLCLU | 404614073164401 | 4046140731647 | 01 | 69.7 | 46 | 42 | 46 | 0 | 8 | 194 | 0 | | SL 827 | 6 |
| 26 | S | 1810. 2 | 112GLCLU | 404613073164702 | 4046130731647 | 02 | 93.7 | 48 | 46 | 48 | 0 | 8 | 194 | 0 | | SL 828 | 6 |
| 27 | S | 1810. 3 | 112GLCLU | 404614073164403 | 4046140731644 | 03 | 90.1 | 56 | 54 | 56 | 0 | 8 | 194 | 0 | | SL 828 | 6 |
| 28 | S | 1810. 4 | 112GLCLU | 404614073164404 | 4046140731644 | 04 | 90.8 | 51 | 0 | 0 | 0 | 8 | 194 | 0 | | SL 828 | 1 |
| 29 | S | 1816. 1 | | 404610073184001 | 4046100731840 | 01 | 80.0 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 714 | 1 |
| 30 | S | 1817. 1 | | 404520073214501 | 4045200732145 | 01 | 58.0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 515 | 1 |
| 31 | S | 2314. 1 | 211MGTY | 404605073211801 | 4046050732118 | 01 | 80.0 | 480 | 465 | 480 | 0 | 4 | 167 | 0 | | SL 550 | 5 |
| 32 | S | 2424. 1 | 211MGTY | 404603073221401 | 4046030732214 | 01 | 110.0 | 150 | 147 | 150 | 0 | 7 | 0 | 0 | | SK 509 | 5 |
| 33 | S | 2455. 1 | | 404309073172701 | 4043090731727 | 01 | 33.0 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 710 | 1 |
| 34 | S | 3515. 1 | | 404445073153701 | 4044450731537 | 01 | 0.0 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | | SH 851 | 1 |
| 35 | S | 3516. 1 | 112GLCLU | 404509073152301 | 4045090731523 | 01 | 60.0 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | | SH 879 | 1 |
| 36 | S | 4266. 1 | 112GLCLU | 404630073160001 | 4046300731800 | 01 | 80.0 | 125 | 81 | 101 | 0 | 4 | 159 | 0 | | SL 763 | 5 |
| 37 | S | 4270. 1 | | 404725073162201 | 4047250731622 | 01 | 119.2 | 83 | 0 | 0 | 0 | 0 | 0 | 0 | | SK 579 | 1 |
| 38 | S | 4519. 1 | 112GLCLU | 404813073194401 | 4048130731944 | 01 | 140.0 | 118 | 115 | 118 | 0 | 7 | 133 | 0 | | SJ 706 | 5 |
| 39 | S | 4534. 1 | 112GLCLU | 404740073202901 | 4047400732029 | 01 | 130.0 | 120 | 115 | 120 | 0 | 7 | 143 | 0 | | SJ 649 | 5 |
| 40 | S | 5134. 1 | 211MGTY | 404756073203301 | 4047560732033 | 01 | 175.0 | 160 | 152 | 157 | 0 | 7 | 143 | 0 | | SJ 647 | 5 |
| 41 | S | 5716. 1 | 211MGTY | 404630073215001 | 4046300732150 | 01 | 200.0 | 159 | 0 | 159 | 0 | 7 | 0 | 0 | | SK 536 | 5 |
| 42 | S | 7148. 1 | 211MGTY | 404804073203701 | 4048040732037 | 01 | 170.0 | 144 | 138 | 144 | 0 | 7 | 143 | 0 | | SJ 646 | 5 |
| 43 | S | 8323. 1 | 112GLCLU | 404343073154103 | 4043380731540 | 03 | 26.0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 820 | |
| 44 | S | 8943. 1 | 211MGTY | 404649073215201 | 4046490732152 | 01 | 240.0 | 268 | 258 | 266 | 0 | 7 | 143 | 0 | | SK 543 | 4 |
| 45 | S | 9645. 1 | 112GLCLU | 404412073185701 | 4044120731857 | 01 | 0.0 | 43 | 0 | 0 | 0 | 0 | 0 | 0 | | SH 659 | |
| 46 | S | 9646. 1 | 112GLCLU | 404446073191801 | 4044460731918 | 01 | 51.0 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | | SH 644 | 1 |
| 47 | S | 9904. 1 | 112GLCLU | 404343073154104 | 4043380731540 | 04 | 26.0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 820 | |
| 48 | S | 9905. 1 | 112GLCLU | 404343073154105 | 4043380731541 | 05 | 26.0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 820 | |
| 49 | S | 10222. 1 | 112GLCLU | 404448073183001 | 4044480731830 | 01 | 0.0 | 46 | 0 | 0 | 0 | 0 | 0 | 0 | | SH 695 | |
| 50 | S | 10370. 1 | | 404342073195501 | 4043420731955 | 01 | 38.0 | 66 | 0 | 0 | 0 | 0 | 0 | 0 | | | |

| | WELL | AQUIFER | STATION | ID | LAT-LONG | SQ | LSD | MP | DEPTH | --SCREEN-- | | MAX DRILL | TOWN | COMM | SWDST | ZON | HGSTRM | WELUS |
|-----|-------------|----------|-----------------|---------------|----------|-------|--------|-----|-------|------------|--------|--------------|------|------|-------|--------|--------|-------|
| | | | | | | | | | | TOP | BOTTOM | | | | | | | |
| 101 | S 23058. 1 | 211MGTY | 404345073171101 | 4043450731711 | 01 | 40.0 | 0.00 | 217 | 187 | 213 | 0 | 8 | 190 | 0 | | SN 746 | 5 | |
| 102 | S 23445. 1 | 211MGTY | 404659073164101 | 4046590731642 | 01 | 110.0 | 113.56 | 610 | 541 | 605 | 610 | 8 | 169 | 0 | | SL 642 | 7 | |
| 103 | S 23522. 1 | 112GLCLU | 404808073191301 | 4048080731913 | 01 | 145.0 | 0.00 | 424 | 358 | 420 | 424 | 7 | 133 | 0 | | SJ 728 | 7 | |
| 104 | S 23848. 1 | 211MGTY | 404430073211301 | 4044300732113 | 01 | 50.0 | 52.34 | 634 | 558 | 631 | 669 | 4 | 167 | 0 | | SM 523 | 7 | |
| 105 | S 24769. 1 | 211MGTY | 404819073160301 | 4048190731603 | 01 | 139.0 | 137.83 | 810 | 800 | 810 | 858 | 8 | 169 | 0 | | SK 913 | 1 | |
| 106 | S 24770. 1 | 211MGTY | 404829073161502 | 4048190731603 | 02 | 139.0 | 138.12 | 434 | 424 | 434 | 0 | 11 | 198 | 0 | | SK 913 | 1 | |
| 107 | S 24771. 1 | 112GLCLU | 404820073160303 | 4048200731603 | 03 | 139.0 | 137.94 | 127 | 117 | 127 | 0 | 8 | 198 | 0 | | SK 912 | 1 | |
| 108 | S 24846. 1 | 211MGTY | 404639073151401 | 4046390731514 | 01 | 90.0 | 0.00 | 597 | 461 | 517 | 597 | 8 | 189 | 0 | | SL 927 | 7 | |
| 109 | S 25511. 1 | 112GLCLU | 404407073154701 | 4044070731547 | 01 | 40.0 | 0.00 | 80 | 76 | 80 | 0 | 8 | 187 | 0 | | SN 836 | 5 | |
| 110 | S 25617. 1 | 211MGTY | 404459073182401 | 4045000731824 | 01 | 64.0 | 67.69 | 441 | 359 | 440 | 0 | 4 | 159 | 0 | | SM 704 | 7 | |
| 111 | S 25674. 1 | 211MGTY | 404431073211401 | 4044310732115 | 01 | 50.0 | 53.30 | 625 | 550 | 625 | 654 | 4 | 167 | 0 | | SM 523 | 7 | |
| 112 | S 26535. 1 | 211MGTY | 404318073153801 | 4043380731540 | 01 | 26.0 | 29.25 | 776 | 710 | 773 | 782 | 8 | 187 | 0 | | SO 820 | 7 | |
| 113 | S 27739. 1 | 211MGTY | 404603073214803 | 4046030732148 | 03 | 139.9 | 141.37 | 850 | 840 | 850 | 0 | 4 | 167 | 0 | | SL 520 | 1 | |
| 114 | S 27740. 1 | 211MGTY | 404603073214804 | 4046030732148 | 04 | 140.5 | 141.85 | 429 | 419 | 429 | 0 | 0 | 0 | 0 | | SL 520 | 1 | |
| 115 | S 27741. 1 | 211MGTY | 404603073214805 | 4046030732148 | 05 | 140.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 520 | 1 | |
| 116 | S 28449. 1 | 112GLCLU | 404603073214806 | 4046030732148 | 06 | 140.0 | 141.18 | 98 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 520 | 1 | |
| 117 | S 28503. 1 | 211MGTY | 404318073201901 | 4043180732019 | 01 | 30.0 | 31.05 | 676 | 599 | 676 | 0 | 4 | 166 | 0 | | SN 544 | 7 | |
| 118 | S 30193. 1 | 112GLCLU | 404524073160601 | 4045240731606 | 01 | 65.0 | 0.00 | 80 | 76 | 80 | 0 | 8 | 190 | 0 | | SM 845 | 5 | |
| 119 | S 31104. 1 | 211MGTY | 404703073164401 | 4047000731641 | 01 | 110.0 | 105.47 | 658 | 592 | 655 | 665 | 8 | 189 | 0 | | SL 842 | 7 | |
| 120 | S 32412. 1 | | 404736073153201 | 4047360731532 | 01 | 110.0 | 0.00 | 900 | 0 | 0 | 900 | 8 | 189 | 0 | | SK 929 | 7 | |
| 121 | S 32841. 1T | | 404534073210802 | 4045340732108 | 02 | 61.0 | 0.00 | 648 | 0 | 0 | 0 | 4 | 167 | 0 | | SL 555 | 3 | |
| 122 | S 33005. 1 | 211MGTY | 404317073201801 | 4043180732018 | 01 | 33.0 | 27.59 | 681 | 605 | 679 | 0 | 4 | 0 | 0 | | SN 554 | 7 | |
| 123 | S 34022. 1T | | 404657073210401 | 4046570732104 | 01 | 220.0 | 0.00 | 560 | 400 | 487 | 0 | 7 | 133 | 0 | | SK 594 | 3 | |
| 124 | S 34030. 1 | 211MGTY | 404536073210801 | 4045360732108 | 01 | 54.0 | 58.45 | 538 | 0 | 538 | 563 | 4 | 167 | 0 | | SL 554 | 7 | |
| 125 | S 34031. 1 | 211MGTY | 404534073210801 | 4045340732108 | 01 | 54.1 | 0.00 | 521 | 0 | 521 | 563 | 4 | 167 | 0 | | SL 555 | 7 | |
| 126 | S 34032. 1 | 112GLCLU | 404808073191201 | 4048080731912 | 01 | 150.0 | 0.00 | 441 | 369 | 436 | 441 | 7 | 133 | 0 | | SJ 733 | 7 | |
| 127 | S 34063. 1 | 211MGTY | 404635073214001 | 4046350732140 | 01 | 200.0 | 0.00 | 736 | 656 | 736 | 742 | 7 | 148 | 0 | | SK 556 | 7 | |
| 128 | S 34064. 1 | 211MGTY | 404635073214002 | 4046350732140 | 02 | 200.0 | 0.00 | 632 | 0 | 0 | 664 | 7 | 148 | 0 | | SK 556 | 7 | |
| 129 | S 35669. 1T | 112GLCLU | 404604073175101 | 4046040731751 | 01 | 70.0 | 0.00 | 118 | 91 | 101 | 0 | 4 | 159 | 0 | | SL 757 | 1 | |
| 130 | S 36138. 1 | 112GLCLU | 404800073193501 | 4048000731935 | 01 | 149.0 | 152.74 | 110 | 108 | 110 | 112 | 0 | 0 | 0 | | SJ 708 | 6 | |
| 131 | S 36139. 1 | 112GLCLU | 404600073193201 | 4046000731932 | 01 | 76.0 | 70.91 | 21 | 0 | 0 | 0 | 4 | 159 | 0 | | SL 654 | 1 | |
| 132 | S 36460. 1 | 211MGTY | 404627073070901 | 4045370731635 | 01 | 76.0 | 70.10 | 611 | 0 | 611 | 0 | 8 | 189 | 0 | | SM 823 | 7 | |
| 133 | S 36714. 1 | 211MGTY | 404458073182502 | 4044580731824 | 02 | 63.0 | 0.00 | 308 | 244 | 304 | 354 | 4 | 159 | 0 | | SM 704 | 7 | |
| 134 | S 37861. 1 | 211MGTY | 404406073193401 | 4044020731929 | 01 | 41.8 | 36.16 | 636 | 0 | 636 | 0 | 0 | 0 | 0 | | SN 610 | 7 | |
| 135 | S 38192. 1 | 211MGTY | 404528073150402 | 4045310731501 | 02 | 65.9 | 0.00 | 306 | 0 | 0 | 605 | 8 | 189 | 0 | | SM 906 | 7 | |
| 136 | S 39024. 1 | 211MGTY | 404358073181801 | 4043570731815 | 01 | 45.0 | 0.00 | 623 | 0 | 623 | 655 | 8 | 198 | 0 | | SN 693 | 7 | |
| 137 | S 40497. 1 | 211MGTY | 404606073174602 | 4046040731752 | 02 | 74.0 | 74.29 | 283 | 220 | 280 | 708 | 4 | 0 | 0 | | SL 757 | 7 | |
| 138 | S 42762. 1 | 211MGTY | 404305073161401 | 4043050731615 | 01 | 26.0 | 21.02 | 714 | 650 | 710 | 739 | 8 | 187 | 0 | | SO 783 | 7 | |
| 139 | S 43088. 1T | 211MGTY | 404640073152102 | 4046400731521 | 02 | 90.0 | 90.00 | 902 | 0 | 0 | 0 | 8 | 0 | 0 | | SL 917 | 3 | |
| 140 | S 43814. 1 | 112GLCLU | 404455073215001 | 4044550732150 | 01 | 60.0 | 63.29 | 50 | 35 | 45 | 0 | 4 | 167 | 0 | | SL 508 | 1 | |
| 141 | S 43817. 1 | 112GLCLU | 404618073205001 | 4046180732050 | 01 | 70.0 | 66.82 | 56 | 41 | 51 | 0 | 4 | 167 | 0 | | SK 599 | 1 | |
| 142 | S 43818. 1 | 112GLCLU | 404257073202401 | 4042570732024 | 01 | 25.0 | 25.04 | 36 | 20 | 30 | 0 | 4 | 166 | 0 | | SN 536 | 1 | |
| 143 | S 43820. 1 | 112GLCLU | 404649073184001 | 4046490731840 | 01 | 110.0 | 104.13 | 98 | 82 | 92 | 0 | 4 | 159 | 0 | | SK 729 | 1 | |
| 144 | S 43821. 1 | 112GLCLU | 404302073185501 | 4043020731855 | 01 | 22.4 | 22.40 | 36 | 21 | 31 | 0 | 4 | 164 | 0 | | SN 629 | 1 | |
| 145 | S 43822. 1 | 112GLCLU | 404302073185502 | 4043020731855 | 02 | 20.0 | 22.02 | 74 | 59 | 69 | 0 | 4 | 164 | 0 | | SN 629 | 1 | |
| 146 | S 44137. 1T | 211MGTY | 404432073151304 | 4044320731513 | 04 | 39.0 | 39.00 | 720 | 0 | 0 | 0 | 8 | 187 | 0 | | SN 874 | 3 | |
| 147 | S 45347. 1 | 211MGTY | 404726073162601 | 4047260731626 | 01 | 130.0 | 0.00 | 643 | 587 | 643 | 0 | 0 | 0 | 0 | | SK 879 | 5 | |
| 148 | S 45348. 1 | 211MGTY | 404729073162801 | 4047290731628 | 01 | 130.0 | 0.00 | 650 | 590 | 648 | 0 | 0 | 0 | 0 | | SK 878 | 5 | |
| 149 | S 45446. 1 | 112GLCLU | 404400073154402 | 4044000731544 | 02 | 38.0 | 38.49 | 41 | 29 | 39 | 0 | 0 | 0 | 0 | | SN 837 | 1 | |
| 150 | S 45638. 1 | 211MGTY | 404804073204401 | 4048040732044 | 01 | 163.6 | 164.34 | 725 | 653 | 725 | 757 | 7 | 133 | 0 | | | | |

| WELL | AQUIFER | STATION | ID | LAT-LONG | SQ | LSD | MP | DEPTH | --SCREEN-- | | MAX DRILL | TOWN | COMM | SWDST | ZON | HGSTRM | WELUS |
|-----------------|----------|-----------------|---------------|----------|-------|--------|-----|-------|------------|--------|--------------|------|------|-------|--------|--------|-------|
| | | | | | | | | | TOP | BOTTOM | | | | | | | |
| 151 S 45639. 1 | 211MGTY | 404805073203701 | 4048040732047 | 01 | 154.5 | 156.00 | 745 | 660 | 735 | 748 | 7 | 133 | 0 | | SJ 636 | 7 | |
| 152 S 45717. 1 | 112GLCLU | 404618073164501 | 4046180731645 | 01 | 93.0 | 89.84 | 75 | 63 | 75 | 0 | 0 | 0 | 0 | | SL 827 | 1 | |
| 153 S 45935. 1 | 112GLCLU | 404851073185101 | 4048510731851 | 01 | 285.0 | 285.00 | 605 | 539 | 599 | 660 | 4 | 159 | 0 | | SJ 763 | 7 | |
| 154 S 46235. 1 | 211MGTY | 404432073151300 | 4044320731513 | 02 | 39.0 | 37.40 | 713 | 649 | 710 | 0 | 8 | 187 | 0 | | SN 874 | 7 | |
| 155 S 46287. 1 | 112GLCLU | 404400073154401 | 4044000731544 | 01 | 38.7 | 38.70 | 88 | 76 | 86 | 0 | 0 | 0 | 0 | | SN 837 | 1 | |
| 156 S 46830. 1 | 211MGTY | 404606073174601 | 4046060731746 | 01 | 76.0 | 67.75 | 655 | 550 | 651 | 663 | 0 | 0 | 0 | | SL 767 | 7 | |
| 157 S 47435. 1 | 211MGTY | 404317073201802 | 4043170732018 | 02 | 0.0 | 0.00 | 441 | 0 | 441 | 0 | 0 | 0 | 0 | | SN 554 | 7 | |
| 158 S 50546. 1 | 211MGTY | 404432073151303 | 4044320731513 | 03 | 39.0 | 36.45 | 668 | 604 | 665 | 0 | 0 | 0 | 0 | | SN 874 | 7 | |
| 159 S 52236. 1 | 112GLCLU | 404504073221901 | 4045040732219 | 01 | 80.0 | 0.00 | 98 | 94 | 98 | 0 | 4 | 167 | 0 | | SL 476 | | |
| 160 S 52384. 1 | 112GLCLU | 404523073181101 | 4045230731811 | 01 | 63.0 | 66.45 | 33 | 16 | 21 | 0 | 0 | 0 | 0 | | SM 722 | 1 | |
| 161 S 54155. 1T | 211MGTY | 404326073173501 | 4043260731735 | 01 | 38.0 | 0.00 | 721 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 718 | 1 | |
| 162 S 55463. 1 | 211MGTY | 404458073182503 | 4044580731825 | 03 | 62.4 | 0.00 | 360 | 0 | 360 | 0 | 0 | 0 | 0 | | SM 694 | 7 | |
| 163 S 55733. 1 | 211MGTY | 404326073174101 | 4043260731741 | 01 | 38.0 | 0.00 | 233 | 180 | 230 | 0 | 0 | 0 | 0 | | SN 708 | 1 | |
| 164 S 55734. 1 | 211MGTY | 404326073174102 | 4043260731741 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 708 | 7 | |
| 165 S 56347. 1 | | 404513073212401 | 4045130732124 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 537 | | |
| 166 S 56348. 1 | | 404514073203501 | 4045140732035 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 588 | | |
| 167 S 56349. 1 | | 404509073210301 | 4045090732103 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 558 | | |
| 168 S 56350. 1 | | 404440073201201 | 4044400732012 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 583 | | |
| 169 S 56351. 1 | | 404417073210401 | 4044170732104 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 525 | | |
| 170 S 56352. 1 | 112GLCLU | 404418073204401 | 4044180732044 | 01 | 34.3 | 34.03 | 20 | 17 | 20 | 0 | 4 | 0 | 0 | | SM 545 | 1 | |
| 171 S 56353. 1 | 112GLCLU | 404400073195601 | 4044000731956 | 01 | 33.6 | 32.65 | 20 | 17 | 20 | 0 | 4 | 164 | 0 | | SM 589 | | |
| 172 S 56354. 1 | | 404337073204801 | 4043370732048 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 520 | | |
| 173 S 56355. 1 | 112GLCLU | 404355073202001 | 4043550732020 | 01 | 26.4 | 25.95 | 20 | 17 | 20 | 0 | 4 | 164 | 0 | | SM 569 | | |
| 174 S 56356. 1 | | 404331073193101 | 4043310731931 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 604 | | |
| 175 S 56357. 1 | 112GLCLU | 404309073200101 | 4043090732001 | 01 | 17.1 | 16.64 | 20 | 17 | 20 | 0 | 4 | 0 | 0 | | SN 566 | | |
| 176 S 56358. 1 | | 404313073195601 | 4043130731956 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 565 | | |
| 177 S 56359. 1 | 112GLCLU | 404258073195501 | 4042580731955 | 01 | 17.1 | 16.64 | 20 | 17 | 20 | 0 | 4 | 0 | 0 | | SN 567 | | |
| 178 S 56360. 1 | | 404241073192801 | 4042410731928 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 580 | | |
| 179 S 56423. 1 | 211MGTY | 404418073171801 | 4044180731718 | 01 | 50.0 | 0.00 | 800 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 742 | 3 | |
| 180 S 57008. 1 | 211MGTY | 404658073164201 | 4046580731642 | 01 | 111.0 | 0.00 | 635 | 529 | 632 | 0 | 0 | 0 | 0 | | SL 842 | 3 | |
| 181 S 59347. 1 | 211MGTY | 404419073171601 | 4044190731716 | 01 | 51.0 | 0.00 | 463 | 388 | 458 | 515 | 0 | 0 | 0 | | SN 752 | 7 | |
| 182 S 61356. 1T | | 404805073203702 | 4048040732049 | 01 | 152.8 | 0.00 | 752 | 0 | 0 | 0 | 0 | 0 | 0 | | SJ 636 | | |
| 183 S 61356. 2 | 211MGTY | 404804073204902 | 4048040732049 | 02 | 152.8 | 154.36 | 678 | 618 | 678 | 0 | 0 | 0 | 0 | | SJ 636 | 5 | |
| 184 S 62720. 1 | 112GLCLU | 404510073165501 | 4045100731655 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 796 | 1 | |
| 185 S 62721. 1 | | 404454073165501 | 4044540731655 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 798 | | |
| 186 S 63741. 1 | | 404430073183001 | 4044300731830 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 636 | | |
| 187 S 63747. 1 | | 404426073181201 | 4044260731812 | 01 | 50.0 | 51.55 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 699 | | |
| 188 S 63761. 1 | | 404433073203301 | 4044330732033 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 554 | | |
| 189 S 63822. 1 | | 404546073135901 | 4045460731359 | 01 | 0.0 | 51.01 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 976 | | |
| 190 S 63823. 1 | | 404531073140801 | 4045310731408 | 01 | 0.0 | 52.03 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 968 | | |
| 191 S 63844. 1 | | 404332073145101 | 4043320731451 | 01 | 0.0 | 21.54 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 872 | | |
| 192 S 63848. 1 | 112GLCLU | 404353073144501 | 4043530731445 | 01 | 0.0 | 15.60 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 880 | | |
| 193 S 63849. 1 | | 404417073143401 | 4044170731434 | 01 | 0.0 | 28.38 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 907 | | |
| 194 S 63850. 1 | | 404439073142601 | 4044390731426 | 01 | 0.0 | 37.79 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 924 | | |
| 195 S 63851. 1 | | 404420073151401 | 4044200731514 | 01 | 35.0 | 34.51 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 865 | | |
| 196 S 63852. 1 | | 404430073154801 | 4044300731548 | 01 | 0.0 | 44.92 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 843 | | |
| 197 S 63853. 1 | | 404420073154101 | 4044200731541 | 01 | 0.0 | 43.41 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 844 | | |
| 198 S 63854. 1 | | 404317073155001 | 4043170731550 | 01 | 0.0 | 20.51 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 802 | | |
| 199 S 63855. 1 | | 404301073154101 | 4043010731541 | 01 | 85.0 | 19.80 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 815 | | |

| WELL | AQUIFER | STATION ID | LAT-LONG | SQ | LSD | MP | DEPTH | --SCREEN-- | | MAX DRILL | TOWN | COMM | SWDST | ZON | H6STRM | WELUS |
|----------------|----------|-----------------|------------------|----|-------|-------|-------|------------|--------|--------------|------|------|-------|-----|--------|-------|
| | | | | | | | | TOP | BOTTOM | | | | | | | |
| 201 S 64189. 1 | | 404326073172501 | 4043260731725 01 | | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 728 | |
| 202 S 64190. 1 | | 404336073175801 | 4043360731758 01 | | 0.0 | 38.80 | 0 | 0 | 0 | 0 | 0 | 0 | U | | SN 696 | |
| 203 S 64191. 1 | | 404252073181701 | 4042520731817 01 | | 0.0 | 26.54 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 651 | |
| 204 S 64197. 1 | | 404234073192401 | 4042340731924 01 | | 0.0 | 19.44 | 0 | 0 | U | 0 | 0 | 0 | 0 | | SO 531 | |
| 205 S 64221. 1 | | 404314073192401 | 4043140731924 01 | | 0.0 | 29.65 | 0 | 0 | 0 | 0 | 0 | 0 | U | | SN 606 | |
| 206 S 64222. 1 | | 404346073200501 | 4043460732005 01 | | 0.0 | 34.30 | 0 | 0 | 0 | 0 | 0 | 0 | U | | SN 571 | |
| 207 S 64223. 1 | 112GLCLU | 404344073202201 | 4043440732022 01 | | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 550 | 1 |
| 208 S 64224. 1 | | 404343073202201 | 4043430732022 01 | | 0.0 | 27.82 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 550 | |
| 209 S 64225. 1 | | 404339073202801 | 4043390732028 01 | | 0.0 | 35.71 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 541 | |
| 210 S 64226. 1 | | 404340073202801 | 4043400732028 01 | | 0.0 | 35.76 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 541 | |
| 211 S 64227. 1 | | 404337073204501 | 4043370732045 01 | | 0.0 | 41.84 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 531 | |
| 212 S 64228. 1 | | 404400073193301 | 4044000731933 01 | | 0.0 | 34.99 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 610 | |
| 213 S 64229. 1 | | 404402073194001 | 4044020731940 01 | | 0.0 | 34.58 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 609 | |
| 214 S 64230. 1 | | 404401073195401 | 4044010731954 01 | | 0.0 | 33.43 | 0 | 0 | U | 0 | 0 | 0 | 0 | | SM 599 | |
| 215 S 64231. 1 | | 404401073195701 | 4044010731957 01 | | 0.0 | 34.01 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 589 | |
| 216 S 64304. 1 | | 404433073203201 | 4044330732032 01 | | 0.0 | 44.35 | 0 | 0 | 0 | 0 | 0 | 0 | U | | SM 564 | |
| 217 S 64305. 1 | | 404431073204201 | 4044310732042 01 | | 0.0 | 39.25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 554 | |
| 218 S 64306. 1 | | 404431073204101 | 4044310732041 01 | | 0.0 | 39.21 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 554 | |
| 219 S 64307. 1 | | 404427073204101 | 4044270732041 01 | | 0.0 | 49.44 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 554 | |
| 220 S 64308. 1 | | 404427073204201 | 4044270732042 01 | | 0.0 | 39.27 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 554 | |
| 221 S 64309. 1 | | 404429073204701 | 4044290732047 01 | | 0.0 | 39.47 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 554 | |
| 222 S 64310. 1 | | 404513073175501 | 4045130731755 01 | | 0.0 | 60.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 733 | |
| 223 S 64311. 1 | | 404517073181201 | 4045170731812 01 | | 0.0 | 53.39 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 712 | |
| 224 S 64312. 1 | | 404537073174001 | 4045370731740 01 | | 0.0 | 0.00 | 0 | 0 | 0 | U | 0 | 0 | 0 | | SM 751 | |
| 225 S 64313. 1 | 112GLCLU | 404659073202001 | 4046590732020 01 | | 89.4 | 89.20 | 30 | 25 | 30 | 0 | 7 | 143 | 0 | | SK 635 | 1 |
| 226 S 64314. 1 | 112GLCLU | 404818073171601 | 4048180731716 01 | | 100.1 | 99.94 | 60 | 55 | 60 | 0 | 7 | 169 | 0 | | SK 840 | 1 |
| 227 S 64504. 1 | | 404549073140201 | 4045490731402 01 | | 0.0 | 58.14 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 976 | |
| 228 S 64526. 1 | | 404449073144501 | 4044490731445 01 | | 0.0 | 38.05 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 902 | |
| 229 S 64527. 1 | | 404442073144401 | 4044420731444 01 | | 0.0 | 33.85 | 0 | 0 | 0 | U | 0 | 0 | 0 | | SN 903 | |
| 230 S 64528. 1 | | 404442073144701 | 4044420731447 01 | | 0.0 | 31.40 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 903 | |
| 231 S 64535. 1 | | 404230073175101 | 4042300731751 01 | | 0.0 | 18.45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 675 | |
| 232 S 64536. 1 | | 404254073174301 | 4042540731743 01 | | 0.0 | 25.07 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 692 | |
| 233 S 64537. 1 | | 404304073174201 | 4043040731742 01 | | 0.0 | 26.74 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 691 | |
| 234 S 64538. 1 | | 404307073173801 | 4043070731738 01 | | 0.0 | 24.40 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 700 | |
| 235 S 64539. 1 | | 404307073174701 | 4043070731747 01 | | 0.0 | 28.90 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 690 | |
| 236 S 64540. 1 | | 404421073174301 | 4044210731743 01 | | 0.0 | 50.49 | 0 | 0 | U | 0 | 0 | 0 | U | | SN 720 | |
| 237 S 64541. 1 | | 404425073175701 | 4044250731757 01 | | 0.0 | 52.66 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 710 | |
| 238 S 64542. 1 | | 404425073181801 | 4044250731818 01 | | 0.0 | 50.64 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 699 | |
| 239 S 64543. 1 | | 404513073175401 | 4045130731754 01 | | 0.0 | 53.26 | 0 | 0 | 0 | 0 | 0 | 0 | U | | SM 733 | |
| 240 S 64544. 1 | | 404511073174401 | 4045110731744 01 | | 0.0 | 56.49 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 744 | |
| 241 S 64545. 1 | | 404517073174401 | 4045170731744 01 | | 0.0 | 56.72 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 743 | |
| 242 S 64546. 1 | | 404335073184401 | 4043350731844 01 | | 0.0 | 33.37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 645 | |
| 243 S 64547. 1 | | 404328073185701 | 4043280731857 01 | | 0.0 | 32.70 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 635 | |
| 244 S 64548. 1 | | 404250073185801 | 4042500731858 01 | | 0.0 | 18.10 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SO 610 | |
| 245 S 64562. 1 | | 404531073210701 | 4045310732107 01 | | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SL 555 | |
| 246 S 64563. 1 | | 404538073211001 | 4045380732110 01 | | 0.0 | 57.12 | 13 | 11 | 13 | 0 | 0 | 0 | 0 | | SL 554 | 1 |
| 247 S 64579. 1 | | 404408073152801 | 4044080731528 01 | | 0.0 | 35.01 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 856 | |
| 248 S 64580. 1 | | 404409073154501 | 4044090731545 01 | | 0.0 | 43.63 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SN 836 | |
| 249 S 65196. 1 | 211MGTY | 404529073171901 | 4045290731719 01 | | 69.0 | 0.00 | 124 | 0 | 0 | 0 | 8 | 189 | 0 | | SM 772 | 3 |
| 250 S 65199. 1 | | 404529073171201 | 4045290731712 01 | | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 783 | |

| | WELL | AQUIFER | STATION | ID | LAT-LONG | SQ | LSD | MP | DEPTH | --SCREEN-- | | MAX DRILL | TOWN | COMM | SWDST | ZON | HGSTRM | WELUS |
|-----|----------|---------|----------|-----------------|---------------|----|-------|--------|-------|------------|--------|--------------|------|------|-------|-----|--------|-------|
| | | | | | | | | | | TOP | BOTTOM | | | | | | | |
| 251 | S 66137. | 1 | 211MGTY | 404618073212101 | 4046180732121 | 01 | 140.0 | 140.02 | 0 | 120 | 130 | 0 | 0 | 0 | 0 | SK | 568 | 1 |
| 252 | S 66138. | 1 | 211MGTY | 404430073215601 | 4044300732156 | 01 | 60.0 | 63.14 | 150 | 119 | 129 | 0 | 4 | 167 | 0 | SM | 481 | 1 |
| 253 | S 66139. | 1 | 211MGTY | 404332073212201 | 4043320732122 | 01 | 45.0 | 41.47 | 152 | 118 | 128 | 0 | 4 | 164 | 0 | SN | 490 | 1 |
| 254 | S 66142. | 1 | 211MGTY | 404815073163201 | 4048150731632 | 01 | 150.0 | 0.00 | 203 | 172 | 182 | 0 | 11 | 169 | 0 | SK | 882 | 1 |
| 255 | S 66143. | 1 | 211MGTY | 404541073180301 | 4045410731803 | 01 | 70.0 | 69.40 | 185 | 166 | 176 | 0 | 4 | 159 | 0 | SL | 739 | 1 |
| 256 | S 66144. | 1 | 211MGTY | 404448073164101 | 4044480731641 | 01 | 55.0 | 59.31 | 143 | 126 | 136 | 0 | 8 | 189 | 0 | SM | 799 | 1 |
| 257 | S 66145. | 1 | 211MGTY | 404435073171201 | 4044350731712 | 01 | 40.0 | 41.61 | 175 | 147 | 157 | 0 | 8 | 190 | 0 | SN | 760 | 1 |
| 258 | S 66429. | 1 | 211MGTY | 404326073174103 | 4043260731741 | 03 | 0.0 | 29.88 | 718 | 0 | 718 | 0 | 8 | 209 | 0 | SN | 708 | 7 |
| 259 | S 66576. | 1 | | 404335073184701 | 4043350731847 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN | 644 | |
| 260 | S 67538. | 1 | 112GLCLU | 404618073212102 | 4046180732121 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SK | 568 | 1 |
| 261 | S 67539. | 1 | | 404430073215602 | 4044300732156 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM | 481 | |
| 262 | S 67540. | 1 | | 404332073212202 | 4043320732122 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN | 490 | |
| 263 | S 67544. | 1 | 112GLCLU | 404541073180302 | 4045410731803 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SL | 739 | 1 |
| 264 | S 67546. | 1 | | 404435073171202 | 4044350731712 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN | 760 | |
| 265 | S 68334. | 1 | 112GLCLU | 404352073165101 | 4043520731651 | 01 | 41.0 | 0.00 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | SN | 766 | |
| 266 | S 71033. | 1 | 211MGTY | 404319073153701 | 4043190731537 | 01 | 29.7 | 0.00 | 592 | 0 | 592 | 0 | 0 | 0 | 0 | SO | 823 | 7 |
| 267 | S 71083. | 1 | 211MGTY | 404528073150701 | 4045280731507 | 01 | 61.9 | 56.43 | 798 | 0 | 798 | 0 | 8 | 187 | 0 | SM | 907 | 7 |
| 268 | S 72060. | 1 | | 404723073193701 | 4047230731937 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SK | 883 | |
| 269 | S 72917. | 1 | 211MGTY | 404419073171602 | 4044190731716 | 02 | 47.0 | 0.00 | 460 | 0 | 0 | 0 | 8 | 204 | 0 | SN | 752 | 7 |
| 270 | S 74489. | 1 | 112GLCLU | 404402073194002 | 4044020731940 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SM | 609 | |
| 271 | S 74492. | 1 | 112GLCLU | 404497073193901 | 4044970731939 | 01 | 0.0 | 0.00 | 16 | 16 | 26 | 0 | 0 | 0 | 0 | SM | 622 | |
| 272 | S 74493. | 1 | 112GLCLU | 404539073175701 | 4045390731757 | 01 | 0.0 | 0.00 | 35 | 25 | 35 | 0 | 4 | 159 | 0 | SM | 740 | |
| 273 | S 74494. | 1 | 112GLCLU | 404441073182801 | 4044410731828 | 01 | 0.0 | 0.00 | 30 | 20 | 30 | 0 | 4 | 164 | 0 | SM | 686 | |
| 274 | S 76016. | 1T | | 404530073181101 | 4045300731811 | 01 | 70.0 | 0.00 | 857 | 0 | 0 | 0 | 0 | 0 | 0 | SM | 721 | |
| 275 | S 76016. | 2 | 211MGTY | 404530073181102 | 4045300731811 | 02 | 63.5 | 63.17 | 762 | 752 | 757 | 0 | 0 | 0 | 0 | SM | 721 | 1 |
| 276 | S 76017. | 1 | 211MGTY | 404530073181103 | 4045300731811 | 03 | 63.2 | 62.85 | 503 | 495 | 500 | 0 | 0 | 0 | 0 | SM | 721 | 1 |
| 277 | S 76018. | 1 | 211MGTY | 404530073181104 | 4045300731811 | 04 | 63.0 | 62.76 | 194 | 186 | 191 | 0 | 0 | 0 | 0 | SM | 721 | 1 |
| 278 | S 76019. | 1 | 112GLCLU | 404530073181105 | 4045300731811 | 05 | 63.0 | 62.86 | 62 | 57 | 62 | 0 | 0 | 0 | 0 | SM | 721 | 1 |
| 279 | S 90097. | 1 | 112GLCLU | 404458073152901 | 4044580731529 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | SN | 860 | |
| 280 | S 90098. | 1 | 112GLCLU | 404458073152902 | 4044580731529 | 02 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 8 | 202 | 0 | SN | 860 | 1 |
| 281 | S 90099. | 1 | 112GLCLU | 404452073153701 | 4044520731537 | 01 | 52.2 | 52.16 | 25 | 23 | 25 | 75 | 8 | 202 | 0 | SN | 850 | 1 |
| 282 | S 90100. | 1 | 112GLCLU | 404450073153101 | 4044500731531 | 01 | 50.0 | 50.05 | 25 | 23 | 25 | 75 | 8 | 202 | 0 | SN | 861 | 1 |
| 283 | S 90101. | 1 | 112GLCLU | 404450073152801 | 4044500731528 | 01 | 50.0 | 50.61 | 25 | 23 | 25 | 75 | 8 | 202 | 0 | SN | 861 | 1 |
| 284 | S 90102. | 1 | 112GLCLU | 404444073152101 | 4044440731521 | 01 | 48.0 | 47.91 | 91 | 89 | 91 | 91 | 8 | 202 | 0 | SN | 872 | 1 |
| 285 | S 90103. | 1 | 112GLCLU | 404444073152002 | 4044440731520 | 02 | 48.0 | 48.27 | 90 | 88 | 90 | 90 | 8 | 202 | 0 | SN | 872 | 1 |
| 286 | S 90104. | 1 | 112GLCLU | 404444073152001 | 4044440731520 | 01 | 48.0 | 48.44 | 24 | 22 | 24 | 96 | 8 | 202 | 0 | SN | 872 | 1 |
| 287 | S 90105. | 1 | 112GLCLU | 404444073151901 | 4044440731519 | 01 | 48.5 | 48.45 | 96 | 94 | 96 | 96 | 8 | 202 | 0 | SN | 872 | 1 |
| 288 | S 90106. | 1 | 112GLCLU | 404444073151801 | 4044440731518 | 01 | 50.0 | 0.00 | 66 | 64 | 66 | 66 | 8 | 202 | 0 | SN | 872 | 1 |
| 289 | S 90107. | 1 | 112GLCLU | 404433073151801 | 4044330731518 | 01 | 43.5 | 43.18 | 87 | 84 | 87 | 87 | 8 | 202 | 0 | SN | 873 | 1 |
| 290 | S 90108. | 1 | 112GLCLU | 404433073151501 | 4044330731515 | 01 | 44.0 | 43.57 | 86 | 84 | 86 | 86 | 8 | 202 | 0 | SN | 874 | 1 |
| 291 | S 90109. | 1 | 112GLCLU | 404434073151201 | 4044340731512 | 01 | 44.5 | 44.28 | 84 | 82 | 84 | 84 | 8 | 202 | 0 | SN | 874 | 1 |
| 292 | S 90110. | 1 | 112GLCLU | 404434073150901 | 4044340731509 | 01 | 45.0 | 44.83 | 86 | 84 | 86 | 86 | 8 | 202 | 0 | SN | 874 | 1 |
| 293 | S 91148. | 1 | 112GLCLU | 404435073150801 | 4044350731508 | 01 | 44.5 | 44.12 | 89 | 87 | 89 | 89 | 8 | 202 | 0 | SN | 884 | 1 |
| 294 | S 91149. | 1 | 112GLCLU | 404432073151305 | 4044320731513 | 05 | 42.4 | 43.48 | 86 | 84 | 86 | 97 | 8 | 202 | 0 | SN | 874 | 1 |
| 295 | S 91150. | 1 | 112GLCLU | 404430073151001 | 4044300731510 | 01 | 42.5 | 42.03 | 91 | 89 | 91 | 91 | 8 | 202 | 0 | SN | 874 | 1 |
| 296 | S 91151. | 1 | 112GLCLU | 404429073150901 | 4044290731509 | 01 | 38.5 | 37.89 | 83 | 81 | 83 | 83 | 8 | 202 | 0 | SN | 874 | 1 |
| 297 | S 91152. | 1 | 112GLCLU | 404425073145701 | 4044250731457 | 01 | 38.2 | 38.05 | 0 | 0 | 0 | 0 | 8 | 202 | 0 | SN | 885 | 1 |
| 298 | S 91153. | 1 | 112GLCLU | 404422073145901 | 4044220731459 | 01 | 37.0 | 36.99 | 86 | 84 | 86 | 86 | 8 | 202 | 0 | SN | 885 | 1 |
| 299 | S 91154. | 1 | 112GLCLU | 404422073145701 | 4044220731457 | 01 | 38.0 | 37.98 | 80 | 78 | 80 | 80 | 8 | 202 | 0 | SN | 886 | 1 |
| 300 | S 91155. | 1 | 211MGTY | 404430073154803 | 4044300731548 | 03 | 0.0 | 0.00 | 133 | 131 | 133 | 0 | 8 | 202 | 0 | SN | 887 | 1 |

| WELL | AQUIFER | STATION ID | LAT-LONG | SQ | LSD | MP | DEPTH | --SCREEN-- | | MAX DRILL | TOWN | COMM | SWDST | ZON | HGSTRM | WELUS |
|----------------|----------|-----------------|---------------|----|------|-------|-------|------------|--------|--------------|------|------|-------|-----|--------|-------|
| | | | | | | | | TOP | BOTTOM | | | | | | | |
| 301 S 91156. 1 | 112GLCLU | 404430073154602 | 4044300731548 | 02 | 0.0 | 0.00 | 12 | 7 | 12 | 12 | 8 | 202 | 0 | | SN 843 | 1 |
| 302 S 91157. 1 | 211MGTY | 404417073143402 | 4044170731434 | 02 | 0.0 | 0.00 | 134 | 131 | 134 | 0 | 8 | 202 | 0 | | SN 907 | 1 |
| 303 S 91158. 1 | 211MGTY | 404432073151306 | 4044320731513 | 06 | 42.8 | 44.44 | 153 | 145 | 150 | 0 | 8 | 202 | 0 | | SN 874 | 1 |
| 304 S 91159. 1 | 112GLCLU | 404432073151307 | 4044320731513 | 07 | 43.1 | 44.51 | 318 | 310 | 315 | 0 | 8 | 202 | 0 | | SN 874 | 1 |
| 305 S 91160. 1 | 211MGTY | 404436073150101 | 4044360731501 | 01 | 44.0 | 45.76 | 136 | 129 | 133 | 136 | 8 | 202 | 0 | | SN 884 | 1 |
| 306 S 91161. 1 | 112GLCLU | 404436073150102 | 4044360731501 | 02 | 44.0 | 45.40 | 46 | 36 | 46 | 46 | 8 | 202 | 0 | | SN 884 | 1 |
| 307 S 91162. 1 | 211MGTY | 404400073154403 | 4044000731544 | 03 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 8 | 202 | 0 | | SN 837 | 1 |
| 308 S 92392. 1 | 112GLCLU | 404517073181401 | 4045170731814 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 712 | 1 |
| 309 S 92393. 1 | 112GLCLU | 404518073182401 | 4045180731824 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 702 | 1 |
| 310 S 92394. 1 | 112GLCLU | 404529073173701 | 4045290731737 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 752 | 1 |
| 311 S 92395. 1 | 112GLCLU | 404448073181001 | 4044480731810 | 01 | 0.0 | 0.00 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | SM 716 | 1 |

REFERENCE NO. 12



PROJECT NOTE

TO: Commercial Envelope Mfg. Cont'luc. fileDATE: 23 June 1994FROM: J.D. MinsavageW.O. NO.: 04200-022-081-0006-SUBJECT: Geology in the vicinity of the site

A survey of well logs for wells installed in Suffolk County was paired to those located within 1 mile of the site. A table of the information collected from these well logs is attached; Within 1 mile of the site the depth to the Magothy ranges from 104 to 138 feet below ground surface (bgs).

Within 0.5 mile of the site the depth to the Magothy ranges from 110 to 120 feet bgs. Only one well log indicated the underlying Raritan Confining Unit was penetrated - this well, located approximately 0.2 mile from the site indicates the thickness of the Magothy in the vicinity of the site is 710 feet.

A 9-foot thick Gardiners Clay Unit was encountered in 2 of the 11 wells investigated; the Gardiners Clay overlies the Magothy Formation, but is not continuous throughout the region. [See Attachment A]

The well logs were culled from "Hydrogeologic Correlations for Selected Wells on Long Island, New York" U.S. G.S. Water-Resource Investigations Report 86-4318. [See Attachment B]

Additional Attachments document general geology of the area and the general groundwater flow patterns in the glacial and Magothy aquifers. [See Attachments C and D]

**GEOLOGY ENCOUNTERED IN WELLS INSTALLED WITHIN 1 MILE
OF THE COMMERCIAL ENVELOPE MFG. CO., INC. SITE**

| Well ID No. | Distance (miles) | Latitude | Longitude | Altitude of well (sea level) | | Well depth (ft) | Depth hydrogeologic unit penetrated/unit surface | | | Depth to Magothy (ft) | Magothy Thickness (ft) |
|----------------|---------------------|----------|-----------|---------------------------------|--------|-----------------------|--------------------------------------------------|---------|---------------------------|-----------------------------|------------------------------|
| | | | | top | bottom | | Gardiners Clay | Magothy | Raritan Confining Unit | | |
| S-4266 | 1.0 | 404630 | 731800 | 80 | -45 | 125 | | | | NA | NA |
| S-12873 | 0.4 | 404558 | 731825 | 82 | -306 | 388 | | -38 | | 120 | >268 |
| S-23045 | 0.7 | 404502 | 731822 | 60 | -545 | 605 | | -44 | | 104 | >501 |
| S-23046 | 0.8 | 404457 | 731824 | 60 | -45 | 105 | | | | NA | NA |
| S-25617 | 0.8 | 404458 | 731823 | 64 | -377 | 441 | | | | NA | NA |
| S-35669 | 0.6 | 404604 | 731751 | 70 | -48 | 118 | | -38 | | 108 | >10 |
| S-40497 | 0.7 | 404606 | 731746 | 74 | -210 | 284 | | -64 | | 138 | >146 |
| S-46830 | 0.7 | 404606 | 731746 | 76 | -579 | 655 | | -60 | | 136 | >519 |
| S-65196 | 0.8 | 404529 | 731719 | 69 | -55 | 124 | -39 | -48 | | 117 | >7 |
| S-66143 | 0.3 | 404540 | 731754 | 70 | -115 | 185 | -36 | -45 | | 115 | >70 |
| S-76016 | 0.2 | 404540 | 731811 | 65 | -792 | 857 | | -45 | -755 | 110 | 710 |

HYDROGEOLOGIC CORRELATIONS FOR SELECTED WELLS ON
LONG ISLAND, NEW YORK--

A data base with retrieval program

by H. T. Buxton, D. A. Smolensky, and P. K. Shernoff

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations
Report 86-4318

Prepared in cooperation with the

NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS
SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
SUFFOLK COUNTY WATER AUTHORITY
NEW YORK CITY DEPARTMENT OF ENVIRONMENTAL PROTECTION



Syosset, New York

1989

DEPARTMENT OF THE INTERIOR
MANUEL LUJAN, JR., Secretary

U.S. GEOLOGICAL SURVEY
Dallas L. Peck, Director

For additional information
write to:

U.S. Geological Survey
5 Aerial Way
Syosset, New York 11791
(516) 938-8830

Copies of this report may be
purchased from:

U.S. Geological Survey
Books and Open-File Reports
Federal Center Bldg. 41
Box 25425
Denver, CO 80225
(303) 236-7476

HYDROGEOLOGIC CORRELATIONS FOR SELECTED WELLS ON LONG ISLAND, NEW YORK--

A data base with retrieval program

By H. T. Buxton, D. A. Smolensky, and P. K. Shernoff

ABSTRACT

Accurate delineation of Long Island's internal hydrogeologic structure is integral to the understanding and management of the ground-water system. The irregular extent and surface configuration of Long Island's seven major hydrogeologic units give the ground-water system a complex internal structure. This report presents a computerized data base of hydrogeologic correlations for 3,146 wells on Long Island and adjacent parts of New York City. The data base includes the well-identification number, the latitude and longitude of the well location, the altitude of land surface at the well, the altitude of the bottom of the drilled hole, and the altitude of the upper surface of the major hydrogeologic units penetrated by the well. A computer program is included that allows retrievals of selected types of data for all or any local area of Long Island. These data retrievals are a valuable aid to the construction of hydrogeologic-surface maps.

INTRODUCTION

Long Island extends approximately 120 mi eastward from the East River and New York Harbor to Montauk Point (fig. 1). It contains the densely populated boroughs of New York City (Kings and Queens Counties) in the west, suburban Nassau and western Suffolk Counties in the central part, and areas of farmlands and pine barrens in the east.

Ground water is the sole source of freshwater supply for the 2.6 million inhabitants of Nassau and Suffolk Counties. About 500 Mgal/d was pumped from the Island's ground-water reservoir in 1981 for public supply, commercial, and agricultural needs. This demand is expected to increase in coming years, which will make proper resource management imperative.

Long Island's geologic history has consisted of alternating periods of erosion and deposition. The result is a sequence of aquifers and confining units of irregular extent and surface configuration that give the ground-water system a complex internal structure. This irregular internal geometry has a large influence on the patterns and rates of ground-water flow. Ground-water flow is retarded where the aquifers are separated by a confining unit but is unimpeded where the intervening confining unit has been eroded or where cut-and-fill deposition makes two aquifers laterally contiguous.

Knowledge of the internal hydrogeologic structure is necessary for efficient resource management, which includes (1) designing future water-development plans; (2) selecting sites for waste disposal; (3) locating and tracking the movement of contaminants within the ground-water system; and (4) mitigating other undesirable effects of man's influence on the system, such as streamflow depletion and saltwater intrusion.

Purpose and Scope

This report presents a computerized data base of hydrogeologic-unit correlations for 3,146 wells on Long Island and adjacent parts of New York City. The data base (at end of report) gives the altitude at which the upper surface of each of seven major hydrogeologic units was penetrated and also includes the location, land-surface altitude, and depth of each well.

The following sections discuss the hydrogeologic units and the well data used to correlate surface altitudes for each unit; they also describe the format of the data base and explain each element. Also included is a description of a simple system of data retrieval that facilitates construction of hydrogeologic maps with a computer program.

A report by Smolensky and others (in press) presents a set of maps showing the configuration of the upper surface of these hydrogeologic units. The correlations presented herein were developed during construction of those maps and are consistent with their representation of the system geometry. The data-retrieval methods described in this report were used during map construction.




Figure 1.--Location of Long Island, N.Y., and of hydrogeologic sections depicted in figure 9.

Previous Investigations

Some previous hydrogeologic investigations that were completed on a local scale were used as a starting point for this study. Krulikas (1981) and Jensen and Soren (1971) evaluated the hydrogeology of Suffolk County, Kilburn (1980) and Kilburn and Krulikas (1986) evaluated the hydrogeology of parts of Nassau County, and Buxton and others (1981) evaluated the hydrogeology of Kings and Queens Counties.

Acknowledgments

The authors greatly appreciate support provided by the New York State Department of Environmental Conservation, Nassau County Department of Public Works, Suffolk County Department of Health Services, Suffolk County Water Authority, and New York City Department of Environmental Protection.

HYDROGEOLOGIC FRAMEWORK


Long Island is underlain by unconsolidated deposits of clay, silt, sand, and gravel that overlie southward-dipping consolidated bedrock (fig. 2). The unconsolidated deposits are thinnest in northern Queens County (northwestern Long Island) and thicken to the south and east to a maximum thickness of 2,000 ft at the south shore. These deposits contain several distinct geologic units ranging in age from Late Cretaceous through Pleistocene, with some recent deposits near shores and along streams. These units are differentiated by age, method of deposition, and lithology in table 1.

In studies of ground-water availability and flow patterns, correlations that are based strictly on geologic factors may not adequately describe the internal structure of the hydrologic system; generally an interpretation in which the units are differentiated on the basis of water-transmitting properties is more useful. Thus, table 1 gives both the geologic units and the corresponding hydrogeologic units and shows their stratigraphic relationships. Eight major hydrogeologic units are indicated; these are, in order of deposition, consolidated bedrock, the Lloyd aquifer, the Raritan confining unit, the Magothy aquifer, the Monmouth greensand, the Jameco aquifer, the Gardiners Clay, and the upper glacial aquifer. The two hydrogeologic vertical sections shown in figure 3 depict the relative position of these units in western and eastern Long Island, respectively. The Jameco aquifer is present only in western Long Island (fig. 3A), and the Monmouth greensand is present only in eastern Long Island (fig. 3B). A map showing the extent and configuration of all units below the upper glacial aquifer is given in Smolensky and others (in press). Other local hydrogeologic units have been identified within the upper glacial deposits but are not discussed herein.

Table 1.--Hydrogeologic units of Long Island and their water-bearing properties.

| System | Series | Geologic unit | Hydro-geologic unit | Approximate maximum thickness (ft) | Character of deposits | Water-bearing properties |
|------------|-------------|--------------------------------------------------------------------------------------|-----------------------|------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Quaternary | Holocene | Recent deposits: Salt marsh deposits, stream alluvium, shoreline deposits, and fill. | Recent deposits | 50 | Sand, gravel, clay, silt, organic mud, peat, loam, and shells. Colors are gray, brown, green, black, and yellow. | Beach deposits are highly permeable; marsh deposits poorly permeable. Locally hydraulically connected to underlying aquifers. |
| | Pleistocene | Upper Pleistocene deposits | Upper glacial aquifer | 700 | Till composed of clay, sand, gravel, and boulders, forms Harbor Hill and Ronkonkoma terminal moraines. Outwash deposits consist of quartzose sand, fine to very coarse, and gravel, pebble to boulder sized. Also contains lacustrine, marine, and reworked deposits. Local units are Port Washington aquifer and confining unit, "20-foot clay," and clay at Smithtown. | Till is poorly permeable. Outwash deposits are moderately to highly permeable. Glaciolacustrine and marine clay deposits are mostly poorly permeable but locally have thin, moderately permeable layers of sand and gravel. Average horizontal hydraulic conductivity is approximately 270 ft/d; conductivity of morainal material is approximately 50 percent of outwash deposits; anisotropy is approximately 10:1. |
| | | unconformity? | | | | |
| | | Gardiners Clay | Gardiners Clay | 150 | Clay, silt, and few layers of sand. Colors are grayish green and brown. Contains marine shells and glauconite. | Poorly permeable; constitutes a confining layer for underlying aquifer. Some sand lenses may be permeable. Average vertical hydraulic conductivity is approximately 0.001 ft/d. |
| | | unconformity? | | | | |
| | | Jameco Gravel | Jameco aquifer | 200 | Sand, fine to very coarse, and gravel to large-pebble size; few layers of clay and silt. Gravel is composed of crystalline and sedimentary rocks. Color is mostly brown. | Moderately to highly permeable. Confined by overlying Gardiners Clay. Average horizontal hydraulic conductivity is 200 to 300 ft/d; anisotropy is approximately 10:1. |
| | | unconformity | | | | |

| | | | | | | | | | |
|---------------------------|------------------|-------------------|--------------|---------------------------------------------------|---------------------|------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Cretaceous | Upper Cretaceous | unconformity | | Monmouth Group | Monmouth Greensand | 200 | Interbedded marine deposits of clay, silt, and sand, dark-greenish gray, greenish-black, greenish, dark-gray, and black, containing much glauconite. | Poorly permeable; primarily a confining unit for underlying Magothy aquifer. Average vertical hydraulic conductivity is approximately 0.001 ft/d. | |
| | | unconformity | | Matawan Group-Magothy Formation, undifferentiated | Magothy aquifer | 1,100 | Sand, fine to medium, clayey in part; interbedded with lenses and layers of coarse sand and sandy and solid clay. Gravel is common in basal zone. Sand and gravel are quartzose. Lignite, pyrite, and iron oxide concretions are common. Colors are gray, white, red, brown, and yellow. | Most layers are poorly to moderately permeable; some are highly permeable locally. Water is unconfined in uppermost parts, elsewhere is confined. Constitutes principal aquifer for public supply. Average horizontal hydraulic conductivity is 50 ft/d; anisotropy is approximately 100:1. | |
| | | Raritan Formation | unconformity | | Unnamed clay member | Raritan confining unit | 200 | Clay, solid and silty; few lenses and layers of sand. Lignite and pyrite are common. Colors are gray, red, and white, commonly variegated. | Poorly to very poorly permeable; constitutes confining layer for underlying Lloyd aquifer. Average vertical hydraulic conductivity is approximately 0.001 ft/d. |
| | | | | | Lloyd Sand Member | Lloyd aquifer | 500 | Sand, fine to coarse, and gravel, commonly with clayey matrix; some lenses and layers of solid and silty clay; locally contains thin lignite layers. Sand and most of gravel are quartzose. Colors are yellow, gray, and white; clay is red locally. | Poorly to moderately permeable. Water is confined by overlying Raritan clay. Average horizontal hydraulic conductivity is 40 ft/d; anisotropy is approximately 10:1. |
| | | unconformity | | Bedrock | | Bedrock | - - | Crystalline metamorphic and igneous rocks; muscovite-biotite schist, gneiss, and granite. A soft, clayey zone of weathered bedrock locally is more than 70 ft thick. | Poorly permeable to virtually impermeable; constitutes lower boundary of ground-water reservoir. Some hard fresh water is contained in joints and fractures but is impractical to develop at most places. |
| Precambrian and Paleozoic | - - - | | | | | | | | |



EXPLANATION

1800 ——— LINE OF EQUAL THICKNESS OF UNCONSOLIDATED DEPOSITS--
Dashed where approximately located. Contour interval 200 feet

Figure 2.--Thickness of unconsolidated deposits on Long Island.




Figure 9.--Generalized vertical sections showing major hydrogeologic units:
 A. On western Long Island. B. On eastern Long Island.
 (Locations are shown in fig. 1.)


Loan Copy

ATTACHMENT C

UNITED STATES DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

**POTENTIOMETRIC-SURFACE ALTITUDE OF MAJOR
AQUIFERS ON LONG ISLAND, NEW YORK, IN 1983**

By
Thomas P. Doriski



WATER-RESOURCES INVESTIGATIONS REPORT 85-4321

Plate 1. Water-table altitude

Plate 3. Potentiometric surface of Magothy aquifer

Plate 2. Water-table well numbers

Plate 4. Potentiometric surface of Lloyd aquifer

Prepared in cooperation with the
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
SUFFOLK COUNTY WATER AUTHORITY

Syosset, New York

1986

WATER-TABLE ALTITUDE ON LONG ISLAND, NEW YORK, IN MARCH 1983

The general configuration of the water table on Long Island is an east-west-trending mound along the center of Long Island with an isolated high in central Nassau County and another in central Suffolk County. This map depicts the static water levels in March 1983 in wells tapping the water table.

The New York State Department of Environmental Conservation well numbers are shown on plate 2. These wells are screened in the upper glacial aquifer except where the entire thickness of the aquifer is unsaturated and the water table is in the upper part of the Magothy aquifer.

The water-table altitudes range from 9.4 ft below sea level in central Queens County to 111.5 ft above sea level in northwestern Nassau County. The water table is, in general, 1 to 7 ft lower than in 1979 (Donaldson and Koszalka, 1983). Also indicated are the approximate water-surface altitudes of south-shore streams that have been surveyed; the water levels in these gaining streams indicate the water-table altitude adjacent to the stream.

The water table is high in several areas on Long Island, because the geologic units have low hydraulic conductivity. These areas are the north-central part of the south fork in eastern Suffolk County (sheet 2), the Flanders area in eastern Suffolk County along Riverhead-Hampton Bays Road (Rt. 24 on sheet 2), several areas near the Northern State Parkway in western Suffolk County (sheet 1), northern Nassau County, particularly Manhasset Neck north of Northern State Parkway (sheet 1), and the Park Slope section of Brooklyn, south of Flatbush Avenue (sheet 1). The water table tends to be slightly elevated where the clay at Smithtown is present--particularly the Lake Ronkonkoma area (sheet 1), which is underlain by the clay and has a higher hydraulic head than the area south of Lake Ronkonkoma, where the clay is absent. The extent of the clay at Smithtown is depicted in Krulikas and Koszalka (1983).

Most wells on plate 1 were measured in March 1983. In comparing the water levels in the water-table aquifer to water levels in the Magothy aquifer (pl. 3), also measured in March, the user should verify whether the wells in each aquifer were measured at approximately the same time of the month to account for differences due to precipitation. Information on the date and time of water-level measurements is available at the U.S. Geological Survey in Syosset, N.Y.


This study was done in cooperation with the Nassau County Department of Public Works, Suffolk County Department of Health Services, Suffolk County Water Authority, and the New York State Department of Environmental Conservation.

REFERENCES CITED

- Donaldson, C. D., and Koszalka, E. J., 1983, Water table on Long Island, New York, March 1979: U.S. Geological Survey Open-File Report 82-163, 2 sheets.
- Krulikas, R. K., and Koszalka, E. J., 1983, Geologic reconnaissance of an extensive clay unit in north-central Suffolk County, Long Island, New York: U.S. Geological Survey Water-Resources Investigations Report 82-4075, 9 p.

WATER-TABLE ON LONG ISLAND, NEW YORK, MARCH 1980

WATER-RESOURCES INVESTIGATIONS REPORT 85-4
PLATE 1A--WATER-TABLE ALTITUDE--W



general, 1
Koszalka, 1
water level
28 ft below

REFERENCES CITED

- Buxton, H. T., Soren, Julian, Posner, Alex, and Shernoff, P. K., 1981, Reconnaissance of the ground-water resources of Kings and Queens Counties, New York: U.S. Geological Survey Open-File Report 81-1186, 59 p.
- Donaldson, C. D., and Koszalka, E. J., 1983, Potentiometric surface of the Magothy aquifer, Long Island, New York, in March 1979: U.S. Geological Survey Open-File Report 82-160, 2 sheets.
- Kilburn, Chabot, 1979, Hydrogeology of the Town of North Hempstead, Nassau County, Long Island, New York: Long Island Water Resources Bulletin 12, 87 p.
- Kilburn, Chabot, and Krulikas, R. K., Hydrogeology and ground-water quality of the northern part of the Town of Oyster Bay, Nassau County, New York, in 1980: U.S. Geological Survey Water-Resources Investigations Report 85-4051 (in press).
- Nemickas, Bronius, and Koszalka, E. J., 1982, Geohydrologic appraisal of water resources of the South Fork, Long Island, New York: U.S. Geological Survey Water-Supply 2073, 55 p.

On the
County (shee
saline exce
(Nemickas a
the Magothy
depicted he
data of Bux
Nassau Coun
(1979) and

Most w
March 1983.
Magothy aqu
measured in
wells in ea
the same ti
due to prec
of water-le
Geological

This w
County Depa
Department
Authority,
Environment
extended to
on Long Isl
measurement

POTENTIOMETRIC SURFACE OF THE MAGOTHY AQUIFER, LONG ISLAND, NEW YORK, IN MARCH 1983

The Magothy aquifer of the Cretaceous Magothy Formation and overlying Matawan Group undifferentiated supplies water for public supply and industrial use in Nassau and Suffolk Counties. The potentiometric-surface altitude is monitored by the U.S. Geological Survey. This map depicts the static water-level measurements taken in March 1983 in observation wells and public-supply wells screened in the Magothy aquifer.

The measurements show the potentiometric-surface altitude to range from 9.8 ft below sea level in eastern Queens County to 83.5 ft above sea level in central Nassau County (sheet 1). The general shape of the potentiometric surface is similar to that of the overlying upper glacial (water-table) aquifer, rising gradually from a depression in the western part of the island to an east-west mound in the central part. In areas where deep channels have been eroded into the Magothy aquifer and filled with glacial deposits, the potentiometric-surface contours were drawn from water levels measured in wells screened deep in these glacial deposits, which are laterally contiguous and hydraulically connected with the Magothy aquifer.

The potentiometric-surface altitude is, in general, 1 to 7 ft lower than in 1979 (Donaldson and Koszalka, 1983), except in central Queens County, where water levels in the depression area have recovered from 28 ft below sea level in 1979 to 10 ft below sea level.

On the north and south forks of eastern Suffolk County (sheet 2), water in the Magothy aquifer is saline except in the central part of the south fork (Nemickas and Koszalka, 1982). The northern limit of the Magothy aquifer in Kings and Queens Counties as depicted here has been revised in accordance with data of Buxton and others (1981); its northern limit in Nassau County has been revised according to Kilburn (1979) and Kilburn and Krulikas (1985).

Most wells shown on this map were measured in March 1983. In comparing the water levels in the Magothy aquifer with the water table (plate 1), also measured in March 1983, the user should verify that the wells in each aquifer were measured at approximately the same time of the month to account for differences due to precipitation. Information on the date and time of water-level measurements is available at the U.S. Geological Survey in Syosset, N.Y.

This work was done in cooperation with the Nassau County Department of Public Works, Suffolk County Department of Health Services, Suffolk County Water Authority, and the New York State Department of Environmental Conservation. Special thanks are extended to the water companies and private industries on Long Island who cooperated in the static water-level measurements.

Alex, and
sance of the
and Queens
ogical Survey

J., 1983, Potentio-
uifer, Long
U.S. Geological
2 sheets.

f the Town of
Long Island, New
rces Bulletin 12,

., Hydrogeology and
rthern part of the
y, New York, in
water-Resources
(in press).

., 1982, Geohydro-
rces of the South
S. Geological

Loan Copy Only

ATTACHMENT D

DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

HYDROLOGIC FRAMEWORK OF LONG ISLAND, NEW YORK

By D.A. Smolensky, H.T. Buxton, and P.K. Shernoff

Prepared in cooperation with the
NEW YORK CITY DEPARTMENT OF ENVIRONMENTAL PROTECTION,
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS,
SUFFOLK COUNTY WATER AUTHORITY and DEPARTMENT OF HEALTH SERVICES

HYDROLOGIC INVESTIGATIONS ATLAS
Published by the Geological Survey, 1989

SMOLENSKY AND OTHERS—HYDROGEOLOGIC FRAMEWORK OF LONG ISLAND, NEW YORK 1:250,000 ATLAS HA-709

Loan Copy Only

DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

HYDROLOGIC FRAMEWORK OF LONG ISLAND, NEW YORK

By D.A. Smolensky, H.T. Buxton, and P.K. Shernoff

Prepared in cooperation with the
NEW YORK CITY DEPARTMENT OF ENVIRONMENTAL PROTECTION,
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS,
SUFFOLK COUNTY WATER AUTHORITY and DEPARTMENT OF HEALTH SERVICES

HYDROLOGIC INVESTIGATIONS ATLAS
Published by the Geological Survey, 1989

INTRODUCTION

Long Island, N.Y., is underlain by a mass of unconsolidated geologic deposits of clay, silt, sand, and gravel that overlie southward-sloping consolidated bedrock. These deposits are thinnest in northern Queens County (northwestern Long Island), where bedrock crops out, and increase to a maximum thickness of 2,000 ft in southeastern Long Island. This sequence of unconsolidated deposits consists of several distinct geologic units ranging in age from late Cretaceous through Pleistocene, with some recent deposits near shores and streams. These units are differentiated by age, depositional environment, and lithology in table 1.

Investigations of ground-water availability and flow patterns may require information on the internal geometry of the hydrologic system that geologic correlations and interpretation alone cannot provide; hydrologic interpretations in which deposits are differentiated on the basis of water-transmitting properties are generally needed also. This set of maps and vertical sections depicts the hydrogeologic framework of the unconsolidated deposits that form Long Island's ground-water system. These deposits can be classified into eight major hydrogeologic units (table 1). The hydrogeologic interpretations presented herein are not everywhere consistent with strict geologic interpretation owing to facies changes and local variations in the water-transmitting properties within geologic units.

These maps depict the upper-surface altitude of seven of the eight hydrogeologic units, which, in ascending order, are: consolidated bedrock, Lloyd aquifer, Raritan confining unit, Magothy aquifer, Monmouth greensand, Jameco aquifer, and Gardiners Clay. The upper glacial aquifer—the uppermost unit—is at land surface over most of Long Island and is, therefore, not included. The nine north-south hydrogeologic sections shown below depict the entire sequence of unconsolidated deposits and, together with the maps, provide a detailed three-dimensional interpretation of Long Island's hydrogeologic framework.

The structure-contour map that shows the upper-surface altitude of the Cretaceous deposits is included to illustrate the erosional unconformity between the Cretaceous and overlying Pleistocene deposits. Pleistocene erosion played a major role in determining the shape and extent of the Lloyd aquifer, the Raritan confining unit, and the Magothy aquifer, and thus partly determined their hydrogeologic relation with subsequent (post-Cretaceous) deposits.

PREVIOUS HYDROGEOLOGIC INVESTIGATIONS

The first attempt to map the complete sequence of geologic units on an islandwide scale was made by Suter and others (1949) despite a paucity of data. The most recent report to interpret the hydrogeology of Long Island on an islandwide scale was by McClymonds and Franke (1972) which gives the estimated thickness of the Lloyd, Magothy, Jameco, and upper glacial aquifers. Recent investigations have provided more detailed information in several local areas.

The hydrogeologic framework of Kings and Queens Counties has been evaluated by Buxton and Shernoff (U.S. Geological Survey, written comm., 1985), and the northern part of Nassau County has been studied by Kilburn (1980) and Kilburn and Krulikas (1986). The Roosevelt and Mitchell Field area in Nassau County has been studied by Eckhardt (in press), and the upper surface altitude of the Matawan Group and Magothy Formation and shallower geologic units of southern Nassau and Suffolk Counties have been mapped by Doriski and Wilde-Katz (1982).

Jensen and Soren (1974) mapped the complete sequence of aquifers and confining units in Suffolk county. Local hydrogeologic studies in Suffolk County include the Montauk Point area (Prince, 1986); the south fork (Nemickas and Koszalka, 1982); the northern part of the Town of Brookhaven (Koszalka, 1980); and the surface of the Matawan Group and Magothy Formation in Suffolk County (Krulikas, Koszalka, and Doriski, 1983). All of these reports define either geologic or hydrogeologic units, which may create some discrepancies upon comparison owing to the

Jensen and Soren (1974) mapped the complete sequence of aquifers and confining units in Suffolk county. Local hydrogeologic studies in Suffolk County include the Montauk Point area (Prince, 1986); the south fork (Nemickas and Koszalka, 1982); the northern part of the Town of Brookhaven (Koszalka, 1980); and the surface of the Matawan Group and Magothy Formation in Suffolk County (Krulik, Koszalka, and Doriski, 1983). All of these reports define either geologic or hydrogeologic units, which may create some discrepancies upon comparison owing to the differing criteria for interpretation.

The hydrogeologic units on Long Island can be correlated with those of northeastern New Jersey, which have been investigated by Gill and Farlekas (1976), Minard (1969), Zapoczka (1984). Although southern Connecticut parallels the north shore of Long Island (fig.1), it lacks the hydrogeologic units of Long Island because they pinch out beneath the Long Island Sound.

SOURCES OF DATA

Two major sources of hydrogeologic data were used to construct the maps—records of wells and offshore seismic surveys.

Well Data

The well data used in this investigation include drillers' logs, geophysical logs, and geologists' descriptions of cores and other drilling samples. Hydrogeologic data from more than 3,100 wells on Long Island are available. Hydrogeologic interpretations of all wells used in this study, including the altitude of the upper surface of each unit penetrated, are given in a report by Buxton, Smolensky, and Shernoff (in press). Hydrogeologic data on these wells are on file at the U.S. Geological Survey office in Syosset, N.Y.

Offshore Seismic Surveys

Several seismic surveys conducted in recent years have produced a means of mapping offshore structures. Primarily through reflection techniques, the configuration of the bedrock and Cretaceous surfaces under the water surrounding Long Island have been defined. Grim and others (1970) and the U.S. Geological Survey (1970) contoured the eroded surface of the Cretaceous deposits and bedrock beneath Long Island Sound. Williams (1976) investigated the shallow bottom structure off Long Island with emphasis around the north and south forks. McMaster and Ashraf (1973) discuss paleo-drainage in New England and Long Island and resultant buried valleys. Hutchinson (written commun., 1984) has interpreted data from recent cruises on the Long Island Sound and on the inner continental shelf directly south of Long Island.

In this study, knowledge gained from offshore seismic survey was used to correlate onshore and offshore data and to project the extent of the hydrogeologic units offshore. The eroded surface of Cretaceous deposits or consolidated bedrock beneath Long Island Sound (U.S. Geological Survey, 1970) was correlated with the surface of the Upper Cretaceous unit onshore. The dip of the relatively flat underlying Cretaceous units was assumed to persist offshore; thus the onshore surfaces were extended northward to their contact with the Cretaceous or bedrock surface. The bedrock surface was similarly extended northward to the point at which the effects of post-Cretaceous erosion could be observed. The extent of each Cretaceous unit is defined by the point of post-Cretaceous erosion on the next underlying unit. The logic of this analysis is consistent with the concepts of the sedimentation model described in the following section.

EROSIONAL AND DEPOSITIONAL HISTORY

The unconsolidated deposits that comprise the hydrogeologic framework of Long Island reflect the island's erosional and depositional history.

Present-day depositional environments show the close relation between environment of deposition and type and rate of sediments deposited. These relations can be applied to the present sequence of sediments and their structure and characteristics to identify and correlate recurring intervals of deposition, nondeposition, and (or) erosion in the paleo-environments.

This study used a theoretical sedimentation model to help define the structure and configuration of the individual hydrogeologic units. The model was used to help conceptualize the type, location, and thickness of sediments on the basis of a sequence of changing physical environments through geologic time.

The following paragraphs briefly summarize the paleo-environments in Long Island's geologic past and their correlation with the present hydrogeologic units on Long Island.

Consolidated bedrock on Long Island (sheet 2) is of Precambrian and/or Paleozoic age, and its surface configuration is defined as a peneplain (Suter and others, 1949). Because Paleozoic and lower Mesozoic deposits are absent above bedrock, the period when erosion on the bedrock surface occurred cannot be dated.

The overlying Cretaceous age sediments can be characterized by three periods of deposition, each separated by an interval of nondeposition and (or) erosion. The lowermost Cretaceous sediments on Long Island, which form the Raritan Formation, were probably deposited in an environment dominated by streams and coalescing deltas (Buxton and others, 1981). These deposits exhibit a distinct fining upward that may be a result of changing stream gradients and (or) a prograding shoreline. The formation has been divided into two members—the Lloyd Sand Member (Lloyd aquifer) and a conformable overlying unnamed clay member (Raritan confining unit). These members are differentiated primarily by grain size. The intervening conformity is relatively flat lying and dips gradually to the southeast (sheet 2).

The first interval of nondeposition (or erosion) is shown by a distinct unconformity that separates the fine-grained clay member of the Raritan Formation from the coarse basal zone of the Matawan Group and Magothy Formation, undifferentiated (Magothy aquifer). This unconformity is shown on the surface configuration of the Raritan clay member (sheet 2) and indicates little erosion.

After the interval of nondeposition, the Magothy Formation was deposited in an environment again dominated by streams and coalescing deltas (Doriski and Wilde-Katz, 1983). Its coarse basal zone indicates an environment of high energy that decreased rapidly, causing an upward gradation to the fine sands and clays that form the bulk of this unit.

The Monmouth Group (Monmouth greensand) unconformably overlies the Matawan Group and Magothy Formation, undifferentiated. The unconformity between these units indicates a second interval of nondeposition or erosion during the Cretaceous on Long Island. The surface of this deposit is gently rolling with no severe erosion (sheet 3). The clay and silty sand material that forms the Monmouth Group (sheet 3) was deposited by a transgressing sea. The abundance of glauconite indicates a quiet marine environment.

Although Tertiary deposits are reported offshore south of Long Island, they are not present onshore. Whether Tertiary deposition occurred and was subsequently eroded, or never occurred, is uncertain.

Several episodes of Pleistocene glaciation by a southward advance from New England and the Hudson River valley severely eroded the Cretaceous deposits. The unconformity, which extends across Long Island between all Cretaceous and overlying deposits, reflects the glacial scouring and glaciofluvial erosion typical of the high-energy Pleistocene environments.

The well-dissected surface of Cretaceous or older deposits is depicted on sheet 1. The erosion is most severe on the north shore and in Long Island Sound, where glacial processes locally cut through the entire sequence of Cretaceous deposits and, in some areas, into crystalline bedrock. Several deep channels in the Cretaceous surface in central Suffolk County indicate severe scouring by ice tongues and erosion in meltwater channels that trend both along the ice margin and southward.

The lack of ice-contact erosion on the relatively flat-lying Cretaceous surface in the south half of the island marks the furthest extent of any of the glacial advances.

Island between all Cretaceous and overlying deposits, reflects the glacial scouring and glaciofluvial erosion typical of the high-energy Pleistocene environments.

The well-dissected surface of Cretaceous or older deposits is depicted on sheet 1. The erosion is most severe on the north shore and in Long Island Sound, where glacial processes locally cut through the entire sequence of Cretaceous deposits and, in some areas, into crystalline bedrock. Several deep channels in the Cretaceous surface in central Suffolk County indicate severe scouring by ice tongues and erosion in meltwater channels that trend both along the ice margin and southward.

The lack of ice-contact erosion on the relatively flat-lying Cretaceous surface in the south half of the island marks the furthest extent of any of the glacial advances.

The oldest Pleistocene deposit is the Jameco Gravel (Jameco aquifer), which is present only in western Long Island. It is a channel filling of gravel and coarse sand of Illinoian age and may be the remnant of a high-energy ancestral Hudson River (Soren, 1978). The surface of this unit (sheet 3) probably underwent extensive erosion and reworking by glaciation and fluvial processes during interglacial periods.

The effects of eustatic sea-level changes during the Pleistocene are shown by several lagoonal and shallow-bay clays along southern Long Island. The most prominent of these is the Gardiners Clay (sheet 3), which was probably deposited during Sangamon interglaciation (Soren, 1971).

Subsequent deposition on Long Island, except for small recent deposits, occurred in late Wisconsin glaciation. Long Island's present topography is characterized by the Ronkonkoma and Harbor Hill moraine ridges and a gradually southward sloping outwash plain south of the moraines.

SELECTED REFERENCES

- Buxton, H.T., Soren, Julian, Posner, A., and Shernoff, P.K., 1981, Reconnaissance of the ground-water resources of Kings and Queens Counties, New York: U.S. Geological Survey Open-File Report 81-1186, 59 p.
- Buxton, H.T., and Shernoff, P.K., Ground-water resources of Kings and Queens Counties, New York: U.S. Geological Water-Supply Paper (in press).
- Buxton, H.T., Smolensky, D.A., and Shernoff, P. K., 1989, Hydrogeologic correlations for selected wells on Long Island, New York—A data base and retrieval program: U.S. Geological Survey Water-Resources Investigations Report 86-4318, 107 p.
- Crandell, H.C., Jr., 1962, Geology and ground-water resources of Plum Island, Suffolk County, New York: U.S. Geological Survey Water-Supply Paper 1539-X, 35 p.
- 1963, Geology and ground-water resources of the Town of Southold, Suffolk County, New York: U.S. Geological Survey Water-Supply Paper 1619-GG, 36 p.
- deLaguna, Wallace, 1963, Geology of Brookhaven National Laboratory and vicinity, Suffolk County, New York: U.S. Geological Survey Bulletin 1156-A, 35 p.
- deLaguna, Wallace, and Brashears, M.L., Jr., 1948, The configuration of the rock floor in western Long Island, New York: New York State Water Power and Control Commission Bulletin GW-13, 32 p.
- Doriski, T.P., and Wilde-Katz, Franceska, 1983, Geology of the "20-Foot" clay in southern Nassau and southwestern Suffolk Counties, Long Island, New York: U.S. Geological Survey Water-Resources Investigations Report 82-4056, 17 p.
- Eckhardt, D.A., and Pearsall, K.A., Chlorinated compounds in ground water at Roosevelt Field, Nassau County, Long Island, New York: U.S. Geological Survey Water-Resources Investigations Report (in press).
- Faust, G.T., 1963, Physical properties and mineralogy of selected samples of the sediments from the vicinity of Brookhaven National Laboratory, Long Island, New York: U.S. Geological Survey 1156-B, 34 p.
- Fuller, M.L., 1914, The geology of Long Island, New York: U.S. Geological Survey Professional Paper 82, 231 p.
- Gill, H.E., and Farlekas, G.M., 1976, Geohydrologic maps of the Potomac-Raritan-Magothy aquifer system in the New Jersey Coastal Plain: U.S. Geological Survey Hydrologic Atlas HA-557, 2 sheets, scale 1:500,000.
- Grim, M.S., Drake, C.L., and Heirtzler, J.R., 1970, Sub-bottom study of Long Island Sound: Geological Society of America Bulletin 81, p. 649-666.
- Irbister, John, 1966, Geology and hydrology of northeastern Nassau County, Long Island, New York: U.S. Geological Survey Water-Supply Paper 1825, 89 p.
- Jensen, H.M., and Soren, Julian, 1971, Hydrogeologic data from selected wells and test holes in Suffolk County, Long Island, New York: Long Island Water Resources Bulletin 3, 35 p.
- 1974, Hydrogeology of Suffolk County, Long Island, New York: U.S. Geological Survey Hydrologic Investigation Atlas HA-501, 2 sheets, scale 1:250,000.

- Kilburn, Chabot, 1980, Hydrogeology of the Town of North Hempstead, Nassau County, Long Island, New York: Long Island Water Resources Bulletin 12, 87 p.
- Kilburn, Chabot, and Krulikas, R.K., Hydrogeology and ground-water quality of the northern part of the Town of Oyster Bay, Nassau County, New York, in 1980: U.S. Geological Survey Water-Resources Investigations Report 85-4051, 71 p, (in press).
- Koszalka, E.J., 1980, Hydrogeologic data from the northern part of the Town of Brookhaven, Suffolk County, New York: Suffolk County Water Authority, Long Island Water Resources Bulletin 15, 80 p.
- Krulikas, R.K., 1981, Hydrogeologic data from selected wells and test holes in Suffolk County, Long Island, New York, 1972-80: U.S. Geological Survey Open-File Report 81-500, 27 p.
- Krulikas, R.K., Koszalka, E.J., and Doriski, T.P., 1983, Altitude of the top of the Matawan Group-Magothy Formation, Suffolk County, Long Island, New York: U.S. Geological Survey Open-File Report 83-137, 1 sheet.
- Ku, H.F.H., Vecchioli, John, and Cerrillo, L.A., 1975, Hydrogeology along the proposed barrier-recharge-well alignment in southern Nassau County, Long Island, New York: U.S. Geological Survey Hydrologic Investigation Atlas HA-502, 1 sheet, scale 1:96,000.
- Leggette, R.M., 1938a, Record of wells in Nassau County, New York: New York State Water Power and Control Commission Bulletin GW-5, 140 p.
- 1938b, Record of wells in Suffolk County, New York: New York State Water Power and Control Commission Bulletin GW-4, 108 p.
- Lubke, E.R., 1964, Hydrogeology of the Huntington-Smithtown area, Suffolk County, New York, in U.S. Geological Survey Water-Supply Paper 1669-D, p. D1-D68.
- MacClintock, Paul, and Richards, H.R., 1936, Correlation of late Pleistocene marine and glacial deposits of New Jersey and New York: Geological Society of America Bulletin, v. 47, no. 3, p. 289-338.
- McClymonds, N.E., and Franke, O.L., 1972, Water-transmitting properties of aquifers on Long Island, New York: U.S. Geological Survey Professional Paper 627-E, p. E1-E24, 24 p.
- McMaster, R.L., and Ashraf, Asaf, 1973, Sub-bottom basement drainage system of inner continental shelf off southern New England: Geological Society of America Bulletin, v. 84, p. 187-190.
- 1973, Extent and formation of deeply buried channels on the continental shelf off southern New England: Journal of Geology, v. 81, p. 374-379.
- 1973, Drowned and buried valleys on the southern New England continental shelf: Marine Geology, v. 15, no. 249-268.
- Minard, J.P., 1969, Geology of the Sandy Hook Quadrangle in Monmouth County, New Jersey: U.S. Geological Survey Bulletin 1276, 43 p.
- Nemickas, Bronius, and Koszalka, E.J., 1982, Geohydrologic appraisal of the water resources of the South Fork, Long Island, New York: U.S. Geological Survey Water-Supply Paper 2073, 55 p.
- Oliver, J.E., and Drake, C.L., 1951, Geophysical investigations in the emerged and submerged Atlantic coastal plain, part IV—the Long Island area: Geological Society of America Bulletin, v. 62, p. 1278-1296.
- Perlmutter, N.M., and Todd, Ruth, 1965, Correlation and foraminifera of the Monmouth Group (Upper Cretaceous), Long Island, New York: U.S. Geological Survey Professional Paper 483-I, 24 p.
- Perlmutter, N.M., and Geraghty, J.J., 1963, Geology and ground-water conditions in southern Nassau and southeastern Queens Counties, Long Island, New York: U.S. Geological Survey Water-Supply Paper 1613-A, p. A1-A205.
- Prince, K.R., 1986, Ground-water assessment of the Montauk area, Long Island, New York: U.S. Geological Survey Water-Resources Investigations Report 85-4013, 103 p.
- Sirkin, L.A., 1968, Geology, geomorphology, and late-glacial environments of western Long Island, New York, in Finks, R.M. (ed.), Guidebook to field excursions, New York State Geological Association, 40th Annual meeting: p. 233-253.
- 1974, Palynology and stratigraphy of Cretaceous strata in Long Island, New York, and Block Island, Rhode Island: U.S. Geological Survey Journal of Research, v. 2, p. 431-446.
- 1976, Block Island, Rhode Island—evidence of fluctuation of the late Pleistocene ice margin: Geological Society of America Bulletin, v. 87, p. 574-580.

- Sirkin, L.A., and Stuckenrath, R., 1980. The Portwashingtonian warm interval in the northern Atlantic Coastal Plain: Geological society of America Bulletin, part 1, v. 91, p. 332-336.
- Soren, Julian, 1971. Results of subsurface exploration in the mid-island area of western Suffolk County, Long Island, New York: Long Island Water Resources Bulletin 1, 60 p.
- 1978. Hydrogeologic conditions in the Town of Shelter Island, Suffolk County, Long Island, New York: U.S. Geological Survey Water-Resources Investigations 77-77, 22 p.
- Suter, Russell, deLaguna, Wallace, and Perlmutter, N.M., 1949. Mapping of geologic formations and aquifers of Long Island: New York State Water Power and Control Commission Bulletin GW-18, 212 p.
- Upson, J.E., 1970. The Gardiners Clay of eastern Long Island, New York—a reexamination, U.S. Geological Survey Professional Paper 700-B, p. 157-160.
- U.S. Geological Survey, 1967. Engineering geology of the northeast corridor, Washington D.C. to Boston, Massachusetts, coastal plain and surficial geology: U.S. Geological Survey Miscellaneous Geologic Investigations 514, 8 sheets.
- Veatch, A.C., Slichter, C.S., Bowman, Isiah, Crosby, W.O., and Horton, R.E., 1906. Underground water resources of Long Island, New York: U.S. Geological Survey Professional Paper 44, 394 p.
- Warren, M.A., deLaguna, Wallace, and Lusczynski, N.J., 1968. Hydrology of Brookhaven National Laboratory and vicinity, Suffolk County, New York: U.S. Geological Survey Bulletin 1156-C, 127 p.
- Williams, S.J., 1976. Sediments and shallow structure of the Long Island Atlantic inner continental shelf: U.S. Army Corps of Engineers, Coastal Engineering Research Center, Fort Belvoir, Va., technical paper 76-2, 123 p.
- 1981. Sand resources and geological character of Long Island Sound: U.S. Army Corps of Engineers, Coastal Engineering Research Center, Fort Belvoir, Va., Technical Paper 81-3.
- Zapczka, O.S., 1984. Hydrogeologic framework of the New Jersey coastal plain: U.S. Geological Survey Open-file Report 84-730, 61 p.


Table 1.—Hydrogeologic units of Long Island and their water bearing properties
[ft/d, feet per day; ft, feet]


| System | Series | Geologic unit | Hydrogeologic unit | Approximate maximum thickness (ft) | Character of deposits | Water bearing properties |
|------------|-------------|------------------------------------------------------------------------------------|-----------------------|------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Quaternary | Holocene | Recent deposits: Salt marsh deposits, stream alluvium, shoreline deposits and fill | Recent deposits | 50 | Sand, gravel, clay, silt, organic mud, peat, loam, and shells. Colors are gray, brown, green, black, and yellow. | Beach deposits are highly permeable; marsh deposits poorly permeable. Locally hydraulically connected to underlying aquifers. |
| | Pleistocene | Upper Pleistocene deposits | Upper glacial aquifer | 700 | Till composed of clay, sand, gravel, and boulders, forms Harbor Hill and Ronkonkoma terminal moraines. Outwash deposits consist of quartzose sand, fine to very coarse, and gravel, pebble to boulder sized. Also contains lacustrine, marine, and reworked deposits. Local units are Port Washington aquifer and confining unit, "20-foot clay," and clay at Smithtown. | Till is poorly permeable. Outwash deposits are moderately to highly permeable. Glaciolacustrine and marine clay deposits are mostly poorly permeable but locally have thin, moderately permeable layers of sand and gravel. Average horizontal hydraulic conductivity is approximately 270 ft/d; conductivity of morainal material is approximately 50 percent of outwash deposits; anisotropy is approximately 10:1. |
| | | unconformity | | | | |
| | | Gardiners Clay | Gardiners Clay | 150 | Clay, silt, and few layers of sand. Colors are grayish green and brown. Contains marine shells and glauconite. | Poorly permeable; constitutes a confining layer for underlying aquifer. Some sand lenses may be permeable. Average vertical hydraulic conductivity is approximately 0.001 ft/d. |
| | | unconformity | | | | |
| | | Jameco Gravel | Jameco aquifer | 200 | Sand, fine to very coarse, and gravel to large-pebble size; few layers of clay and silt. Gravel is composed of crystalline and sedimentary rocks. Color is mostly brown. | Moderately to highly permeable. Confined by overlying Gardiners clay. Average horizontal hydraulic conductivity is 200 to 300 ft/d; anisotropy is approximately 10:1. |
| | | Monmouth Group | Monmouth greensand | 200 | Interbedded marine deposits of clay, silt, and sand, dark-greenish gray, greenish-black, greenish, dark-gray, and black, containing much glauconite. | Poorly permeable; primarily a confining unit for underlying Magothy aquifer. Average vertical hydraulic conductivity is approximately 0.001 ft/d. |
| | | unconformity | | | Sand, fine to medium clayey in part; | Most layers are poorly to moderately |

| | | | | | | |
|---------------------------|-------------|-----------------------------------------------------|------------------------|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | | | | | Smithtown. | of outwash deposits; anisotropy is approximately 10:1. |
| | Pleistocene | unconformity | | | | |
| | | Gardiners Clay | Gardiners Clay | 150 | Clay, silt, and few layers of sand. Colors are grayish green and brown. Contains marine shells and glauconite. | Poorly permeable; constitutes a confining layer for underlying aquifer. Some sand lenses may be permeable. Average vertical hydraulic conductivity is approximately 0.001 ft/d. |
| | | unconformity | | | | |
| | | Jameco Gravel | Jameco aquifer | 200 | Sand, fine to very coarse, and gravel to large-pebble size; few layers of clay and silt. Gravel is composed of crystalline and sedimentary rocks. Color is mostly brown. | Moderately to highly permeable. Confined by overlying Gardiners clay. Average horizontal hydraulic conductivity is 200 to 300 ft/d; anisotropy is approximately 10:1. |
| | | unconformity | | | | |
| | | Monmouth Group | Monmouth greensand | 200 | Interbedded marine deposits of clay, silt, and sand, dark-greenish gray, greenish-black, greenish, dark-gray, and black, containing much glauconite. | Poorly permeable; primarily a confining unit for underlying Magothy aquifer. Average vertical hydraulic conductivity is approximately 0.001 ft/d. |
| | | unconformity | | | | |
| | | Matawan Group - Magothy Formation, undifferentiated | Magothy aquifer | 1,100 | Sand, fine to medium clayey in part; interbedded with lenses and layers of coarse sand and sandy and solid clay. Gravel is common in basal zone. Sand and gravel are quartzose. Lignite, pyrite, and iron oxide concretions are common. Colors are gray, white, red, brown, and yellow. | Most layers are poorly to moderately permeable; some are highly permeable locally. Water is unconfined in uppermost parts, elsewhere is confined. Constitutes principal aquifer for public supply. Average horizontal hydraulic conductivity is 50 ft/d; anisotropy is approximately 100:1. |
| | | unconformity | | | | |
| | | Unnamed clay member | Raritan confining unit | 200 | Clay, solid and silty; few lenses and layers of sand. Lignite and pyrite are common. Colors are gray, red, and white, commonly variegated. | Poorly to very poorly permeable; constitutes confining layer for underlying Lloyd aquifer. Average vertical hydraulic conductivity is approximately 0.001 ft/d. |
| | | Raritan Formation | | | | |
| | | Lloyd Sand Member | Lloyd aquifer | 500 | Sand, fine to coarse, and gravel, commonly with clayey matrix; some lenses and layers of solid and silty clay; locally contains thin lignite layers. Sand and most of gravel are quartzose. Colors are yellow, gray, and white; clay is red locally. | Poorly to moderately permeable. Water is confined by overlying Raritan clay. Average horizontal hydraulic conductivity is 40 ft/d; anisotropy is approximately 10:1. |
| | | | | | | |
| Paleozoic and Precambrian | | Bedrock | Bedrock | | Crystalline metamorphic and igneous rocks; muscovite-biotite schist, gneiss, and granite. A soft, clayey zone of weathered bedrock locally is more than 70 ft thick. | Poorly permeable to virtually impermeable; constitutes lower boundary of ground-water reservoir. Some hard fresh water is contained in joints and fractures but is impractical to develop at most places. |

ALTITUDE OF THE UPPER SURFACE OF SUBCROPS OF CRETACEOUS DEPOSITS AND BEDROCK BENEATH THE UPPER GLACIAL AQUIFER, LONG ISLAND, NEW YORK

EXPLANATION





ALTITUDE OF THE UPPER SURFACE OF CRE

ALTITUDE OF THE UPPER SURFACE OF THE RARITAN CONFINING UNIT, LONG ISLAND, NEW YORK

EXPLANATION





SHADING INDICATES LOCATION OF SUBCROP OF THE
RARITAN CONFINING UNIT

— — — UPDIP LIMIT OF THE RARITAN CONFINING UNIT

—o— — STRUCTURE CONTOUR—Shows the upper surface of the
Raritan confining unit. Dashed where approximately lo-
cated. Contour interval 100 feet. National Geodetic Verti-
cal Datum of 1929

Scale 1:250,000





ALTITUDE OF THE UPPER SURFACE OF THE RARITAN CONFINING UNIT

ALTITUDE OF THE UPPER SURFACE OF THE MAGOTHY AQUIFER, LONG ISLAND, NEW YORK

EXPLANATION





SHADING INDICATES LOCATION OF SUBCROP OF THE
MAGOTHY AQUIFER

—— ——— UPDIP LIMIT OF THE MAGOTHY AQUIFER

—— 0 —— STRUCTURE CONTOUR—Shows the upper surface of the
Magothy aquifer. Dashed where approximately located.
Contour interval 50 and 100 feet. National Geodetic Verti-
cal Datum of 1929

Scale 1:250,000





ALTITUDE OF THE UPPER SURFACE OF THE MAGOTHY AQUIFER

REFERENCE NO. 13



PROJECT NOTE

TO: Commercial Envelope Mfg. Co., Inc. file DATE: 24 June 1994
FROM: D. D. Minsavage W.O. NO.: 04200-022-081-00016-02
SUBJECT: Well head protection areas located within 4 miles of the site.

The NYSDEC / Division of Water designated the following areas as well head protection areas on Long Island:

- The deep flow recharge area of the Magothy and Lloyd aquifers
- fixed variable shape zone: radius of 1,500 feet upgradient and radius of 500 feet downgradient of any public water supply well drawing from the Glacial aquifer.

[See Attachment A]


The NYSDEC well head protection area plan has been accepted by the U.S. EPA [See Attachment B]

Review of available background information does not indicate the presence of a deep flow Recharge area of either the Magothy, or Lloyd aquifer within 4 miles of the site [See Attachment C]

Suffolk County Water Authority and Dix Hills Water District operate potable water wells, drawing from the Glacial aquifer within 4 miles of the site; however, none of the "Glacial" wells is located within 1 mile of the site. Therefore, the site does not overlie a wellhead protection area. [See "Potable water sources" Project Note]

Department of Environmental Conservation

PROPOSED NEW YORK STATE WELLHEAD PROTECTION PROGRAM



Submittal

to

United States Environmental Protection Agency

New York State Department of Environmental Conservation

MARIO M. CUOMO, Governor

THOMAS C. JORLING, Commissioner

May 1990

Approved by EPA

**PROPOSED
NEW YORK STATE
WELLHEAD PROTECTION PROGRAM**

**SUBMITTAL
TO
UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
IN
APPLICATION FOR IMPLEMENTATION FUNDS**

**NEW YORK STATE
DEPARTMENT OF ENVIRONMENTAL CONSERVATION
DIVISION OF WATER
ALBANY, NY**

MAY 1990

with the overall wellhead protection objectives if they unduly diminish funds available for management program implementation or if the management program does not require great sophistication. Increased refinements of delineations are justifiable to the extent that corresponding refinements in management and enforcement are practical and possible.

1.4. Wellhead Protection Program Summary

This summary is an overview of material developed in more detail in Chapters 2 through 8.

1.4.1. Agency Responsibilities

The Department of Environmental Conservation (DEC) is the principal agency responsible for developing and implementing state-level aspects of the Wellhead Protection Program and for coordination. The Department of Health (DOH) is responsible for certain aspects related to public water supply well data, contingency planning, new well planning, and Watershed Rules and Regulations. Regional and county planning agencies and county governments are responsible for county-level planning, management and educational outreach elements in the overall program, in addition to any county-level ordinances developed for wellhead protection. Town, village and city governments are responsible for local land use control, local ordinances and other local-level aspects of wellhead protection. Water suppliers will have a role in developing local Watershed Rules and Regulations, education, land acquisition and other program aspects determined by DEC and DOH. The educational effort will be shared by all levels, including Cooperative Extension, the universities and the State Education Department. Federal agencies and other state agencies will participate as appropriate, as coordinated by DEC with the assistance of EPA for federal agencies.

1.4.2. Wellhead Protection Area Delineation

The Safe Drinking Water Act defines a Wellhead Protection Area (WHPA) as "the surface and subsurface area surrounding a water well or wellfield, supplying a public water system, through which contaminants are reasonably likely to move toward and reach such water well or wellfields." This definition is not specific because there is no

time framework and because there is a requirement that contaminants be reasonably likely to reach the well, a condition that is very difficult to accurately predict. States are given flexibility by the Safe Drinking Water Act in determining delineation approaches. ...

New York State proposes that unconsolidated aquifer boundaries serve as the fundamental delineation of wellhead protection areas and that a multiple zone approach be used within the total WHPA for varying management relative to risk. This approach is modified for Long Island and for bedrock aquifers, as described in Chapter 3. New York's approach proposes to allow local flexibility in an evolutionary process of delineation refinements, and to allow utilization of previously delineated protection areas, where appropriate.

There are many distinct advantages in this overall approach. A very important advantage is that considerable aquifer characterization and mapping work has already been accomplished. Second, it is consistent with the evolution and principal policies of both the comprehensive New York State Groundwater Management Program (1987) and New York State Water Resources Management Strategy (1989), in addition to the New York State Watershed Rules and Regulation policies. Third, it focuses attention of local governments on the entire aquifer resource and facilitates contingency planning and new (or future) well protection. Finally, it provides a base within which more sophisticated delineations (e.g., subdividing the overall WHPA) can be made as programs require and funding permits.

A possible drawback of using aquifer boundaries—that aquifers may be broad regional systems—is not a major problem in most of New York State. In Upstate New York most public water supplies using groundwater are in unconsolidated aquifers of rather limited areal extent. Most important recharge areas are within the boundaries of the unconsolidated aquifers, another advantage of this approach.

Chapter 3 provides further details and background on wellhead protection area delineation.

CHAPTER 3

WELLHEAD PROTECTION AREA DELINEATION

3.1. Introduction and Institutional Processes

3.1.1. Introduction

The comprehensive New York State Groundwater Management Program, developed in the early 1980's and published in revised and final documents in 1986 (for Long Island) and 1987 (for Upstate), recommended key policies and program initiatives endorsing geographic targeting and critical area protection. These concepts were forerunners of the Safe Drinking Water Act's Wellhead Protection Program. Significant progress has been made in different aspects of geographic targeting of programs and in different parts of New York State. New York acknowledges these accomplishments as an integral part of its overall Wellhead Protection Program.

Delineation determines geographic areas for which different levels of groundwater protection activities are to be instituted. The Wellhead Protection Program in New York State is intended to accomplish a wider recognition of targeting objectives by all levels of government, by citizens in general, and to begin an evolutionary process toward improved targeting and protective program implementation.

The basic wellhead protection delineation approach in New York State recognizes aquifers as the fundamental geographic unit for targeting management efforts. This approach must be modified where aquifers are broad regional systems (DEC considers this case to occur only on Long Island), or where aquifers are not well characterized (considered to be the case for bedrock aquifers, in general). Elsewhere, the unconsolidated aquifers of New York tend to be of limited areal extent and they generally include the important recharge areas within their boundaries. These unconsolidated aquifers also are the source of the large majority of groundwater-derived public water supply systems.

The New York State Wellhead Protection Program proposes that unconsolidated aquifer boundaries (the land surface overlying the aquifer) serve as the baseline definition for the overall wellhead protection area (WHPA). For the baseline definition, both confined and unconfined unconsolidated aquifers are grouped together. Revisions are allowable based on site-specific evaluations. This aquifer boundary approach is proposed to be modified on Long Island and for wells in bedrock aquifers as described in Section 3.2. For all public water supply wells, specific proposed WHPA delineation policies are described in Section 3.2.

The aquifer boundary approach for the overall WHPA has several distinct advantages. It takes advantage of considerable recent and ongoing work in mapping and detailed assessments of aquifer boundaries. Incorporating this work directly into the Wellhead Protection Program provides a practical way for more effective targeting to move forward rapidly rather than being constrained by the need to perform modeling to delineate protection areas.

The aquifer approach also encompasses other non-public wells and potential future well sites, and places major focus on the high-yielding groundwater resources which are most important and most vulnerable. This last aspect is considered very important in the education component of wellhead protection, both for local officials and for the general public.

Wellhead protection area delineation is an evolutionary process. The first need for refinement is the further subdivision of the total wellhead protection area, as required for differentiated management objectives. A second area for potential refinement is delineation of the overall WHPA in the Glacial Aquifer on Long Island and in bedrock aquifers. Issues related to these topics are reviewed in both Sections 3.2 and 3.3. Flexibility for refinement or revision is very important due to the wide variability in

TABLE 3.1.
WELLHEAD PROTECTION AREA
DELINEATION SUMMARY

| Geographic Region | Aquifer Area | Wellhead Protection Area Baseline Delineation |
|-------------------|-------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------|
| Long Island | Magothy & Lloyd Aquifers Glacial Aquifer | Deep Flow Recharge Area Simplified Variable Shape: 1,500 ft. radius upgradient 500 ft. radius downgradient |
| Upstate | Unconsolidated Aquifers Bedrock Aquifers | Aquifer Boundaries (land surface) Fixed Radius: 1,500 ft. radius |

"Potential Yields of Wells in Unconsolidated Aquifers in Upstate New York" by the U.S. Geological Survey. Specifically, these maps, distributed for sale by the U.S. Geological Survey, are as follows:

1. Bugliosi, E.F., et al., 1988. Potential Yields of Wells in Unconsolidated Aquifers in Upstate New York - Lower Hudson Sheet. Water Resources Investigations Report 87-4274. U.S. Department of the Interior, Geological Survey, Albany, NY.
2. Bugliosi, E.F., et al., 1988. Potential Yields of Wells in Unconsolidated Aquifers in Upstate New York - Hudson Mohawk Sheet. Water Resources Investigations Report 87-4275. U.S. Department of the Interior, Geological Survey, Albany, NY.
3. Bugliosi, E.F., et al., 1988. Potential Yields of Wells in Unconsolidated Aquifers in Upstate New York - Adirondack Sheet. Water Resources Investigations Report 87-4276. U.S. Department of the Interior, Geological Survey, Albany, NY.
4. Miller, T.S., 1988. Unconsolidated Aquifers in Upstate New York - Finger Lakes Sheet. Water Resources Investigations Report 87-4122. U.S. Department of the Interior, Geological Survey, Albany, NY.
5. Miller, T.S., 1988. Potential Yields of Wells in Unconsolidated Aquifers in Upstate New York - Niagara Sheet. Water Resources Investigations Report 88-4078. U.S. Department of the Interior, Geological Survey, Albany, NY.

The boundaries illustrated on these maps serve as the total wellhead protection areas for public water supplies utilizing those aquifers. In certain cases, more detailed aquifer boundary maps or determinations for primary or principal aquifers (subsets of the full range of unconsolidated aquifers) have been or will be made by the U.S. Geological Survey or NYS Department of Environmental Conservation. These more detailed boundary determinations will generally supersede boundaries illustrated on the above referenced

maps as "revised" delineations of wellhead protection areas.

Both unconfined and confined unconsolidated aquifers are included on these maps and both are included in this definition of the overall wellhead protection area.

For all public water supplies utilizing groundwater, the overall wellhead protection area (WHPA) delineation will be subdivided into two parts. The innermost zone is referred to as the Remedial Action Area. The remainder of the WHPA is referred to as the Wellfield Management Area. The terminology is derived from the EPA guidance referenced earlier. Depending on local management objectives for groundwater protection, local hydrogeology, and data availability and resource availability, the Wellfield Management Area may be further subdivided. This further subdivision of the Wellfield Management Area would be considered a refinement of the "baseline" delineation. Methodologies, criteria and thresholds used for such revisions are flexible. Approaches proposed by local water purveyors will be evaluated and approved or disapproved upon submittal to the New York State Department of Environmental Conservation.

The term "baseline" delineation, as used in this submittal, is intended to represent the initial WHPA delineation advocated by the Department of Environmental Conservation. The delineation may be directly utilized in implementing management activities for groundwater protection. However, if site-specific conditions suggest that alternative delineations are appropriate (including the further subdivision of the Wellfield Management Area already cited), those delineations may be accepted by the Department of Environmental Conservation. The evolution of improved delineation techniques, the growing availability of hydrogeologic information, and the longer-term enhancements of groundwater protection programs may lead to a redefinition of the baseline delineations by the Department of Environmental Conservation.

These baseline delineations apply to public water supply wells. Applicants for new public water supply wells may be required to perform

alternative site-specific delineations according to conditions stipulated through the Water Supply Permit Program (refer to Chapter 7).

The proposed WHPA delineations are described according to the following geographic and hydrogeologic settings. They are also summarized in Table 3.1.

• Unconsolidated Aquifers - Upstate New York

1. WHPA Definition:

The boundaries of wellhead protection areas for public water supplies in unconsolidated aquifers in Upstate New York are the land surface boundaries of the aquifers as illustrated on the five-aquifer sheet maps for Upstate published and distributed by the U.S. Geological Survey (see earlier reference). These boundaries may be revised in accordance with more detailed primary and principal aquifer maps and boundary determinations as approved by the Department of Environmental Conservation. The maps provide definition for both unconfined and confined aquifers. Revisions of these boundaries may be made, pending approval by the Department of Environmental Conservation.

2. Rationale:

The delineations proposed above are hydrogeologically-based and are consistent with the policies and goals of the Upstate Groundwater Management Program already adopted and certified by the Governor of New York as an element of the New York State Water Quality Management Plan.

3. Mapping and Case Studies:

Mapping of these areas is already completed and published. Case studies are not considered appropriate, as the maps have been reviewed and approved by the U.S. Geological Survey and the Department of Environmental Conservation as part of the publication process.

4. Public Water Supply Significance:

The large majority of public water supplies using groundwater, particularly for municipal and community systems, are located in unconsolidated aquifers. It is expected that a significant proportion of additional future supplies will also tap these systems.

• Bedrock Aquifers - Upstate New York

1. WHPA Definition:

The baseline boundaries of wellhead protection areas for public water supplies in bedrock aquifers are fixed radius areas with a radius of 1,500 feet from the wellhead. Revisions based on site-specific information are desirable, with the goals being to identify and delineate principal recharge areas. Revisions may be developed, pending approval by the Department of Environmental Conservation.

2. Rationale:

The fixed radius approach for the initial WHPA is not based on estimated times-of-travel or drawdown. It provides a substantial increase in protection over more commonly existing protection zones (typically 100 feet or 200 feet). The principal rationale is that the baseline delineation gives a basis for immediate action on wellfield management without requiring expensive site-specific delineations. Revisions based on local conditions are encouraged, particularly for municipal community systems, of which there are relatively few in the State. The geographic targeting benefits of uniformly delineating substantially larger fixed radius areas for all bedrock wells are very questionable. Many of the bedrock public water supply wells are among the approximately 10,000 non-community public wells (e.g., isolated public buildings, roadside rest areas, etc.). There will be little geographic targeting advantage for groundwater protection programs if

numerous 3 to 12 square mile WHPA's (1-2 mile radius) for non-community wells intersect or nearly intersect across the State. It must be recognized that all fresh groundwaters in bedrock aquifers are classified as GA groundwaters and thus are already protected by substantial statewide protection programs which use rigorous ambient water quality standards in their design.

3. Mapping and Case Studies:

Mapping will be performed according to the phasing priorities described in Section 3.3. Case studies of fixed radius approaches are not considered to be of significant benefit. As proposals for revisions based on alternative approaches are submitted to the Department of Environmental Conservation, they will be evaluated for potential use as models for comparable hydrogeologic conditions.

4. Public Water Supply Significance:

Relatively few municipal community systems utilize bedrock aquifers in New York State and those that do are generally with low population dependence. Public water supplies in bedrock aquifers are typically non-community wells serving small numbers of people.

• Magothy and Lloyd Aquifers - Long Island

1. WHPA Definition:

The boundaries of the wellhead protection area for public water supplies using the Magothy and Lloyd aquifers are the boundaries of the Deep Flow Recharge Area as recognized by the Department of Environmental Conservation. Refinements within the overall WHPA may include further definition of Wellfield Management Areas, pending approval by the Department of Environmental Conservation.

— 2. Rationale:

The Deep Flow Recharge Area was determined to be the most important overall groundwater protection area for wells in the Magothy and Lloyd aquifers in the Long Island Groundwater Management Program already adopted and certified by the Governor of New York as an element of the New York State Water Quality Management Program. The delineations have also been adopted in the Suffolk County Sanitary Code.

3. Mapping and Case Studies:

Mapping of the Deep Flow Recharge Area is already completed. Additional case studies are not considered appropriate.

4. Public Water Supply Significance:

Most public water in Nassau County is withdrawn from the Magothy aquifer. The majority of public water supplies in Suffolk County are also withdrawn from the Magothy aquifer. Of those public water supplies in Suffolk County utilizing the Glacial aquifer, approximately half are located within the Deep Flow Recharge Area. Thus, these wells are included within the overall wellhead protection area for the deeper aquifers.

• Glacial Aquifer - Long Island

1. WHPA Definition:

The boundaries of the wellhead protection area for public water supplies using the Glacial aquifer are defined as a fixed variable shape zone with a fixed radius in the upgradient groundwater flow direction of 1,500 feet and a fixed radius in the downgradient direction of 500 feet. Revisions may be made, pending approval by the Department of Environmental Conservation.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION II
26 FEDERAL PLAZA
NEW YORK, NEW YORK 10278

SEP 27 1990

Honorable Mario M. Cuomo
Governor of the State of
New York
State Capitol
Executive Chamber
Albany, New York 12224

Dear Governor Cuomo:

In response to a letter from former EPA Administrator, Lee Thomas, you designated the New York State Department of Environmental Conservation (DEC) as the lead State agency for the development and implementation of New York's Wellhead Protection Program under Section 1428 of the Safe Drinking Water Act Amendments of 1986 (SDWA).

In accordance with the SDWA, the DEC submitted a draft Wellhead Protection (WHP) Program document to EPA, Region II, on June 19, 1989. Under Section 1428 of the SDWA, EPA must evaluate each State's Program document to determine whether the Program is fully adequate to protect public water supply systems from contaminants that may have an adverse effect on the public's health.

EPA Region II reviewed DEC's June 1989 submittal and subsequent addenda that were received over the next few weeks. Comments were sent to the State, and DEC revised its plan to address comments from EPA and the public. The revised documents, received in September 1990, responded to all comments sufficiently. Therefore, I am pleased to inform you that the New York Wellhead Protection Program document adequately addresses the requirements of Section 1428 of the Safe Drinking Water Act and the program is fully approved.


The level of activity and sense of commitment to Wellhead Protection on the part of New York State is impressive, especially considering the delays associated with Congressional appropriations for the WHP Program. It is a great credit to the Department of Environmental Conservation, and in particular to the staff of the Division of Water, to have successfully completed the Wellhead Protection Program document. New York State is one of twenty-seven states nationwide to have submitted a WHP Program document within the time frame specified by the SDWA and is one of the first states to receive EPA approval of its program. We recognize your continual efforts to improve upon the program, as reflected in the current revisions to New York's Wellhead Protection Program document.

New York has made major strides in ground water protection over the years, particularly with respect to the development of the State's Upstate and Long Island Ground Water Management Programs, the Nonpoint Source Management Program, and the Water Resources Management Strategy. The State has established itself as a national leader in ground water protection, and EPA looks forward to further advances in this area.

EPA continues to support New York State in the implementation of the Wellhead Protection Program. Federal funding is presently available under Section 106 of the Clean Water Act to support the Department of Environmental Conservation with this new program. Our Ground Water Management Section staff will assist DEC in preparing a WHP implementation workplan for the use of these funds in the coming fiscal year.

Again, congratulations on the accomplishments of your staff.

Sincerely,


Constantina Sidamon-Eristoff
Regional Administrator

cc: Thomas Jorling, NYSDEC
Sal Pagano, NYSDEC
Phil DeGaetano, NYSDEC
Al Tedrow, NYSDEC
Kevin Roberts, NYSDEC

Loan Copy

ATTACHMENT C

UNITED STATES DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

POTENTIOMETRIC-SURFACE ALTITUDE OF MAJOR AQUIFERS ON LONG ISLAND, NEW YORK, IN 1983

By
Thomas P. Doriski



WATER-RESOURCES INVESTIGATIONS REPORT 85-4321

Plate 1. Water-table altitude

Plate 3. Potentiometric surface of Magothy aquifer

Plate 2. Water-table well numbers

Plate 4. Potentiometric surface of Lloyd aquifer

Prepared in cooperation with the
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
SUFFOLK COUNTY DEPARTMENT OF HEALTH SERVICES
SUFFOLK COUNTY WATER AUTHORITY

Syosset, New York

1986

POTENTIOMETRIC SURFACE OF THE MAGOTHY AQUIFER, LONG ISLAND, NEW YORK, IN MARCH 1983

The Magothy aquifer of the Cretaceous Magothy Formation and overlying Matawan Group undifferentiated supplies water for public supply and industrial use in Nassau and Suffolk Counties. The potentiometric-surface altitude is monitored by the U.S. Geological Survey. This map depicts the static water-level measurements taken in March 1983 in observation wells and public-supply wells screened in the Magothy aquifer.

The measurements show the potentiometric-surface altitude to range from 9.8 ft below sea level in eastern Queens County to 83.5 ft above sea level in central Nassau County (sheet 1). The general shape of the potentiometric surface is similar to that of the overlying upper glacial (water-table) aquifer, rising gradually from a depression in the western part of the island to an east-west mound in the central part. In areas where deep channels have been eroded into the Magothy aquifer and filled with glacial deposits, the potentiometric-surface contours were drawn from water levels measured in wells screened deep in these glacial deposits, which are laterally contiguous and hydraulically connected with the Magothy aquifer.

The potentiometric-surface altitude is, in general, 1 to 7 ft lower than in 1979 (Donaldson and Koszalka, 1983), except in central Queens County, where water levels in the depression area have recovered from 28 ft below sea level in 1979 to 10 ft below sea level.

On the north and south forks of eastern Suffolk County (sheet 2), water in the Magothy aquifer is saline except in the central part of the south fork (Nemickas and Koszalka, 1982). The northern limit of the Magothy aquifer in Kings and Queens Counties as depicted here has been revised in accordance with data of Buxton and others (1981); its northern limit in Nassau County has been revised according to Kilburn (1979) and Kilburn and Krulik (1985).

Most wells shown on this map were measured in March 1983. In comparing the water levels in the Magothy aquifer with the water table (plate 1), also measured in March 1983, the user should verify that the wells in each aquifer were measured at approximately the same time of the month to account for differences due to precipitation. Information on the date and time of water-level measurements is available at the U.S. Geological Survey in Syosset, N.Y.

This work was done in cooperation with the Nassau County Department of Public Works, Suffolk County Department of Health Services, Suffolk County Water Authority, and the New York State Department of Environmental Conservation. Special thanks are extended to the water companies and private industries on Long Island who cooperated in the static water-level measurements.

Alex, and
sance of the
and Queens
cal Survey

1983, Potentio-
nifer, Long
U.S. Geological
2 sheets.


the Town of
Long Island, New
s Bulletin 12,

Hydrogeology and
ern part of the
y, New York, in
ter-Resources
press).

., 1982, Geohydro-
s of the South
. Geological

POTENTIOMETRIC SURFACE OF THE MAGOTHY AQUIFER, LONG ISLAND, NEW YORK, MARCH 1983

WATER-RESOURCES INVESTIGATIONS REPORT 85-432
PLATE 3A--MAGOTHY AQUIFER--WES



POTENTIOMETRIC SURFACE OF THE LLOYD AQUIFER, LONG ISLAND, NEW YORK, IN JANUARY 1983

The Lloyd aquifer, in the Cretaceous Lloyd Sand Member of the Raritan Formation, is a significant source of water for public supply and a minor source for industrial use in Queens and Nassau Counties. The potentiometric surface is monitored by the U.S. Geological Survey. This map depicts static water levels of January 1983 in 72 wells screened in the Lloyd aquifer and Port Washington aquifer. (Wells screened in the Port Washington aquifer, in northern Nassau County, are included because the Port Washington aquifer seems to be hydraulically connected to the Lloyd aquifer. See Kilburn, 1979, and Kilburn and Krulikas, 1985, for the stratigraphic relationship of the two aquifers.) The northern limit of the Lloyd, and the extent of the Port Washington aquifer and the aquifer in which each well is screened, are indicated.

General trends of the potentiometric surface are similar to those in the two major overlying aquifers (plates 1 and 3); it gradually rises from a depression in the western part of the island to an east-west-trending mound in the central part. The potentiometric-surface altitude ranges from 26.8 ft below sea level in central Queens County to 39.6 ft above sea level in north-central Suffolk County.

The potentiometric-surface altitude of the Lloyd aquifer is, in general, 1 to 3 ft lower than in 1979 (Donaldson and Koszalka, 1983) except in northeastern Nassau County, where water levels are slightly higher than in 1979. The depression in Queens County is slightly larger than in 1979 and extends into western Nassau County.

In eastern Suffolk County, the Lloyd aquifer is saline and has no observation wells. The northern limit of the Lloyd aquifer in Kings and Queens Counties has been revised in accordance with data of Buxton and others (1981); the limits of the Lloyd and Port Washington aquifers in Nassau County have been revised according to Kilburn (1979) and Kilburn and Krulikas (1985).


This study was done in cooperation with the Nassau County Department of Public Works, Suffolk County Department of Health Services, Suffolk County Water Authority, and the New York State Department of Environmental Conservation. Special thanks are extended to the water companies and private industries on Long Island who cooperated in the static water-level measurements.

REFERENCES CITED

- Buxton, H. T., Soren, Julian, Posner, Alex, and Shernoff, P. K., 1981, Reconnaissance of the ground-water resources of Kings and Queens Counties, New York: U.S. Geological Survey Open-File Report 81-1186, 59 p.
- Donaldson, C. D., and Koszalka, E. J., 1983, Potentiometric surface of the Lloyd aquifer, Long Island, New York, in January 1979: U.S. Geological Survey Open-File Report 82-160, 2 sheets.
- Kilburn, Chabot, 1979, Hydrogeology of the Town of North Hempstead, Nassau County, Long Island, New York: Long Island Water Resources Bulletin 12, 87 p.
- Kilburn, Chabot, and Krulikas, R. K., Hydrogeology and ground-water quality of the northern part of the Town of Oyster Bay, Nassau County, New York, in 1980: U.S. Geological Survey Water-Resources Investigations Report 85-4051 (in press).

POTENTIOMETRIC SURFACE OF THE LLOYD AQUIFER, LONG ISLAND, NEW YORK, JANUARY 1983

WATER-RESOURCES INVESTIGATIONS REPORT 85-4:
PLATE 4A--LLOYD AQUIFER--WE



OBSERVATION WELL AND NUMBER--Prefixes K, Q, N and S for Kings, Queens, Nassau, and Suffolk Counties, respectively, are omitted. Lower number is potentiometric-surface altitude in feet above or below (-) NGVD of 1929. (PW) indicates Port Washington aquifer. (L) indicates Lloyd aquifer

—10— LINE OF EQUAL POTENTIOMETRIC-SURFACE ALTITUDE--Shows altitude at which water level would have stood in tightly-cased wells. Solid where approximately known; dashed where inferred. Contour interval 5 feet. Hachures indicate depression

INFERRED NORTHERN LIMIT OF LLOYD AQUIFER

REFERENCE NO. 14

Friday
December 14, 1990

Test Report

Part II

Environmental Protection Agency

40 CFR Part 300

Hazard Ranking System; Final Rule

TABLE 3-6.—HYDRAULIC CONDUCTIVITY OF GEOLOGIC MATERIALS

| Type of material | Assigned hydraulic conductivity (cm/sec) |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|
| Clay; low permeability till (compact unfractured till); shale; unfractured metamorphic and igneous rocks | 10^{-8} ²⁻² |
| Silt; loesses; silty clays; sediments that are predominantly silts; moderately permeable till (fine-grained, unconsolidated till, or compact till with some fractures); low permeability limestones and dolomites (no karst); low permeability sandstone; low permeability fractured igneous and metamorphic rocks | 10^{-6} ²⁻⁶ |
| Sands; sandy silts; sediments that are predominantly sand; highly permeable till (coarse-grained, unconsolidated or compact and highly fractured); peat; moderately permeable limestones and dolomites (no karst); moderately permeable sandstone; moderately permeable fractured igneous and metamorphic rocks | 10^{-4} ²⁻⁴ |
| Gravel; clean sand; highly permeable fractured igneous and metamorphic rocks; permeable basalt; karst limestones and dolomites | 10^{-2} ²⁻² |

* Do not round to nearest integer.

TABLE 3-7.—TRAVEL TIME FACTOR VALUES *

| Hydraulic conductivity (cm/sec) | Thickness of lowest hydraulic conductivity layer(s) ^a (feet) | | | |
|------------------------------------|-------------------------------------------------------------------------|-----------------------|-------------------------|------------------|
| | Greater than 3 to 5 | Greater than 5 to 100 | Greater than 100 to 500 | Greater than 500 |
| Greater than or equal to 10^{-3} | 35 | 35 | 35 | 25 |
| Less than 10^{-3} to 10^{-6} | 35 | 25 | 15 | 15 |
| Less than 10^{-6} to 10^{-7} | 15 | 15 | 5 | 5 |
| Less than 10^{-7} | 5 | 5 | 1 | 1 |

35. * If depth to aquifer is 10 feet or less or if, for the interval being evaluated, all layers that underlie a portion of the sources at the site are karst, assign a value of

^b Consider only layers at least 3 feet thick. Do not consider layers or portions of layers within the first 10 feet of the depth to the aquifer.

Determine travel time only at locations within 2 miles of the sources at the site, except: if observed ground water contamination attributable to sources at the site extends more than 2 miles beyond these sources, use any location within the limits of this observed ground water contamination when evaluating the travel time factor for any aquifer that does not have an observed

likelihood of release factor category value for that aquifer. Otherwise, assign the potential to release factor value for that aquifer as the likelihood of release value. Enter the value assigned in Table 3-1.

3.2 *Waste characteristics.* Evaluate the waste characteristics factor category for an aquifer based on two factors: toxicity/mobility and hazardous waste quantity.

3.2.1.1 *Toxicity.* Assign a toxicity factor value to each hazardous substance as specified in Section 2.4.1.1.

3.2.1.2 *Mobility.* Assign a mobility factor value to each hazardous substance for the aquifer being evaluated as follows:

• For any hazardous substance that meets the criteria for an observed

REFERENCE NO. 15

NATIONAL WETLANDS INVENTORY
UNITED STATES DEPARTMENT OF THE INTERIOR

APPROXIMATE 15 MILE SURFACE WATER MIGRATION PATHWAY LIMIT

SYMBOLS

Legend:

- Wetland Codes:** E1W1, E1W2, E1W3, E1W4, E1W5, E1W6, E1W7, E1W8, E1W9, E1W10, E1W11, E1W12, E1W13, E1W14, E1W15, E1W16, E1W17, E1W18, E1W19, E1W20, E1W21, E1W22, E1W23, E1W24, E1W25, E1W26, E1W27, E1W28, E1W29, E1W30, E1W31, E1W32, E1W33, E1W34, E1W35, E1W36, E1W37, E1W38, E1W39, E1W40, E1W41, E1W42, E1W43, E1W44, E1W45, E1W46, E1W47, E1W48, E1W49, E1W50, E1W51, E1W52, E1W53, E1W54, E1W55, E1W56, E1W57, E1W58, E1W59, E1W60, E1W61, E1W62, E1W63, E1W64, E1W65, E1W66, E1W67, E1W68, E1W69, E1W70, E1W71, E1W72, E1W73, E1W74, E1W75, E1W76, E1W77, E1W78, E1W79, E1W80, E1W81, E1W82, E1W83, E1W84, E1W85, E1W86, E1W87, E1W88, E1W89, E1W90, E1W91, E1W92, E1W93, E1W94, E1W95, E1W96, E1W97, E1W98, E1W99, E1W100.
- Wetland Types:** FARMED WETLANDS, CONTROLLED WATER REGIME, SURCLASS WATER REGIME.
- Other Symbols:** PL or PK (FAIRMED WETLANDS), E1W1 (CONTROLLED WATER REGIME), E1W2 (SURCLASS WATER REGIME).

SPECIAL NOTE: This document was prepared primarily by stereoscopic analysis of high altitude aerial photographs. Wetlands were identified on the photographs based on vegetation, visible hydrology, and topography in accordance with the National Wetlands Inventory (NWI) Manual, Version 1.0, dated 1977. The aerial photographs typically reflect conditions during the specific year and season when they were taken. In addition, there is a margin of error inherent in the use of the aerial photographs. Thus, a detailed on the ground and the wetland boundaries established through photographic interpretation. In addition, some small wetlands and those obscured by dense forest cover may not be included on this document.

FEDERAL, STATE AND LOCAL REGULATORY AGENCIES WITH JURISDICTION OVER WETLANDS MAY DEFINE AND DESCRIBE WETLANDS IN A DIFFERENT MANNER THAN THAT USED IN THIS INVENTORY. THERE IS NO ATTEMPT, IN EITHER THE DESIGN OR PRODUCTS OF THIS INVENTORY, TO DEFINE THE LIMITS OF PROPRIETARY JURISDICTION OF ANY FEDERAL, STATE OR LOCAL GOVERNMENT OR TO ESTABLISH THE GEOGRAPHICAL SCOPE OF THE REGULATORY PROGRAMS OF GOVERNMENT AGENCIES. PERSONS INTERESTED IN PROPOSING ACTIVITIES IN WETLANDS SHOULD CONSULT WITH THE APPROPRIATE FEDERAL, STATE OR LOCAL AGENCIES CONCERNING SPECIFIC AGENCY REGULATORY PROGRAMS AND PROPRIETARY JURISDICTIONS THAT MAY AFFECT SUCH ACTIVITIES.

U - Primarily represents upland areas, but may include unclassified wetlands such as man-modified areas, non photo-identifiable areas and/or unintentional omissions.

REFERENCE NO. 16



PROJECT NOTE


TO: Commercial Envelope Mfg. Co., Inc. fileDATE: 24 June 1994FROM: D.D. MiosavageW.O. NO.: 04200-022-081-0001a-02SUBJECT: Surface water pathway information.

Sampawans Creek has been designated as a Class C fresh surface water body from Montauk Highway to the source by the NYSDEC, for fish propagation and survival. The NYSDEC has designated Sampawans Creek from Montauk Highway to its mouth as a Class I saline surface water body also for fish propagation and survival. The NYSDEC has designated Great South Bay and portions of the Atlantic Ocean as Class SA saline surface waters (again) for fish propagation and survival. Class SA waters are used for commercial shellfishing [See Attachment A]

The average discharge (flow) rate Sampawans Creek, measured 0.6 miles upstream from the mouth is 9.63 cubic feet per second [See Attachment B]


Sampawans Creek becomes brackish below Route 27. Residents fish from the fresh water portion of the creek; species include bass, bluegill and pumpkinseed. Sampawans Creek may be stocked with trout [See Attachment C]

Great South Bay and the Atlantic Ocean are commercial fisheries. Fire Island Inlet and South Oyster Bay are recreational fisheries. Species present in these waters include summer and winter flounders, fluke, squid and scallop. [Attachment D]



WATER QUALITY REGULATIONS
SURFACE WATER AND GROUNDWATER
CLASSIFICATIONS AND STANDARDS

New York State
Codes, Rules and Regulations
Title 6, Chapter X
Parts 700-705



New York State Department of Environmental Conservation

PART 701

CLASSIFICATIONS—SURFACE WATERS AND GROUNDWATERS

(Statutory authority: Environmental Conservation Law, §§ 3-0301(2)[m],
15-0313, 17-0301, 17-0303, 17-0809)

| Sec. | | Sec. | |
|-------|----------------------------------------------------------|--------|-------------------------------------------|
| 701.1 | General conditions applying to all water classifications | | SALINE SURFACE WATERS |
| | FRESH SURFACE WATERS | 701.10 | Class SA saline surface waters |
| 701.2 | Class N fresh surface waters | 701.11 | Class SB saline surface waters |
| 701.3 | Class AA-Special (AA-S) fresh surface waters | 701.12 | Class SC saline surface waters |
| 701.4 | Class A-Special (A-S) fresh surface waters | 701.13 | Class I saline surface waters |
| | | 701.14 | Class SD saline surface waters |
| 701.5 | Class AA fresh surface waters | | GROUNDWATERS |
| 701.6 | Class A fresh surface waters | 701.15 | Class GA fresh groundwaters |
| 701.7 | Class B fresh surface waters | 701.16 | Class GSA saline groundwaters |
| 701.8 | Class C fresh surface waters | 701.17 | Class GSB saline groundwaters |
| 701.9 | Class D fresh surface waters | 701.18 | Assignment of groundwater classifications |
| | | 701.19 | Severability |

Historical Note

Part repealed, new filed: April 28, 1972; Feb. 25, 1974; repealed new (§§ 701.1-701.19)
filed Aug. 2, 1991 eff. 30 days after filing.

Section 701.1 General conditions applying to all water classifications. The discharge of sewage, industrial waste or other wastes shall not cause impairment of the best usages of the receiving water as specified by the water classifications at the location of discharge and at other locations that may be affected by such discharge.

Historical Note

Sec. repealed, new filed April 28, 1972; amds. filed: Nov. 5, 1984; July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

FRESH SURFACE WATERS

701.2 Class N fresh surface waters. (a) The best usages of Class N waters are the enjoyment of water in its natural condition and, where compatible, as a source of water for drinking or culinary purposes, bathing, fishing, fish propagation, and recreation.

(b) There shall be no discharge of sewage, industrial wastes, or other wastes, waste effluents or any sewage effluents not having had filtration resulting from at least 200 feet of lateral travel through unconsolidated earth. A greater distance may be required if inspection shows that, due to peculiar geologic conditions, this distance is inadequate to protect the water from pollution.

(c) These waters shall contain no deleterious substances, hydrocarbons or substances that would contribute to eutrophication, nor shall they receive surface runoff containing any such substance.

Historical Note

Sec. repealed, new filed: April 28, 1972; Feb. 25, 1974; amd. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

701.3 Class AA-Special (AA-S) fresh surface waters. (a) The best usages of Class AA-S waters are: a source of water supply for drinking, culinary or food processing purposes; primary and secondary contact recreation; and fishing. The waters shall be suitable for fish propagation and survival.

701.7 Class B fresh surface waters. The best usages of Class B waters are primary and secondary contact recreation and fishing. These waters shall be suitable for fish propagation and survival.

Historical Note

Sec. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

701.8 Class C fresh surface waters. The best usage of Class C waters is fishing. These waters shall be suitable for fish propagation and survival. The water quality shall be suitable for primary and secondary contact recreation, although other factors may limit the use for these purposes.

Historical Note

Sec. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

701.9 Class D fresh surface waters. The best usage of Class D waters is fishing. Due to such natural conditions as intermittency of flow, water conditions not conducive to propagation of game fishery, or stream bed conditions, the waters will not support fish propagation. These waters shall be suitable for fish survival. The water quality shall be suitable for primary and secondary contact recreation, although other factors may limit the use for these purposes.

Historical Note

Sec. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

SALINE SURFACE WATERS

701.10 Class SA saline surface waters. The best usages of Class SA waters are shellfishing for market purposes, primary and secondary contact recreation and fishing. These waters shall be suitable for fish propagation and survival.

Historical Note

Sec. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

701.11 Class SB saline surface waters. The best usages of Class SB waters are primary and secondary contact recreation and fishing. These waters shall be suitable for fish propagation and survival.

Historical Note

Sec. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

701.12 Class SC saline surface waters. The best usage of Class SC waters is fishing. These waters shall be suitable for fish propagation and survival. The water quality shall be suitable for primary and secondary contact recreation, although other factors may limit the use for these purposes.

Historical Note

Sec. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

701.13 Class I saline surface waters. The best usages of Class I waters are secondary contact recreation and fishing. These waters shall be suitable for fish propagation and survival.

Historical Note

Sec. filed July 3, 1985; repealed, new filed Aug. 2, 1991 eff. 30 days after filing.

PART 925**WESTERN SUFFOLK COUNTY WATERS**

(Statutory authority: Environmental Conservation Law, § 17-0301)

| Sec. | Sec. |
|--------------------------------------------------------------------|-----------------------|
| 925.1 Adopting order | 925.6 Table I |
| 925.2 Designated waters | 925.7 Map 1 |
| 925.3 Definitions and conditions | 925.8 Map 2 |
| 925.4 Special conditions | 925.9 Quadrangle maps |
| 925.5 Assigned classifications and standards of quality and purity | |

Historical Note

Part (§§ 925.1-925.9) amd. filed June 20, 1988 eff. 30 days after filing. Amended statutory authority.

Section 925.1 Adopting order. (a) Pursuant to article 12 of the Public Health Law, the Water Resources Commission, after proper study and following public hearings conducted by the commission, held on due notice, hereby adopts and assigns the following classifications and standards of quality and purity to all surface waters within the designated drainage basin of western Suffolk County as hereinafter described.

(b) This adoption and assignment of standards of quality and purity to the above designated waters shall be effective September 22, 1965.

925.2 Designated waters. The Western Suffolk County Waters drainage basin shall be deemed to include the following:

(a) All land and surface areas within Suffolk County, State of New York, lying east of the Nassau County - Suffolk County boundary line and within the topographical limit lines shown on the reproduced reference maps herein. The easterly limit line of this basin is coterminous with the westerly limit line of Great South Bay (easterly section) drainage basin.

(b) All of the Western Suffolk County Waters as defined in Table I included herein.

Historical Note

Sec. amd. filed June 20, 1988 eff. 30 days after filing.

925.3 Definitions and conditions. The several terms, words or phrases hereinafter mentioned shall be construed as follows:

(a) *Item No.* In Table I an item number is assigned consecutively to each specifically designated waters or portion thereof.

(b) *Waters index number* as appearing in Table I shall mean that number or abbreviation assigned to any designated waters or portion thereof for the purpose of identification.

(1) The numbering or index system used to identify specific waters of New York State was adapted from that used by the New York State Conservation Department in its biological survey series of reports on watersheds of the State. The primary waters of a drainage area, such as a river, large lake, bay or sound, is usually referred to by name or an abbreviation. Tributaries of primary river waters are consecutively numbered progressing upstream from the mouth. Tributaries of primary lake, bay or sound waters are consecutively numbered in clockwise order from a defined point, usually the outlet of the primary waters. Subtributaries are numbered as encountered along the tributary proceeding from its mouth to the source, and in like manner all of its other stream courses are so numbered. Ponds and lakes are numbered in the order they are encountered within the system. Tributaries of such lakes and ponds are

925.6 Table I.

TABLE I

CLASSIFICATIONS AND STANDARDS OF QUALITY AND PURITY ASSIGNED TO FRESH SURFACE WATERS AND
TIDAL SALT WATERS OF WESTERN SUFFOLK COUNTY, NEW YORK

| <i>Item No.</i> | <i>Waters Index Number</i> | <i>Name</i> | <i>Description</i> | <i>Map Ref. No.</i> | <i>Class</i> | <i>Standards</i> |
|---------------------|------------------------------------|---------------------------------|--------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------|--------------|------------------|
| 1 | LIS | Long Island Sound | East from Nassau-Suffolk county line to a line running north from Miller Place Beach and north to the New York-Connecticut boundary. | R-26nw R-26ne R-27nw R-27ne | SA | SA |
| 2 | CSH | Cold Spring Harbor | Within Suffolk County including Inner Harbor. | R-26nw | SA | SA |
| 3 | CSH-50 portion | Trib. of Cold Spring Harbor | Mouth to trib. 1a within Suffolk County. | R-26sw | C | C(T) |
| 4 | CSH-50 portion | Trib. of Cold Spring Harbor | From trib. 1a to source. | R-26sw | C | C |
| 5 | CSH-50-P158, P 159 | Subtribs. of Cold Spring Harbor | Within Suffolk County. | R-26sw | C | C(T) |
| 6 | CSH-P 200 | Trib. of Cold Spring Harbor | | R-26sw | C | C |
| 7 | CSH-51 | Trib. of Cold Spring Harbor | Tidal portion. | R-26nw | I | I |

TABLE I (cont'd)

| Item No. | Waters Index Number | Name | Description | Map Ref. No. | Class | Standards |
|----------|---------------------|-----------------------------|---------------------------------------------------------------------------------------------------------------|--------------------------------------|-------|-----------|
| 76 | LIS-PJH-CB-P 340a | Trib. of Conscience Bay | | R-27ne | C | C |
| 77 | LIS-P 343 | Unnamed pond | | R-27ne | C | C |
| 78 | LIS-P 346, P 349 | Unnamed ponds | | R-27ne | C | C |
| 79 | LIS-MSH | Mount Sinai Harbor | | R-27ne | SA | SA |
| 80 | LIS-MSH-87a | Trib. of Mount Sinai Harbor | | R-27ne | C | C |
| 81 | AO | Atlantic Ocean | To three miles out, Nassau county line east to line running south of Blue Point and Water Island. | S-26sw S-26nw S-27nw S-27ne | SA | SA |
| 82 | GSB | Great South Bay | Excluding all adjacent creeks and canals. | S-26nw S-26ne S-27nw S-27ne | SA* | SA* |
| 83 | GSB-188a | Namkee Creek | | S-27ne | SC | SC |
| 84 | GSB-188b | Herman's Creek | | S-27ne | SC | SC |

* All undesignated tidal tribs. to Interstate Sanitation Commission Class A waters within Interstate Sanitation District are classified "I."
All undesignated tidal tribs. outside Interstate Sanitation District are classified "SD."

TABLE I (cont'd)

| <i>Item No.</i> | <i>Waters Index Number</i> | <i>Name</i> | <i>Description</i> | <i>Map Ref. No.</i> | <i>Class</i> | <i>Standards</i> |
|---------------------|-----------------------------------------------------|------------------------------|---------------------------------|-----------------------------|--------------|------------------|
| 139 | GSB-203 portion | Thompsons Creek | From Montauk Highway to source. | S-26ne | C | C |
| 140 | GSB-204 portion | Trues Creek | From mouth to Montauk Highway. | S-26ne | I | I |
| 141 | GSB-204 portion including P 930, P 931, P 932 | Trues Creek | From Montauk Highway to source. | S-26ne | C | C |
| 142 | GSB-P 933a | Unnamed pond | | S-26ne | C | C |
| 143 | GSB-204a | Trib. of Great South Bay | | S-26ne | I | I |
| 144 | GSB-205 portion | Willets Creek | From mouth to Montauk Highway. | S-26ne | I | I |
| 145 | GSB-205 portion | Willets Creek | From Montauk Highway to source. | S-26ne | C | C |
| 146 | GSB-205-P 934 | Lake Capri | | S-26ne | C | C |
| 147 | GSB-206 | Skookwams Creek | | S-26ne | I | I |
| 148 | GSB-207 portion | Sampawams Creek | From mouth to Montauk Highway. | S-26ne | I | I |
| 149 | GSB-207 portion | Sampawams Creek | From Montauk Highway to source. | S-26ne | C | C(T) |
| 150 | GSB-207-P 936 | Trib. of Sampawams Creek | | S-26ne | C | C |
| 151 | GSB-207-P 937, P 938, P 939 | Tribs. of Sampawams Creek | | S-26ne | C | C |





Water Resources Data New York Water Year 1981

Volume 2. Long Island



U.S. GEOLOGICAL SURVEY WATER-DATA REPORT NY-81-2
Prepared in cooperation with the State of New York
and with other agencies

01308000 SAMPWAMS CREEK AT BABYLON, NY

LOCATION.--Lat 40°42'15", long 73°18'52". Suffolk County, Hydrologic Unit 02030202, on left bank at upstream side of John Street Bridge in Babylon, 180 ft (55 m) downstream from Long Island Railroad, and 0.6 mi (1.0 km) upstream from mouth. Water-quality sampling site at discharge station.

DRAINAGE AREA.--About 23 mi² (60 km²).

WATER-DISCHARGE RECORDS

PERIOD OF RECORD.--October 1944 to current year (monthly means estimated December 1966 to November 1967).

REVISED RECORDS.--WSP 1141: Drainage area: WSP 1702: 1955(M), 1956(M). WRD NY 1974: 1970(P).

GAGE.--Water-stage recorder and concrete control. Datum of gage is 6.36 ft (1.939 m) National Geodetic Vertical Datum of 1929. October 1944 to December 1966, water-stage recorder at site 100 ft (30 m) east at datum 0.34 ft (0.104 m) higher.

REMARKS.--Records good except those for November, January, February, and July to September, which are fair. Flow regulated slightly by pumping operations at railroad and occasionally by ponds above station. Indeterminate effect caused by ground-water pumpage for water-supply purposes at Smith Street substation 0.2 mi (0.3 km) northwest of gage. Prior to November 1950, slight diurnal fluctuation caused by power operations.

AVERAGE DISCHARGE.--37 years, 9.63 ft³/s (0.273 m³/s).

EXTREMES FOR PERIOD OF RECORD.--Maximum discharge, 136 ft³/s (3.85 m³/s) Sept. 12, 1960, gage height, 2.11 ft (0.643 m) datum then in use; maximum gage height, 3.28 ft (1.000 m) Feb. 7, 1971; minimum discharge, 1.6 ft³/s (0.045 m³/s) June 28, 1963, gage height, 0.13 ft (0.040 m) datum then in use.

EXTREMES FOR CURRENT YEAR.--Peak discharges above base of 55 ft³/s (1.56 m³/s) and maximum (*):

| Date | Time | Discharge (ft ³ /s) (m ³ /s) | Gage height (ft) (m) | Date | Time | Discharge (ft ³ /s) (m ³ /s) | Gage height (ft) (m) |
|---------|------|-------------------------------------------------------|-------------------------|---------|------|-------------------------------------------------------|-------------------------|
| Oct. 25 | 1230 | 63 1.78 | 1.41 0.43 | June 25 | 2100 | 70 1.98 | 1.56 0.48 |
| Nov. 28 | 1130 | 85 2.41 | 1.97 .60 | Sept. 1 | 1015 | a*113 3.20 | *2.53 .77 |

a From rating extended above 80 ft³/s (2.27 m³/s).

Minimum discharge, 3.5 ft³/s (0.099 m³/s) Nov. 22, 23, minimum gage height, 0.22 ft (0.067 m) Oct. 22-24.

DISCHARGE, IN CUMIC FEET PER SECOND, WATER YEAR OCTOBER 1980 TO SEPTEMBER 1981
MEAN VALUES

| DAY | OCT | NOV | DEC | JAN | FEB | MAR | APR | MAY | JUN | JUL | AUG | SEP |
|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 1 | 5.8 | 5.1 | 6.5 | 5.8 | 4.2 | 7.9 | 6.8 | 7.9 | 5.8 | 5.8 | 4.5 | 4.7 |
| 2 | 5.2 | 4.8 | 7.2 | 6.1 | 10 | 7.6 | 9.4 | 8.8 | 6.9 | 5.5 | 4.8 | 8.3 |
| 3 | 8.3 | 4.9 | 8.3 | 5.5 | 5.2 | 7.6 | 6.8 | 7.9 | 6.1 | 6.1 | 4.5 | 6.8 |
| 4 | 10 | 6.9 | 6.9 | 5.5 | 4.8 | 7.6 | 6.8 | 7.6 | 6.1 | 17 | 4.5 | 6.5 |
| 5 | 5.9 | 6.0 | 6.8 | 5.2 | 4.5 | 7.9 | 10 | 7.6 | 5.8 | 8.3 | 4.5 | 6.1 |
| 6 | 5.9 | 5.3 | 6.5 | 5.8 | 4.5 | 7.9 | 15 | 7.5 | 6.1 | 6.5 | 4.5 | 6.8 |
| 7 | 5.7 | 5.5 | 6.7 | 6.5 | 4.5 | 7.6 | 9.1 | 7.0 | 5.5 | 6.1 | 4.2 | 6.1 |
| 8 | 5.8 | 5.2 | 7.2 | 4.8 | 14 | 7.6 | 9.1 | 6.9 | 5.5 | 6.1 | 4.8 | 6.5 |
| 9 | 5.4 | 6.1 | 7.6 | 4.8 | 5.5 | 7.6 | 8.7 | 7.3 | 5.8 | 5.8 | 5.7 | 7.2 |
| 10 | 4.8 | 5.8 | 7.6 | 4.8 | 4.5 | 7.6 | 8.7 | 7.3 | 5.5 | 5.8 | 4.7 | 6.1 |
| 11 | 6.1 | 5.2 | 6.9 | 4.8 | 6.8 | 7.9 | 8.7 | 7.6 | 5.2 | 5.8 | 4.2 | 6.1 |
| 12 | 5.5 | 4.8 | 6.9 | 4.8 | 5.8 | 7.6 | 8.7 | 7.6 | 5.2 | 5.8 | 4.2 | 6.1 |
| 13 | 5.2 | 4.8 | 7.0 | 4.8 | 6.1 | 7.6 | 7.9 | 7.6 | 4.8 | 6.1 | 4.2 | 5.8 |
| 14 | 4.8 | 4.5 | 6.6 | 5.2 | 5.8 | 7.2 | 12 | 7.2 | 5.2 | 5.8 | 4.2 | 5.8 |
| 15 | 4.8 | 4.2 | 6.4 | 5.2 | 5.8 | 7.2 | 9.0 | 7.2 | 5.5 | 5.8 | 4.5 | 18 |
| 16 | 4.8 | 4.2 | 6.8 | 4.8 | 5.8 | 7.6 | 8.7 | 7.9 | 5.2 | 5.8 | 5.2 | 22 |
| 17 | 4.8 | 4.2 | 6.5 | 5.2 | 5.8 | 7.2 | 8.7 | 6.8 | 4.8 | 5.8 | 4.5 | 8.3 |
| 18 | 5.8 | 7.9 | 6.5 | 5.2 | 5.5 | 6.5 | 8.5 | 6.7 | 4.8 | 5.8 | 4.2 | 7.9 |
| 19 | 5.8 | 3.8 | 6.1 | 5.2 | 5.8 | 6.8 | 8.0 | 6.6 | 4.8 | 5.8 | 4.5 | 9.4 |
| 20 | 4.5 | 4.2 | 5.8 | 4.8 | 17 | 6.5 | 8.1 | 6.6 | 9.8 | 8.3 | 4.5 | 7.6 |
| 21 | 4.5 | 4.2 | 5.8 | 4.8 | 7.9 | 6.5 | 7.6 | 6.5 | 5.8 | 11 | 4.8 | 7.2 |
| 22 | 4.4 | 3.8 | 5.8 | 5.2 | 7.2 | 6.1 | 7.6 | 6.4 | 5.8 | 7.6 | 4.5 | 7.6 |
| 23 | 4.2 | 3.8 | 7.6 | 5.2 | 7.2 | 6.5 | 8.3 | 6.3 | 5.2 | 5.8 | 4.5 | 7.6 |
| 24 | 4.5 | 7.6 | 7.6 | 5.2 | 12 | 6.5 | 11 | 6.1 | 4.8 | 5.8 | 4.5 | 6.8 |
| 25 | 18 | 11 | 5.8 | 5.2 | 7.6 | 6.1 | 8.2 | 6.2 | 21 | 5.5 | 4.5 | 6.5 |
| 26 | 5.8 | 4.2 | 5.5 | 5.2 | 9.1 | 6.1 | 7.9 | 6.1 | 9.4 | 5.5 | 4.5 | 6.5 |
| 27 | 5.1 | 4.5 | 5.5 | 5.5 | 7.6 | 6.8 | 7.9 | 6.1 | 6.1 | 5.5 | 4.8 | 6.5 |
| 28 | 5.6 | 25 | 5.5 | 4.8 | 8.7 | 6.1 | 7.9 | 6.1 | 5.8 | 4.8 | 5.8 | 8.7 |
| 29 | 5.0 | 6.1 | 5.8 | 4.5 | --- | 6.5 | 9.0 | 7.7 | 5.8 | 9.4 | 4.8 | 6.1 |
| 30 | 5.0 | 6.1 | 5.8 | 4.5 | --- | 8.7 | 8.0 | 6.2 | 5.5 | 4.8 | 5.2 | 6.1 |
| 31 | 5.3 | --- | 5.5 | 4.2 | --- | 6.8 | --- | 6.4 | --- | 4.5 | 9.8 | --- |
| TOTAL | 182.3 | 179.7 | 203.0 | 159.1 | 199.2 | 221.7 | 262.1 | 217.7 | 189.6 | 204.0 | 147.6 | 274.0 |
| MEAN | 5.88 | 5.99 | 6.55 | 5.13 | 7.11 | 7.15 | 8.74 | 7.02 | 6.32 | 6.58 | 4.76 | 9.13 |
| MAX | 18 | 25 | 8.3 | 6.5 | 17 | 8.7 | 15 | 8.8 | 21 | 17 | 9.8 | 47 |
| MIN | 4.2 | 3.8 | 5.5 | 4.2 | 4.2 | 6.1 | 6.8 | 6.1 | 4.8 | 4.5 | 4.2 | 5.8 |

CAL YR 1980 TOTAL 3637.4 MEAN 9.94 MAX 51 MIN 3.8
WTR YR 1981 TOTAL 2440.0 MEAN 6.68 MAX 47 MIN 3.8

STREAMS ON LONG ISLAND

01308000 SAMPANAMS CREEK AT BABYLON, NY--Continued

WATER-QUALITY RECORDS

PERIOD OF RECORD.--May 1966 to current year.

COOPERATION.--All water-quality samples were collected and analyzed by Suffolk County Department of Health Services.

WATER QUALITY DATA, WATER YEAR OCTOBER 1980 TO SEPTEMBER 1981

| DATE | TIME | STREAM- FLOW, INSTAN- TANEOUS (CFS) | SPE- CIFIC CON- DUCT- ANCE (UMHOS) | PH (UNITS) | TEMPER- ATURE (DEG C) | OXYGEN, DIS- SOLVED (MG/L) | MAGNE- SIUM, DIS- SOLVED (MG/L AS MG) | SODIUM, DIS- SOLVED (MG/L AS NA) | POTAS- SIUM, DIS- SOLVED (MG/L AS K) |
|--------------|------|-------------------------------------------------|---------------------------------------------------|---------------|-----------------------------|-------------------------------------|------------------------------------------------------|----------------------------------------------|-----------------------------------------------------|
| DEC 02... | 1450 | 7.2 | 210 | 6.2 | 11.0 | 5.8 | 3.2 | 23 | 3.9 |
| MAR 16... | 1120 | 7.6 | 225 | 6.6 | 9.0 | 8.7 | 3.3 | 26 | 4.5 |
| SEP 15... | 1000 | 6.5 | 220 | 6.3 | 17.0 | 4.7 | 3.5 | 26 | 3.9 |

| DATE | ALKA- LINITY FIELD (MG/L AS CAC03) | SULFATE DIS- SOLVED (MG/L AS SO4) | CHLO- RIDE, DIS- SOLVED (MG/L AS CL) | FLUO- RIDE, DIS- SOLVED (MG/L AS F) | NITRO- GEN, NITRATE TOTAL (MG/L AS N) | NITRO- GEN, NITRATE DIS- SOLVED (MG/L AS N) | NITRO- GEN, NITRITE TOTAL (MG/L AS N) | NITRO- GEN, NITRITE DIS- SOLVED (MG/L AS N) | NITRO- GEN, AMMONIA TOTAL (MG/L AS N) |
|--------------|---------------------------------------------------|-----------------------------------------------|-----------------------------------------------------|----------------------------------------------------|------------------------------------------------------|---------------------------------------------------------------|------------------------------------------------------|---------------------------------------------------------------|------------------------------------------------------|
| DEC 02... | 32 | 26 | 27 | -- | 2.6 | 2.60 | .020 | .021 | 2.00 |
| MAR 16... | 35 | 26 | 32 | < .5 | 2.7 | 2.70 | .014 | .014 | 2.60 |
| SEP 15... | 26 | 26 | 31 | < .5 | 4.0 | 4.00 | .104 | .101 | .940 |

| DATE | NITRO- GEN, AMMONIA DIS- SOLVED (MG/L AS N) | NITRO- GEN, AM- MONIA + ORGANIC TOTAL (MG/L AS N) | NITRO- GEN, AM- MONIA + ORGANIC DIS- SOLVED (MG/L AS N) | PHOS- PHORUS, DIS- SOLVED (MG/L AS P) | PHOS- PHORUS, ORTHO, DIS- SOLVED (MG/L AS P) | IRON, TOTAL RECOV- ERABLE (UG/L AS FE) | IRON, DIS- SOLVED (UG/L AS FE) | MANGA- NESE, TOTAL RECOV- ERABLE (UG/L AS MN) | METHY- LENE BLUE ACTIVE SUB- STANCE (MG/L) |
|--------------|---------------------------------------------------------------|---------------------------------------------------------------------|------------------------------------------------------------------------------|------------------------------------------------------|----------------------------------------------------------------|-------------------------------------------------------|--------------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------------|
| DEC 02... | 2.00 | 2.20 | 2.3 | .004 | .006 | 1250 | 1000 | 1300 | .08 |
| MAR 16... | 2.60 | 4.10 | 3.8 | .010 | .003 | 1600 | 1300 | 1600 | .09 |
| SEP 15... | .910 | 1.00 | 1.2 | .008 | .003 | 450 | 340 | 900 | .05 |

Discharge measurements made at low-flow partial-record stations during water year 1981--Continued

| Station No. | Station name | Location | Drainage area (mi ²) | Period of record | Date | Measurements |
|------------------------|-------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------|------------------------|----------|-----------------------------------|
| | | | | | | Discharge (ft ³ /s) |
| Streams on Long Island | | | | | | |
| 01307100 | Champlin Creek at Montauk Highway, at Islip, N.Y. | Lat 40°43'50", long 73°12'12", Suffolk County, at Montauk Highway, at Islip, and 0.45 mi (0.72 km) downstream from gaging station at Islip. | -- | 1963 | 11-17-80 | 3.6 |
| | | | | 1967 | 3-10-81 | 4.3 |
| | | | | 1973 | 6-9-81 | 5.2 |
| | | | | 1975-81 | 8-27-81 | 1.5 |
| 01307300 | Pardees Ponds Outlet at Islip, N.Y. | Lat 40°43'40", long 73°13'16", Suffolk County, at culvert on State Highway 27A, at Islip. | -- | 1948-72 | 11-3-80 | 4.1 |
| | | | | 1974-81 | 6-11-81 | 2.8 |
| | | | | | 8-28-81 | 2.5 |
| 01307400 | Awixa Creek at Islip, N.Y. | Lat 40°43'39", long 73°13'51", Suffolk County, at culvert on State Highway 27A, 0.75 mi (1.21 km) west of Islip. | -- | 1948-81 | 11-24-80 | .50 |
| | | | | | 3-13-81 | 1.3 |
| | | | | | 8-27-81 | .98 |
| 01307500 ^{c/} | Penataquit Creek at Bay Shore, N.Y. | Lat 40°43'37", long 73°14'41", Suffolk County, at Union Avenue, at Bayshore. | -- | 1945-76† | 10-6-80 | 4.3 |
| | | | | 1977-81 | 11-5-80 | 3.2 |
| | | | | | 12-3-80 | 5.2 |
| | | | | | 1-8-81 | 3.4 |
| | | | | | 2-5-81 | 2.5 |
| | | | | | 3-10-81 | 5.1 |
| | | | | | 4-10-81 | 5.4 |
| | | | | | 5-11-81 | 6.2 |
| | | | | | 6-9-81 | 5.1 |
| | 9-11-81 | 6.7 | | | | |
| 01307600 | Cascade Lakes Outlet at Brightwaters, N.Y. | Lat 40°42'40", long 73°15'38", Suffolk County, at culvert on Montauk Highway, at Brightwaters. | -- | 1958-81 | 11-3-80 | .84 |
| | | | | | 3-13-81 | 2.6 |
| | | | | | 6-11-81 | 1.0 |
| | | | | | 8-27-81 | .15 |
| 01307920 | <u>Sampawams Creek</u> <u>near Deer Park,</u> <u>N.Y.</u> | Lat 40°44'27", long 73°18'24", Suffolk County, 30 ft (9 m) downstream from Bay Shore Road, and 2.5 mi (4.0 km) upstream from gaging station at Babylon. | -- | 1965-66 | 5-28-81 | 1.1 |
| 1973-81 | 8-28-81 | | | .36 | | |
| 01307950 | <u>Sampawams Creek</u> <u>near North</u> <u>Babylon, N.Y.</u> | Lat 40°43'37", long 73°18'46", Suffolk County, 120 ft (37 m) downstream from Hunter Avenue, and 1.6 mi (2.6 km) upstream from gaging station at Babylon. | -- | 1967 | 5-28-81 | 1.2 |
| | | | | 1971-81 | 8-28-81 | .90 |
| 01308200 | <u>Sampawams Creek</u> <u>below Hawleys</u> <u>Lake, at</u> <u>Babylon, N.Y.</u> | Lat 40°41'48", long 73°19'04", Suffolk County at pond out- let, 200 ft (61 m) upstream from State Highway 27A, at Babylon, and 0.5 mi (0.8 km) downstream from gaging station at Babylon. | -- | 1953-67 | 11-4-80 | 4.5 |
| | | | | 1969-81 | 5-28-81 | 5.8 |
| | | | | | 8-28-81 | 4.2 |
| 01308600 | Carlls River at Park Avenue, Babylon, N.Y. | Lat 40°42'06", long 73°19'43", Suffolk County, at culvert on Park Avenue, at Babylon, and 0.5 mi (0.8 km) downstream from gaging station at Babylon. | -- | 1968-81 | 11-4-80 | 22 |
| | | | | | 6-11-81 | 16 |
| | | | | | 8-27-81 | 20 |
| 01309000 ^{c/} | Santapogue Creek at Lindenhurst, N.Y. | Lat 40°41'30", long 73°21'20", Suffolk County, at culvert on East Hoffman Avenue, 1 mi (2 km) east of Long Island Railroad station at Lindenhurst. | -- | 1947-69† | 10-6-80 | .28 |
| | | | | 1970-81 | 11-3-80 | .40 |
| | | | | | 12-1-80 | 2.3 |
| | | | | | 1-8-81 | 1.5 |
| | | | | | 2-5-81 | 1.1 |
| | | | | | 3-10-81 | 3.0 |
| | | | | | 4-10-81 | 2.4 |
| | | | | | 5-11-81 | 2.3 |
| | | | | | 8-27-81 | .26 |
| | 9-11-81 | 1.1 | | | | |
| 01309100 | Santapogue Creek at State Highway 27A, Lindenhurst, N.Y. | Lat 40°41'02", long 73°21'06", Suffolk County, at culvert on State Highway 27A, 0.5 mi (0.8 km) downstream from gaging station at Lindenhurst. | -- | 1953-69 | 11-3-80 | 4.8 |
| | | | | 1971-81 | 3-10-81 | 9.0 |
| | | | | | 8-27-81 | 6.0 |

† Operated as a continuous-record gaging station.
^{c/} Water-quality data included in this report.

PHONE CONVERSATION RECORD

Conversation with:

Name Gregory Kozlowski

Date 6 / 17 / 94

Company NYSDEC - STONY Brook - Fisheries

Time 11:45 AM/PM

Address _____

☒ Originator Placed Call

☐ Originator Received Call

Phone (516) 444-0280

W.O. NO. 04200-022-081-0006

Subject Fishery Information for the surface water pathway of the Commercial Envelopes site.

Notes: Greg Kozlowski (GK) stated that he would only be able to provide information on the freshwater portion of the surface water migration pathway, which is the upper portion of Sampawams Creek. GK said that a few years ago the headwaters of Sampawams Creek were stocked with brook trout, but he is not sure whether this practice is continued today. He said that Hawley's Lake, which is between Route 27 and Union Ave (North of Rte 27), contains bass, blue gill and pumpkin seed communities. He stated that local residents fish in the creek. GK said that south of Hawley's Lake the creek becomes brackish. He gave me the phone number for the NYSDEC Marine Division to provide me with information concerning the brackish waters along the surface water pathway. The number is 516-444-0280.

☐ File _____

Follow-Up-Action: _____

☐ Tickle File _____/_____/_____

☐ Follow-Up By: _____

☐ Copy/Route To: _____

Originator's Initials JF

John Fix

Originator

PHONE CONVERSATION RECORD

Conversation with:

Name Sherry Aicher

Company NYSDEC - Region I - Fisheries

Address _____

Phone 516-444-0280

Subject Fishery information for Great South Bay, Fire Island Inlet, South Oyster Bay and the Atlantic Ocean

Date 6 / 20 / 94

Time 2:30 AM/PM (PM)

☐ Originator Placed Call

☒ Originator Received Call

W.O. NO. 04200-02-081-0006

Notes: Sherry Aicher (SA) told me that both the Great South Bay and the Atlantic Ocean are used to supply commercial fisheries. SA stated that Fire Island Inlet and South Oyster Bay are used as recreational fisheries. She said that some of the species present in these waters are summer and winter flounder, fluke, squid and scallop.

☐ File _____

☐ Tickle File _____ / _____ / _____

☐ Follow-Up By: _____

☐ Copy/Route To: _____

Follow-Up-Action: _____

Originator's Initials JF

REFERENCE NO. 17

FROST ASSOCIATES

P.O. Box 495, Essex, Connecticut 06426
(203) 767-7644 Fax (203) 767-7069

Apr 22, 1994

To: Jan Holderness
Roy F. Weston Inc
4th Floor Raritan Plaza
Edison, New Jersey 08837-3616

Fr: Bob Frost
Frost Associates
P.O. Box 495
Essex, Conn 06426

Tel: (203) 767-1254
Fax: (203) 767-7069

Sub: Commercial Envelope Mfg Co
Deer Park, Suffolk Cty, NY

CERCLIS: NYD981184138

Job: 04200-022-081-0006-02

Site Longitude: 73-18-14 73.303886
Site Latitude : 40-45-38 40.760559

The CENTRACTS report below identifies the population, households, and private water wells of each Block Group that lies within, or partially within, the 4, 3, 2, 1, .5, and .25, mile "rings" of the latitude and longitude coordinates above. CENTRACTS may have up to ten radii of any length. 1000 block groups, and 15000 block group sides.

CENTRACTS uses the 1990 Block Group population and Block Group house count data found in the Census Bureau's 1990 STF-1A files. The sources of water supply data are from the Bureau's 1990 STF-3A files. The boundary line coordinates of the Block Groups were extracted from the Census Bureau's 1990 TIGER/Line Files.

CENTRACTS reports are created with programs written by Frost Associates, P.O. Box 495, Essex, Conn. The code was written using Microsoft's Quick-Basic Ver. 4.5.

Latitude and Longitude coordinates identifying a site are entered in degrees and decimal degrees. One or more county files holding Block Group boundary lines are selected for use by CENTRACTS by determining whether the site coordinates fall within the minimum and maximum Lat/Lon coordinates of each county in the state.

Each Block Group line segment has Lat/Lon coordinates representing the "From" and "To" ends of that line. All coordinates from the selected county files are read and converted from degrees, decimal degrees to X/Y miles from the site location. Each line segment is then examined whether it lies within or partially within the maximum ring from the site.

The unique Block Group ID numbers of each line segment that lie within the maximum ring are retained. All Block Group boundary lines matching the Block Group numbers are then extracted from the respective county files to obtain all sides of the included Block Groups. Boundary records are then sorted in adjacent side order to determine the shape and area of each Block Group polygon.

A method to solve for the area of a polygon is to take one-half the sum of the pro

ducts obtained by multiplying each X-coordinate by the difference between the adjacent Y-coordinates. For a polygon with coordinates at adjacent angles A, B, C, D, and E. The formula can be expressed:

$$\text{Area} = 1/2\{X_a(Y_e - Y_b) + X_b(Y_a - Y_c) + X_c(Y_b - Y_d) + X_d(Y_c - Y_e) + X_e(Y_d - Y_a)\}$$

For each ring, the selected Block Groups will be inside, outside, or intersected by the ring. When a polygon is intersected, the partial Block Group area within that ring is calculated using the method described below.

When a ring intersects a Block Group, the intersect points are solved and plotted at the points where the ring enters and exits the shape. The chord line, a line within the circle connecting the intersect points is determined. This chord line is used to calculate the segment area, the half moon shape between the chord line and the ring, and the sub-polygon created by the chord line and the Block Group boundaries that lie outside the ring.

The segment area is subtracted from the sub-polygon area to determine the area of the sub-polygon outside the ring. The area outside the ring is then subtracted from the area of the entire polygon to arrive at the inside area. This inside area is then divided by the tract's total area to determine the percentage of area within the ring. This process is repeated for each block group that is intersected by one of the rings. The total area, partial area, and percentage of partial area of those block groups within, or partially within a ring, are held in memory for the report.

On occasion, the algorithm described above is unable to determine the area of the partial area. Within the report program is a "Paint" routine which allows an enclosed shape to be highlighted. Another routine calculates the percentage of highlighted screen pixels to the pixels within the polygon. A manual entry is allowed. Both the "Paint" method and manual entry method override the calculated method.

CENTRACTS lists, starting on page 4, all Block Groups in State, County, Census Tract, and Block Group ID order that lie within, or partially within, the maximum ring. Each Block Group is identified by a City or Town name and by the Block Group's State, County, Tract and Block Group ID number. Following is the Block Group's 1990 population and house count extracted from the Census Bureau's 1990 STF-1A files.

The next four columns display water source data from the 1990 STF-3A files. The first column is "Units with Public system or private company source of water", followed by "Units with individual well, Drilled, source of water"; "Units with individual well, Dug, source of water" and "Units with Other source of water".

For each ring, CENTRACTS then shows the Block Groups that are within that ring, the Block Group's total area in square miles, the partial area of the Block Group within that ring, and the partial percentage within the ring. The areas of the included Block Group and the partial areas are then totaled.

The last section tallies the demographic data within each ring. The percentage of area for each Block Group is multiplied times the census data for that Block Group and totaled for all Block Group's within the ring. Ring totals are then determined by subtracting the three mile data from the four mile, the two mile from the three mile, one from the two, etc... Population on private wells is calculated using the formula: $((\text{Drilled} + \text{Dug Wells}) / \text{Households}) * \text{Population}$

=====
Site Data
=====

Population: 197875.09
Households: 59834.72
Drilled Wells: 100.86
Dug Wells: 498.54
Other Water Sources: 134.02

=====
Partial (RING) data
=====

---- Within Ring: 4 Mile(s) and 3 Mile(s) ----

Population: 85990.41
Households: 26349.24
Drilled Wells: 51.98
Dug Wells: 238.31
Other Wells: 65.26

* Population On Private Wells: 947.35

---- Within Ring: 3 Mile(s) and 2 Mile(s) ----

Population: 61852.16
Households: 17610.90
Drilled Wells: 32.58
Dug Wells: 120.70
Other Wells: 20.57

* Population On Private Wells: 538.35

---- Within Ring: 2 Mile(s) and 1 Mile(s) ----

Population: 41253.31
Households: 12914.69
Drilled Wells: 8.73
Dug Wells: 74.04
Other Wells: 28.12

** Population On Private Wells: 264.40

---- Within Ring: 1 Mile(s) and .5 Mile(s) ----

Population: 7570.58
Households: 2447.79
Drilled Wells: 7.56
Dug Wells: 36.42
Other Wells: 11.66

** Population On Private Wells: 136.03

Commercial Envelope Mfg Co
Deer Park, Suffolk Cty, NY
NYD981184138

--- Within Ring: .5 Mile(s) and .25 Mile(s) ----

| | |
|----------------|--------|
| Population: | 973.56 |
| Households: | 393.48 |
| Drilled Wells: | 0.00 |
| Dug Wells: | 20.97 |
| Other Wells: | 5.78 |

* Population On Private Wells: 51.87

--- Within Ring: .25 Mile(s) and 0 Mile(s) ----

| | |
|----------------|--------|
| Population: | 235.08 |
| Households: | 118.61 |
| Drilled Wells: | 0.00 |
| Dug Wells: | 8.11 |
| Other Wells: | 2.63 |

* Population On Private Wells: 16.08

** Total Population On Private Wells: 1954.08

REFERENCE NO. 18



PROJECT NOTE

TO: Commercial Envelope Mfg Co. Inc. fileDATE: 27 June 1994FROM: DD MinsavageW.O. NO.: 04200-022-081-0006-02SUBJECT: Listed species habitats located within a 4-mile radius or 15-miles downstream of the site

The New York State Department of Environmental Conservation / National Heritage Program prepared a report identifying various sensitive environments located within the target distance limits of the site. This information is considered sensitive and not for public release; therefore, the locations of the sensitive environments were determined and are summarized, in general terms below. The original report is located in the "CONFIDENTIAL" file of the project folder.

Air Pathway: Only plant habitats identified

0-1 mile: no habitats designated as sensitive environments identified.

1-2 miles: Habitats of 1 State-listed endangered species, 1 State-listed threatened species, and 1 species under review as to its Federal status.

2-3 miles: Habitats of 1 State-listed endangered species and 1 State-listed threatened species.

3-4 miles: Habitats of 2 federal-listed endangered species, 2 State-listed endangered species, and 2 State-listed threatened species.


SURFACE WATER PATHWAY:

Habitats identified along coastal tidal waters located within 15 miles downstream from the site:

- Three State-listed endangered species (1 vertebrate and 2 plant)
- Two State-listed threatened species (1 vertebrate and 1 plant)

New York State Department of Environmental Conservation

Wildlife Resources Center - (518) 783-3932
Information Services
700 Troy-Schenectady Road
Latham, New York 12110-2400



Thomas C. Jorling
Commissioner

June 15, 1994

Richard M. Settino
Weston
Raritan Plaza 1, 4th floor,
Raritan Center
Edison, New Jersey 08837-2616

Dear Mr. Settino:

We have reviewed the New York Heritage Program files with respect to your recent request for biological information concerning your Hazardous Waste Investigation, USEPA Contract No. 68-W9-0022 covering 15 sites as listed in your letter of May 27, 1994. The enclosed printout covers the COMMERCIAL ENVELOPE SITE, as indicated on your map, located in Suffolk County, New York State.

Enclosed is a computer printout covering the area you requested to be reviewed by our staff. The information contained in this report is considered sensitive and may not be released to the public without permission from the New York Natural Heritage Program.

Our files are continually growing as new habitats and occurrences of rare species and communities are discovered. In most cases, site-specific or comprehensive surveys for plant and animal occurrences have not been conducted. For these reasons, we can only provide data which have been assembled from our files. We cannot provide a definitive statement on the presence or absence of species, habitats or natural communities. This information should not be substituted for on-site surveys that may be required for environmental assessment.

This response applies only to known occurrences of rare animals, plants and natural communities and/or significant wildlife habitats. You should contact our regional office, Division of Regulatory Affairs, at the address enclosed for information regarding any regulated areas or permits that may be required (e.g., regulated wetlands) under State Law.

If this proposed project is still active one year from now we recommend that you contact us again so that we can update this response.

Sincerely,

Nicholas B. Conrad, Info. Data Asst.
NY Natural Heritage Program

Encs.

cc: Region 1, Wildlife Mgr.
Region 1, Fisheries Mgr.